FINAL INITIAL STUDY WITH MITIGATED NEGATIVE DECLARATION



HARLAN ROAD REALIGNMENT AT ROTH ROAD PROJECT CITY OF LATHROP, CALIFORNIA

Prepared for:



City of Lathrop 390 Towne Center Drive Lathrop, CA 95330

Prepared by:

Dokken Engineering 110 Blue Ravine Road, Suite 200 Folsom, California 95630

January 2021

The Draft Initial Study with Proposed Mitigated Negative Declaration was circulated for public comment from November 25, 2020 to December 31, 2020. All comments received during the circulation period have been reviewed and addressed by the City and included within Attachment H of the final document. Any changes made to the final document as a result of public comments are notated in a track changes sidebar.

Mitigated Negative Declaration

Pursuant to: Division 13, Public Resources Code

PROJECT DESCRIPTION

The City of Lathrop (City) proposes to realign Harlan Road by shifting the intersection of Harlan Road and Roth Road within the City of Lathrop, California.

Proposed development projects within San Joaquin County, the City of Manteca, and the City of Lathrop will cause the I-5 interchange at Roth Road within the City of Lathrop to operate at an unacceptable level. The Harlan Road Realignment at Roth Road Project (Project), must be completed prior to any improvements being made to the interchange. The proposed Project will shift the existing Harlan Road/Roth Road intersection approximately 600 feet to the east, increasing the spacing between the I-5/Roth Road northbound ramp termini intersection and Harlan Road. This increased spacing will allow for future improvements at the ramp termini intersection to improve the intersection traffic operations. To match the shifted intersection, Harlan Road, north and south of Roth Road, will require realignment. Harlan Road currently runs parallel adjacent to the I-5 right of way within the Project area.

The proposed Project along Harlan Road will include three travel lanes and a center two-way left turn lane south of Roth Road and two travel lanes with a center striped median north of Roth Road. This lane configuration will incorporate the ultimate improvements necessary for Harlan Road within the Project area. Harlan Road will conform to the existing section at the beginning and end of the realigned portion; ultimate Harlan Road improvements past these conforms will take place as future projects.

The existing Harlan Road intersection will be converted to one cul-de-sac on the south side of Roth Road and a dead-end road on the north side of Roth Road to maintain access to the existing properties on Harlan Road outside of the realigned portion. Three alternatives are being considered for the road realignment north of Roth Road in the Project area. The proposed alternatives are being considered to evaluate the impacts to a private property (APN 19333031), a private residency located north of Roth Road along the existing Harlan Road. The proposed road realignment in the remainder of the Project area south of Roth Road is consistent for all alternatives. The City will select a preferred alternative based on public input and feasibility during final design.

Alternative 1

The entirety of the road alignment of Alternative 1 would pass through the northern portion of a private residential property (APN 19333031). This alternative would only require minimal permanent right of way acquisition from another private commercial property (APN 19333028) just north of APN 19333031, to accommodate curb returns. This alternative would result in the greatest impact to APN 19333031, including impacting the residential structure.

Alternative 2

The entirety of the road alignment of Alternative 2 would pass through a private commercial property (APN 19333028) on its south side. This alternative would only require minimal permanent right of way acquisition from the private residential property (APN 19333031) to accommodate curb returns. This alternative would result in the least impact to APN 19333031.

Alternative 3

The road alignment of Alternative 3 would center the roadway between the private residential property (APN 19333031) and the adjacent private commercial property (APN 19333028). This

alternative would require permanent right of way acquisition from both properties to accommodate each roadway half. This alternative would result in less impact to the private residential property (APN 19333031) than Alternative 1; however, the residential structure would still be impacted.

Common Design Features for Alternatives 1 Through 3

The ultimate typical section along Roth Road for all three alternatives is anticipated to be four travel lanes with a center lane. The intersection will be constructed to the ultimate width so as not to require disturbance to newly constructed improvements when the full Roth Road widening is completed. Beyond the intersection of Roth Road and Harlan Road, improvements to Roth Road will conform to the existing Roth Road section.

There are existing overhead electric and communication utility lines along Harlan Road/Roth Road that will need to be relocated if impacted. Close coordination with the local utility companies will be carried out in order to coordinate the permanent relocation of these utilities. Permanent right-of-way acquisitions and temporary construction easements are needed for the realignment of Harlan Road through commercial and private property. Construction is anticipated to start in the Fall of 2021 and last approximately 12 months total. The Project may require two construction phases due to available funding. If construction phases are required, Phase I would consist of all roadway improvements south of Roth Road as well as improvements along Roth Road. Phase II would include roadway improvements north of Roth Road. During Phase I, the stop sign at the existing Harlan/Roth Road would be maintained, but with the relocation of the south leg of Harlan Road to the new proposed signalized intersection.

The Project is locally funded and therefore requires compliance with the California Environmental Quality Act (CEQA). The lead agency under CEQA is the City.

DETERMINATION

The City has prepared an Initial Study for this Project, and has determined from this study that the Project would not have a significant effect on the environment for the following reasons:

The Project would have no impact on agriculture and forest resources; energy; geology and soils; land use and planning; mineral resources; public services; recreation; and wildfire.

The Project would have a less than significant impact on aesthetics; air quality, biological resources; cultural resources; greenhouse gas emissions; hazards and hazardous materials; hydrology and water quality; traffic and transportation; tribal cultural resources; utilities and service systems.

The Project would have less than significant impact with mitigation incorporated on noise; population and housing; and mandatory findings of significance.

Michael King Director of Public Works City of Lathrop Date

Executive Summary

This environmental document is prepared in conformance with the requirements of the California Environmental Quality Act (CEQA) Public Resources Code 21000-21178. The City of Lathrop is the Lead Agency for CEQA implementation.

Resource	Project Impacts	Summary of Avoidance, Minimization, and/or Mitigation Measures
Aesthetics	Less than significant	Protect vegetation where feasible.
Agriculture and Forest Resources	No impact	N/A
Air Quality	Less than significant	Dust and erosion control during construction.
Biological Resources	Less than significant	Pre-construction nesting bird surveys.
Cultural Resources	Less than significant	Compliance with regulations relating to discovered human and/or Native American remains.
Energy	No impact	N/A
Geology and Soils	No impact	N/A
Greenhouse Gas Emissions	Less than significant	Comply with applicable rules, ordinances, and regulations for greenhouse gas emission restrictions and implement LED lighting.
Hazards and Hazardous Materials	Less than significant	Proper handling of potential hazardous materials and potential Phase II testing.
Hydrology and Water Quality	Less than significant	Standard BMPs and Storm Water Management Plan.
Land Use and Planning	No impact	N/A
Mineral Resources	No impact	N/A
Noise	Less than significant with mitigation incorporated	Implement the use of rubberized and/or open grade asphalt.
Population and Housing	Less than significant with mitigation incorporated	Provide relocation advisory assistance to any person with impacted properties.
Public Services	No impact	N/A
Recreation	No impact	N/A
Transportation/ Traffic	Less than significant	Prepare and implement traffic control plan.
Tribal Cultural Resources	Less than significant	Compliance with regulations relating to discovered human and/or Native American remains.
Utilities and Service Systems	Less than significant	N/A
Wildfire	No impact	N/A
Mandatory Findings of Significance	Less than significant with mitigation incorporated	With mitigation measures in place, all impacts will be reduced to less than significant.

Table 1. Summary of Potential Impacts

The detailed CEQA checklist summarizing specific Project impacts is included within each of the sections contained within the following Initial Study.

THIS PAGE INTENTIONALLY LEFT BLANK

Exec	cutive Summary	iv
Tabl	e of Contents	vi
List	of Abbreviations	viii
1.0	Project	1
1.1	Introduction	1
1.2	Alternatives	1
1.3	Permits and Approvals Needed	2
2.0	Initial Study	11
2.1	Aesthetics	
2.2	Agriculture and Forest Resources	13
2.3	Air Quality	
2.4	Biological Resources	22
2.5	Cultural Resources	34
2.6	Energy	38
2.7	Geology and Soils	39
2.8	Greenhouse Gas Emissions	42
2.9	Hazards and Hazardous Materials	46
2.10	Hydrology and Water Quality	53
2.11	Land use and Planning	57
2.12	Mineral Resources	61
2.13	Noise	62
2.14	Population and Housing	71
2.15	Public Services	77
2.16	Recreation	78
2.17	Transportation/Traffic	79
2.18		
2.19	, ,	
2.20		
2.21	Mandatory Findings of Significance	88
3.0	Comments and Coordination	90
3.1	Consultation and Coordination with Public Agencies	90
3.2	Public Participation	90
4.0	List of Preparers	91
Dok	ken Engineering	91
City	of Lathrop	91
5.0	References	92

Table of Contents

List of Figures

Figure 1: Project Vicinity	3
Figure 2: Project Location	4
Figure 3: Project Features	
Figure 4. Typical Sections	
Figure 5: Land Cover Types within the Biological Study Area	
Figure 6: California Greenhouse Gas Inventory	43
Figure 7: Potential RECs in the Project area	49
Figure 8: City of Lathrop General Plan Zoning Map	
Figure 9. Potential Property Relocations	72

List of Tables

Table 1. Summary of Potential Impacts	iv
Table 2. NAAQS and CAAQS Attainment Status for San Joaquin County	17
Table 3. Daily Operational Emissions	18
Table 4. Construction Emissions from Construction Activity	19
Table 5. SJVAPCD Air Quality Threshold of Significance- Criteria Pollutants	19
Table 6. Plant Species Observed within the BSA	31
Table 7. Estimated GHG Emissions for Project Alternatives	44
Table 8. Annual CO ₂ Emission for the Project Alternatives	45
Table 9: REC Evidence	47
Table 10. Existing Exterior Noise Levels	63
Table 11. Existing Interior Noise Levels	64
Table 12. Comparison of Estimated Exterior Noise Levels in Future (2040)	67
Table 13. Comparison of Estimated Interior Noise Levels in Future (2040)	68
Table 14. Vibration Source Levels for Construction Equipment	69
Table 15. Guideline Vibration Damage Potential Threshold Criteria	70
Table 16. Proposed Property Relocations	

List of Attachments

Attachment A – NRCS Soil Report

Attachment B – CT-EMFAC

Attachment C – CNDDB, USFWS, NMFS and CNPS Species List and Species Potential Table

Attachment D – Representative Photographs

Attachment E – FEMA Map

Attachment F – Mitigation Monitoring and Reporting Program

Attachment G – Distribution List

Attachment H – Response to Public Comments

List of Appendices (Note: All Appendices are available for review on the City's website)

Appendix A – Initial Site Assessment Appendix B – Noise Study Report

List of Abbreviations

AB	Assembly Bill
ADL	Aerially deposited lead
APE	Area of Potential Effects
AUL	Activity and Use Limitation
BMPs	Best Management Practices
BSA	Biological Study Area
CAA	Clean Air Act
CAAQS	California Ambient Air Quality Standards
CARB	California Air Resources Board
CCIC	Central California Information Center
CDFW	California Department of Fish and Wildlife
CESA	California Endangered Species Act
CEQA	California Environmental Quality Act
CFG	California Fish and Game
CFR	Code of Federal Regulation
City	City of Lathrop
CNDDB	California Natural Diversity Database
CNEL	Community Noise Equivalent Level
CNPS	California Native Plant Society
СО	Carbon Monoxide
CO ₂	Carbon Dioxide
County	San Joaquin County
CWA	Clean Water Act
dBA	Decibel A-weighted
EDR	Environmental Data Resources Inc.
EO	Executive Order
EPA	Environmental Protection Agency
FEMA	Federal Emergency Management Agency
FESA	Federal Endangered Species Act
FHWA	Federal Highway Administration
GHG	greenhouse gases
IPCC	Intergovernmental Panel on Climate Change
ISA	Initial Site Assessment
L _{eq} (h)	A-weighted Equivalent Sound Level
MBTA	Migratory Bird Treaty Act

MS4 Municipal Separate Storm Sewer System Mph miles per hour NAAQS National Ambient Air Quality Standards NAHC National Environmental Protection Act NMFS National Environmental Protection Act NMFS National Marine Fisheries Service NO2 Nitrogen Dioxide NO2 Nitrogen Oxides NOA Naturally Occurring Asbestos NPDES National Pollutant Discharge Elimination System NRCS Natural Resource Conservation Service O3 Ozone OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SHPO San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin V	MND	Mitigated Negative Declaration	
NAAQS National Ambient Air Quality Standards NAHC National Environmental Protection Act NMFS National Marine Fisheries Service NO2 Nitrogen Dioxide NO4 National Virogen Dioxide NO4 Nitrogen Oxides NOA Naturally Occurring Asbestos NPDES National Pollutant Discharge Elimination System NRCS Natural Resource Conservation Service O3 Ozone OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SJMSCP San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Valley Air Pollution Control District S	MS4	Municipal Separate Storm Sewer System	
NAHC Native American Heritage Commission NEPA National Environmental Protection Act NMFS National Marine Fisheries Service NO2 Nitrogen Dioxide NO2 Nitrogen Dioxide NO2 Nitrogen Oxides NOA Naturally Occurring Asbestos NPDES National Pollutant Discharge Elimination System NRCS Natural Resource Conservation Service O3 Ozone OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SHPO State Historic Preservation Office SJMSCP San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Valley Air Pollution Control District SO2 Suff	Mph	miles per hour	
NEPA National Environmental Protection Act NMFS National Marine Fisheries Service NO2 Nitrogen Dioxide NO2 Nitrogen Oxides NOA Naturally Occurring Asbestos NPDES National Pollutant Discharge Elimination System NRCS Natural Resource Conservation Service O3 Ozone OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SHPO State Historic Preservation Office SJMSCP San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Valley Air Pollution Control District SO2 Sulf Divide SPCCP Spill Prevention, Control, and Countermeasure Program SWPPP	NAAQS	National Ambient Air Quality Standards	
NMFS National Marine Fisheries Service NO2 Nitrogen Dioxide NOx Nitrogen Oxides NOA Naturally Occurring Asbestos NPDES National Pollutant Discharge Elimination System NRCS Natural Resource Conservation Service O3 Ozone OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SHPO State Historic Preservation Office SJMSCP San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Valley Air Pollution Control District SO2 Sulfur Dioxide SPCCP Spill Prevention, Control, and Countermeasure Program SWPPP State Water Resources Control Board U.S.	NAHC	Native American Heritage Commission	
NO2 Nitrogen Dioxide NOx Nitrogen Oxides NOA Naturally Occurring Asbestos NPDES National Pollutant Discharge Elimination System NRCS Natural Resource Conservation Service O3 Ozone OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SHPO State Historic Preservation Office SJMSCP San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Valley Air Pollution Control District SO2 Sulfur Dioxide SPCCP Spill Prevention, Control, and Countermeasure Program SWRPP Storm Water Pollution Prevention Plan SWRCB State Water Resources Control Board U.S.	NEPA	National Environmental Protection Act	
NOx Nitrogen Oxides NOA Naturally Occurring Asbestos NPDES National Pollutant Discharge Elimination System NRCS Natural Resource Conservation Service O3 Ozone OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SHPO State Historic Preservation Office SJMSCP San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Valley Air Pollution Control District SO2 Sulfur Dioxide SPCCP Spill Prevention, Control, and Countermeasure Program SWPPP Storm Water Pollution Prevention Plan SWRCB State Water Resources Control Board U.S. United States USACE<	NMFS	National Marine Fisheries Service	
NOA Naturally Occurring Asbestos NPDES National Pollutant Discharge Elimination System NRCS Natural Resource Conservation Service O3 Ozone OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SHPO State Historic Preservation Office SJMSCP San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Valley Air Pollution Control District SO2 Sulfur Dioxide SPCCP Spill Prevention, Control, and Countermeasure Program SWRCB State Water Resources Control Board U.S. United States USACE United States Army Corps of Engineers	NO ₂	Nitrogen Dioxide	
NPDES National Pollutant Discharge Elimination System NRCS Natural Resource Conservation Service O3 Ozone OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SHPO State Historic Preservation Office SJMSCP San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Valley Air Pollution Control District SO2 Sulfur Dioxide SPCCP Spill Prevention, Control, and Countermeasure Program SWPPP State Water Resources Control Board U.S. United States USACE United States Army Corps of Engineers USC United States Code	NOx	Nitrogen Oxides	
NRCS Natural Resource Conservation Service O3 Ozone OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SHPO State Historic Preservation Office SJMSCP San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Valley Air Pollution Control District SO2 Sulfur Dioxide SPCCP Spill Prevention, Control, and Countermeasure Program SWPPP State Water Resources Control Board U.S. United States USACE United States Army Corps of Engineers	NOA	Naturally Occurring Asbestos	
O3 Ozone OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SHPO State Historic Preservation Office SJMSCP San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Valley Air Pollution Control District SO2 Sulfur Dioxide SPCCP Spill Prevention, Control, and Countermeasure Program SWPPP Storm Water Pollution Prevention Plan SWRCB State Water Resources Control Board U.S. United States USACE United States Army Corps of Engineers USC United States Code	NPDES	National Pollutant Discharge Elimination System	
OHP Office of Historic Preservation Pb Lead PM Particulate Matter PRC Public Resources Code Project Harlan Road Realignment Project PPV Peak particle velocity REC Recognized Environmental Condition RME Resource Management Element RTP Regional Transportation Plan RWQCB Regional Water Quality Control Board SHPO State Historic Preservation Office SJMSCP San Joaquin Multi-species Conservation Plan SJVAPCD San Joaquin Valley Air Pollution Control District SO2 Sulfur Dioxide SPCCP Spill Prevention, Control, and Countermeasure Program SWPPP Store Water Resources Control Board U.S. United States USACE United States Army Corps of Engineers USC United States Code	NRCS	Natural Resource Conservation Service	
PbLeadPMParticulate MatterPRCPublic Resources CodeProjectHarlan Road Realignment ProjectPPVPeak particle velocityRECRecognized Environmental ConditionRMEResource Management ElementRTPRegional Transportation PlanRWQCBRegional Water Quality Control BoardSHPOState Historic Preservation OfficeSJMSCPSan Joaquin Multi-species Conservation PlanSJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	O ₃	Ozone	
PMParticulate MatterPRCPublic Resources CodeProjectHarlan Road Realignment ProjectPPVPeak particle velocityRECRecognized Environmental ConditionRMEResource Management ElementRTPRegional Transportation PlanRWQCBRegional Water Quality Control BoardSHPOState Historic Preservation OfficeSJMSCPSan Joaquin Multi-species Conservation PlanSJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	OHP	Office of Historic Preservation	
PRCPublic Resources CodeProjectHarlan Road Realignment ProjectPPVPeak particle velocityRECRecognized Environmental ConditionRMEResource Management ElementRTPRegional Transportation PlanRWQCBRegional Water Quality Control BoardSHPOState Historic Preservation OfficeSJMSCPSan Joaquin Multi-species Conservation PlanSJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	Pb	Lead	
ProjectHarlan Road Realignment ProjectPPVPeak particle velocityRECRecognized Environmental ConditionRMEResource Management ElementRTPRegional Transportation PlanRWQCBRegional Water Quality Control BoardSHPOState Historic Preservation OfficeSJMSCPSan Joaquin Multi-species Conservation PlanSJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	PM	Particulate Matter	
PPVPeak particle velocityRECRecognized Environmental ConditionRMEResource Management ElementRTPRegional Transportation PlanRWQCBRegional Water Quality Control BoardSHPOState Historic Preservation OfficeSJMSCPSan Joaquin Multi-species Conservation PlanSJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	PRC	Public Resources Code	
RECRecognized Environmental ConditionRMEResource Management ElementRTPRegional Transportation PlanRWQCBRegional Water Quality Control BoardSHPOState Historic Preservation OfficeSJMSCPSan Joaquin Multi-species Conservation PlanSJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	Project	Harlan Road Realignment Project	
RMEResource Management ElementRTPRegional Transportation PlanRWQCBRegional Water Quality Control BoardSHPOState Historic Preservation OfficeSJMSCPSan Joaquin Multi-species Conservation PlanSJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWPPPState Water Pollution Prevention PlanSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	PPV	Peak particle velocity	
RTPRegional Transportation PlanRWQCBRegional Water Quality Control BoardSHPOState Historic Preservation OfficeSJMSCPSan Joaquin Multi-species Conservation PlanSJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWPPPStorm Water Pollution Prevention PlanSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	REC	Recognized Environmental Condition	
RWQCBRegional Water Quality Control BoardSHPOState Historic Preservation OfficeSJMSCPSan Joaquin Multi-species Conservation PlanSJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWPPPStorm Water Pollution Prevention PlanSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	RME	Resource Management Element	
SHPOState Historic Preservation OfficeSJMSCPSan Joaquin Multi-species Conservation PlanSJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWPPPStorm Water Pollution Prevention PlanSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	RTP	Regional Transportation Plan	
SJMSCPSan Joaquin Multi-species Conservation PlanSJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWPPPStorm Water Pollution Prevention PlanSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	RWQCB	Regional Water Quality Control Board	
SJVAPCDSan Joaquin Valley Air Pollution Control DistrictSO2Sulfur DioxideSPCCPSpill Prevention, Control, and Countermeasure ProgramSWPPPStorm Water Pollution Prevention PlanSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	SHPO	State Historic Preservation Office	
SO2 Sulfur Dioxide SPCCP Spill Prevention, Control, and Countermeasure Program SWPPP Storm Water Pollution Prevention Plan SWRCB State Water Resources Control Board U.S. United States USACE United States Army Corps of Engineers USC United States Code	SJMSCP	San Joaquin Multi-species Conservation Plan	
SPCCPSpill Prevention, Control, and Countermeasure ProgramSWPPPStorm Water Pollution Prevention PlanSWRCBState Water Resources Control BoardU.S.United StatesUSACEUnited States Army Corps of EngineersUSCUnited States Code	SJVAPCD	San Joaquin Valley Air Pollution Control District	
SWPPP Storm Water Pollution Prevention Plan SWRCB State Water Resources Control Board U.S. United States USACE United States Army Corps of Engineers USC United States Code	SO ₂	Sulfur Dioxide	
SWRCB State Water Resources Control Board U.S. United States USACE United States Army Corps of Engineers USC United States Code	SPCCP	Spill Prevention, Control, and Countermeasure Program	
U.S. United States USACE United States Army Corps of Engineers USC United States Code	SWPPP	Storm Water Pollution Prevention Plan	
USACE United States Army Corps of Engineers USC United States Code	SWRCB	State Water Resources Control Board	
USC United States Code	U.S.	United States	
	USACE	United States Army Corps of Engineers	
USFWS United States Fish and Wildlife Service	USC	United States Code	
	USFWS	United States Fish and Wildlife Service	

1.0 Project

1.1 Introduction

The City of Lathrop (City) proposes to realign Harlan Road by shifting the intersection of Harlan Road and Roth Road within the City of Lathrop, California (**Figure 1, Figure 2**).

Proposed development projects within San Joaquin County, the City of Manteca, and the City of Lathrop will cause the I-5 interchange at Roth Road within the City of Lathrop to operate at an unacceptable level. The Harlan Road Realignment at Roth Road Project (Project), must be completed prior to any improvements being made to the interchange. The proposed Project will shift the existing Harlan Road/Roth Road intersection approximately 600 feet to the east, increasing the spacing between the I-5/Roth Road northbound ramp termini intersection and Harlan Road (**Figure 3**). This increased spacing will allow for future improvements at the ramp termini intersection to improve the intersection traffic operations. To match the shifted intersection, Harlan Road, north and south of Roth Road, will require realignment. Harlan Road currently runs parallel adjacent to the I-5 right of way within the Project area.

The proposed Project along Harlan Road will include three travel lanes and a center two-way left turn lane south of Roth Road and two travel lanes with a center striped median north of Roth Road (**Figure 4**). This lane configuration will incorporate the ultimate improvements necessary for Harlan Road within the Project area. Harlan Road will conform to the existing section at the beginning and end of the realigned portion; ultimate Harlan Road improvements past these conforms will take place as future projects.

The existing Harlan Road intersection will be converted to one cul-de-sac on the south side of Roth Road and a dead-end road on the north side of Roth Road to maintain access to the existing properties on Harlan Road outside of the realigned portion. Three alternatives are being considered for the road realignment north of Roth Road in the Project area. The proposed alternatives are being considered to evaluate the impacts to a private property (APN 19333031), a private residency located north of Roth Road along the existing Harlan Road. The proposed road realignment in the remainder of the Project area south of Roth Road is consistent for all alternatives. The City will select a preferred alternative based on public input and feasibility during final design.

1.2 Alternatives

Four alternatives are being considered for this Project— Alternative 1, Alternative 2, Alternative 3, and the No-Build Alternative.

1.2.1 Build Alternatives

Alternative 1

The entirety of the road alignment of Alternative 1 would pass through the northern portion of a private residential property (APN 19333031). This alternative would only require minimal permanent right of way acquisition from another private commercial property (APN 19333028) just north of APN 19333031, to accommodate curb returns. This alternative would result in the greatest impact to APN 19333031, including impacting the residential structure.

Alternative 2

The entirety of the road alignment of Alternative 2 would pass through a private commercial property (APN 19333028) on its south side. This alternative would only require minimal permanent right of way acquisition from the private residential property (APN 19333031) to

accommodate curb returns. This alternative would result in the least impact to the private residential property (APN 19333031).

Alternative 3

The road alignment of Alternative 3 would center the roadway between the private residential property (APN 19333031) and the adjacent private commercial property (APN 19333028). This alternative would require permanent right of way acquisition from both properties to accommodate each roadway half. This alternative would result in less impact to the private residential property (APN 19333031) than Alternative 1; however, the residential structure would still be impacted.

Common Design Features for Alternatives 1 Through 3

The ultimate typical section along Roth Road for all three alternatives is anticipated to be four travel lanes with a center lane. The intersection will be constructed to the ultimate width so as not to require disturbance to newly constructed improvements when the full Roth Road widening is completed. Beyond the intersection of Roth Road and Harlan Road, improvements to Roth Road will conform to the existing Roth Road section.

There are existing overhead electric and communication utility lines along Harlan Road/Roth Road that will need to be relocated if impacted. Close coordination with the local utility companies will be carried out in order to coordinate the permanent relocation of these utilities.

Permanent right-of-way acquisitions and temporary construction easements are needed for the realignment of Harlan Road through commercial and private property. Construction is anticipated to start in the Fall of 2021 and last approximately 12 months total. The Project may require two construction phases due to available funding. If construction phases are required, Phase I would consist of all roadway improvements south of Roth Road as well as improvements along Roth Road. Phase II would include roadway improvements north of Roth Road. During Phase I, the stop sign at the existing Harlan/Roth Road would be maintained, but with the relocation of the south leg of Harlan Road to the new proposed signalized intersection.


The Project is locally funded and therefore requires compliance with the California Environmental Quality Act (CEQA). The lead agency under CEQA is the City.


1.2.2 No-Project Alternative


The State CEQA Guidelines (Section 15126[e]) require consideration of a No-Project alternative that represents the existing conditions, as well as what would reasonably be expected to occur in the foreseeable future if the Project were not approved. Under the No-Build Alternative, Harlan Road will not be realigned. As a result, the goals of the Project will not be met and existing roadway in the corridor would be unable to accommodate planned and approved growth.

1.3 Permits and Approvals Needed

Impacts to waters of the Unites States (U.S.)., State, special status species, or floodway are not anticipated as a result of the proposed Project; therefore, no environmental permits will be required.









 1 inch = 300 feet
 Feet

 0
 300
 600
 900
 1,200


Figure 3 Project Features and Alternatives Harlan Road Realignment Project City of Lathrop, San Joaquin County, California



HARLAN ROAD REALIGNMENT SOUTH OF ROTH ROAD







CUL-DE-SAC

2.0 Initial Study

This chapter explains the impacts that the Project would have on the human, physical, and biological environments in the Project area. It describes the existing environment that could be affected by the Project, potential impacts from the alternatives, and avoidance, minimization, and/or mitigation measures. Any indirect impacts are included in the general impacts analysis and discussions that follow.

2.1 AESTHETICS

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Have a substantial adverse effect on a scenic vista?				\boxtimes
b) Substantially damage scenic resources, including, but not limited to, trees, rock outcroppings, and historic buildings within a state scenic highway?				\boxtimes
c) In non-urbanized areas, substantially degrade the existing visual character or quality of public views of the site and its surroundings?			\boxtimes	
d) Create a new source of substantial light or glare which would adversely affect day or nighttime views in the area?				\boxtimes

REGULATORY SETTING

CEQA establishes that it is the policy of the state to take all action necessary to provide the people of the state "with...enjoyment of aesthetic, natural, scenic and historic environmental qualities (CA Public Resources Code Section 21001[b])."

DISCUSSION

The environmental consequences for aesthetics are the same regardless of whether the Project is constructed in two phases or as one complete project.

a) Have a substantial adverse effect on a scenic vista?

Alternatives 1 through 3: No Impact. No designated scenic vistas are at or near the Project site for any of the proposed alternatives. Harlan Road, Roth Road, and I-5 are not designated Scenic Highways in the National Scenic Byways Program nor is it a State Scenic Highway (Caltrans 2020). There are no Wild and Scenic Rivers within the Project corridor. Therefore, no impacts to a scenic vista would result under any of the proposed Project alternatives.

b) Substantially damage scenic resources, including, but not limited to, trees, rock outcroppings, and historic buildings within a state scenic highway?

Alternatives 1 through 3: No Impact. The Project site is not near or located within a State Scenic Highway. Therefore, no impacts to scenic resources within a State Scenic Highway would result from development of the Project under any of the proposed alternatives, and no mitigation is required.

c) In non-urbanized areas, substantially degrade the existing visual character or quality of public views of the site and its surroundings?

Alternatives 1 through 3: Less than Significant. Minor tree trimming and vegetation clearing in select locations during construction of all three alternatives would result in a temporary change

in aesthetics, but those changes would be negligible and nearly unnoticeable from the realignment of Roth Road within a highly urban area. However, with the implementation of measure **VIS-1** the impacts would be further minimized.

d) Create a new source of substantial light or glare which would adversely affect day or nighttime views in the area?

Alternatives 1 through 3: Less than Significant. The Project would not substantially affect light and glare. No new lighting is proposed. Construction activities would temporarily introduce equipment and vehicles to the Project site; however, work would take place during daylight hours and no construction lighting is anticipated under any of the three proposed alternatives.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

The following measure will be incorporated into the Project to minimize visual impacts. This measure is required regardless of whether the Project is constructed in two phases or as one complete project.

VIS-1: Vegetation clearing would only occur within the delineated Project boundaries in an effort to minimize the impacts. Trees located in areas along the edge of the construction zone would be trimmed whenever possible and only those trees that lie within the active construction areas would be removed.

2.2 AGRICULTURE AND FOREST RESOURCES

	Potentially	Less Than	Less Than	
Would the Project:	Significant	Significant	Significant	No Impact
,	Impact	with Mitigation	Impact	

II. AGRICULTURE AND FOREST RESOURCES:

In determining whether impacts to agricultural resources are significant environmental effects, lead agencies may refer to the California Agricultural Land Evaluation and Site Assessment Model (1997) prepared by the California Dept. of Conservation as an optional model to use in assessing impacts on agriculture and farmland. In determining whether impacts to forest resources, including timberland, are significant environmental effects, lead agencies may refer to information compiled by the California Department of Forestry and Fire Protection regarding the state's inventory of forest land, including the Forest and Range Assessment Project and the Forest Legacy Assessment Project; and the forest carbon measurement methodology provided in Forest Protocols adopted by the California Air Resources Board. Would the Project:

a) Convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to non-agricultural use?		\boxtimes
b) Conflict with existing zoning for agricultural use, or a Williamson Act contract?		\boxtimes
c) Conflict with existing zoning for, or cause rezoning of, forest land (as defined in Public Resources Code section 12220(g)), timberland (as defined by Public Resources Code section 4526), or timberland zoned Timberland Production (as defined by Government Code section 51104(g))?		\boxtimes
d) Result in the loss of forest land or conversion of forest land to non- forest use?		\boxtimes
e) Involve other changes in the existing environment which, due to their location or nature, could result in conversion of Farmland, to non-agricultural use or conversion of forest land to non-forest use?		\boxtimes

DISCUSSION

a) Convert Prime Farmland, Unique Farmland, or Farmland of Statewide Importance (Farmland), as shown on the maps prepared pursuant to the Farmland Mapping and Monitoring Program of the California Resources Agency, to non-agricultural use?

Alternatives 1 through 3: No Impact. To identify Prime and Unique Farmland within the Project area, an examination of the soils in the Project area were queried through the Natural Resource Conservation Service (NRCS) website (NRCS 2020, **Attachment A**). No suitable farmland or Farmland of Statewide Importance was identified within the Project area. Therefore, the proposed Project alternatives would have no impacts to farmland soils.

b) Conflict with existing zoning for agricultural use, or a Williamson Act contract?

Alternatives 1 through 3: No Impact. The Project would not conflict with existing zoning for agriculture use, and there is no Williamson Act contract land within the Project area. Based on the fact that the Project area is located in an urban area and there is not farmland located within or adjacent to the Project area, the Project alternatives would have no impacts on farmland or agriculture in the Project vicinity.

c) Conflict with existing zoning for, or cause rezoning of, forest land (as defined in Public Resources Code section 12220(g)), timberland (as defined by Public Resources Code section 4526), or timberland zoned Timberland Production (as defined by Government Code section 51104(g))?

Alternatives 1 through 3: No Impact. There are no forests or forest resources located within the Project area; therefore, the Project alternatives will have no impacts with existing zoning for, or cause rezoning of, forest land, timberland, or timberland zoned Timberland Production.

d) Result in the loss of forest land or conversion of forest land to non-forest use?

Alternative 1 through 3: No Impact. There are no forests or forest resources located within the Project area; therefore, the Project alternatives will not result in the loss of forest land or conversion of forest land to non-forest use and there will be no impacts on forest land.

e) Involve other changes in the existing environment which, due to their location or nature, could result in the conversion of Farmland, to non-agricultural use or conversion of forest land to non-forest use?

Alternative 1 through 3: No Impact. There are no Farmlands or forest lands within the Project area; therefore, no conversion of Farmland to non-agriculture use or conversion of forest land to non-forest use would occur as a result of the Project.

FINDINGS

The Project would have **No Impacts** relating to agriculture and forest resources.

2.3 AIR QUALITY

Where available, the significance criteria established by the applicable air quality management or air pollution control district may be relied upon to make the following determinations. Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Conflict with or obstruct implementation of the applicable air quality plan?				\boxtimes
b) Result in a cumulatively considerable net increase of any criteria pollutant for which the Project region is non- attainment under an applicable federal or state ambient air quality standard?			\boxtimes	
c) Expose sensitive receptors to substantial pollutant concentrations?			\boxtimes	
d) Result in other emissions (such as those leading to odors) adversely affecting a substantial number of people?			\boxtimes	

REGULATORY SETTING

The Clean Air Act (CAA) as amended in 1990 is the federal law that governs air quality. Its counterpart in California is the California Clean Air Act of 1988. These laws set standards for the quantity of pollutants that can be in the air. At the federal level, these standards are called National Ambient Air Quality Standards (NAAQS). Standards have been established for six criteria pollutants that have been linked to potential health concerns; the criteria pollutants are: carbon monoxide (CO), nitrogen dioxide (NO₂), ozone (O₃), particulate matter (PM), lead (Pb), and sulfur dioxide (SO₂).

Regional level conformity in California is concerned with how well the region is meeting the standards set for CO, NO₂, O₃, and PM. California is in attainment for the other criteria pollutants. At the regional level, Regional Transportation Plans (RTP[s]) are developed that include all of the transportation projects planned for a region over a period of years, usually at least 20. Based on the projects included in the RTP, an air quality model is run to determine whether or not the implementation of those projects would conform to emission budgets or other tests showing that attainment requirements of the Clean Air Act are met. If the conformity analysis is successful, the regional planning organization, such as the San Joaquin Valley Air Pollution Control District (SJVAPCD) for San Joaquin County (County) and the appropriate federal agencies, such as the Federal Highway Administration (FHWA), make the determination that the RTP is in conformity with the State Implementation Plan for achieving the goals of the CCA. Otherwise, the projects in the RTP must be modified until conformity is attained. If the design and scope of the transportation project are the same as described in the RTP, then the Project is deemed to meet regional conformity requirements for purposes of project-level analysis.

Federal and State Ambient Air Quality Standards

California and the federal government have established standards for several different pollutants. For some pollutants, separate standards have been set for different measurement periods. Most standards have been set to protect public health. For some pollutants, standards have been based on other values (such as protection of crops, protection of materials, or avoidance of nuisance conditions). The pollutant of greatest concern in the Project area are ozone 46 parts per billion (SJVAPCD 2019).

State Regulations

Responsibility for achieving California's air quality standards, which are more stringent than federal standards, is placed on the California Air Resources Board (CARB) and local air districts, and is to be achieved through district-level air quality management plans that will be incorporated into the State Implementation Plan. In California, the Environmental Protection Agency (EPA) has delegated authority to prepare State Implementation Plans to the CARB, which, in turn, has delegated that authority to individual air districts.

The CARB has traditionally established state air quality standards, maintaining oversight authority in air quality planning, developing programs for reducing emissions from motor vehicles, developing air emission inventories, collecting air quality and meteorological data, and approving state implementation plans.

Responsibilities of air districts include overseeing stationary source emissions, approving permits, maintaining emissions inventories, maintaining air quality stations, overseeing agricultural burning permits, and reviewing air quality–related sections of environmental documents required by CEQA.

The California CAA of 1988 substantially added to the authority and responsibilities of air districts. The California CAA designates air districts as lead air quality planning agencies, requires air districts to prepare air quality plans, and grants air districts authority to implement transportation control measures. The California CAA focuses on attainment of the state ambient air quality standards, which, for certain pollutants and averaging periods, are more stringent than the comparable federal standards.

The California CAA requires designation of attainment and non-attainment areas with respect to state ambient air quality standards. The California CAA also requires that local and regional air districts expeditiously adopt and prepare an air quality attainment plan if the district violates state air quality standards for CO, SO₂, NO₂, or ozone. These Clean Air Plans are specifically designed to attain these standards and must be designed to achieve an annual 5% reduction in district-wide emissions of each non-attainment pollutant or its precursors. Where an air district is unable to achieve a 5% annual reduction, the adoption of "all feasible measures" on an expeditious schedule is acceptable as an alternative strategy (Health and Safety Code Section 40914(b)(2)). No locally prepared attainment plans are required for areas that violate the state PM₁₀ standards.

The California CAA requires that the state air quality standards be met as expeditiously as practicable but, unlike the federal CAA, does not set precise attainment deadlines. Instead, the act established increasingly stringent requirements for areas that will require more time to achieve the standards.

CARB's *Air Quality and Land Use Handbook: A Community Health Perspective* (2005) provides air resource board recommendations for the siting of new sensitive land uses (including residences) near freeways, distribution centers, ports, refineries, chrome plating facilities, dry cleaners, and gasoline stations. The handbook recommends that new development be placed at distances from such facilities.

AFFECTED ENVIRONMENT

The proposed Project is located within the San Joaquin Valley Air Basin and is under the SJVAPCD. The proposed Project will convert Harlan Road from two travel lanes to three travel lanes.

DISCUSSION

The environmental consequences for air quality are the same regardless of whether the Project is constructed in two phases or as one complete project.

a) Conflict with or obstruct implementation of the applicable air quality plan?

Alternative 1 through 3: No Impact. The Project is consistent with the site land use and zoning for the City of Lathrop; construction of the Project would not conflict with or obstruct implementation of any air quality plan. The Project is included in the RTP; therefore, the Project is consistent with the applicable air quality plan. The Project is listed in the City's General Plan and is in accordance with all local and regional general plans and proposed development for the vicinity.

b) Result in a cumulatively considerable net increase of any criteria pollutant for which the Project region is non-attainment under an applicable federal or state ambient air quality standard?

Alternative 1 through 3: Less than Significant Impact. The CARB is required to designate areas of the state as attainment, non-attainment, or unclassified for any state standard. An "attainment" designation for an area signifies that pollutant concentrations do not violate the standard for that pollutant in that area. A "non-attainment" designation indicates that a pollutant concentration violated the standard at least once within a calendar year. The NAAQS and the California Ambient Air Quality Standards (CAAQS) for San Joaquin County are shown on **Table 4**. San Joaquin County is in non-attainment for four pollutants including, ozone 1-hour, ozone 8-hour, PM₁₀ and PM_{2.5}.

All construction impacts to air quality would be short-term and intermittent; therefore, impacts are anticipated to be less than significant. The emission of pollutants during construction would not contribute significantly to a net increase of any criteria pollutant. Furthermore, no long-term, operational impacts are anticipated.

Operational Emissions

The Project is not anticipated to increase traffic volumes, vehicle miles traveled (VMT) or substantially change traffic patterns. Since there would be no change in operating conditions and traffic would not increase after construction, there would be no additional regional or local air emissions and no impact on air quality. Accordingly, the proposed Project would not exceed the applicable thresholds of significance for air pollutant emissions during operation. Therefore, operation of the Project would not result in a cumulatively considerable net increase in any criteria pollutant for which the Project region is in non-attainment (**Table 2**). CT-EMFAC was utilized to calculate emissions of pollutants, which can be found in **Table 3** below. The inputs and results used for CT-EMFAC can be found in **Attachment B**.

Pollutant	Designation/Classification		
Poliutant	Federal Standards	State Standards	
Ozone – 1-Hour	No Federal Standard	Non-attainment/Severe	
Ozone – 8-Hour	Non-attainment/Extreme	Non-attainment	
PM ₁₀	Attainment	Non-attainment	
PM _{2.5}	Non-attainment	Non-attainment	

 Table 2. NAAQS and CAAQS Attainment Status for San Joaquin County

Carbon Monoxide	Attainment/Unclassified	Attainment/Unclassified
Nitrogen Dioxide	Attainment/Unclassified	Attainment
Sulfur Dioxide	Attainment/Unclassified	Attainment
Sulfates	No Federal Standard	Attainment
Lead (Particulate)	No Designation/Classification	Attainment
Hydrogen Sulfide	No Federal Standard	Unclassified
Visibility Reducing Particles	No Federal Standard	Unclassified
Vinyl Chloride	No Federal Standard	Attainment
Sources: SJVAPCD 2020		

Criteria Pollutants	2019	Future Year (2040)			
	Existing (tons)	No Build Alternative (tons)	Build Alternatives (tons)		
NOx	0.001	<0.001	<0.001		
PM10	<0.001	<0.001	<0.001		
PM2.5	<0.001	<0.001	<0.001		
CO	0.002	<0.001	0.001		
ROG	<0.001	<0.001	<0.001		
Note- NOx and ROG are ozone precursors					

Table 3. Daily Operational Emissions

Construction Emissions

Construction activities associated with the Project may result in some temporary incremental increases in air pollutants, such as ozone precursors and particulate matter due to operation of gaspowered equipment and minor land disturbance. However, the proposed construction activities would be temporary in nature and are not anticipated to generate large amounts of dust or particulates because the Project will have limited operations on exposed ground. Additionally, the Project will be implementing best available control measures, as required by **AQ-1** through **AQ-3**, to reduce dust and particulate spreading.

The Project's construction is anticipated to take 12 months total and is anticipated to start in Fall of 2021. Phase I of the Project would require approximately 12 months of construction and Phase II of the Project would require approximately 4 months of construction. The Project's construction emissions were estimated using the Roadway Construction Emissions Model by the Sacramento Metropolitan Air Quality Management District (SMAQMD 2014), which is the accepted model for all CEQA roadway projects throughout California. The results in **Table 4** show the maximum potential of daily emissions that would occur during construction. The Roadway Construction Emissions Model results are compared with the SJVAPCD Air Quality Significance Thresholds in **Table 5**. As summarized in **Table 4**, construction activities from the Project would not exceed emission thresholds established by the SJVAPCD.

Construction Activities	CO (lbs/day)	NOx (lbs/day)	ROG (lbs/day)	SOx (lbs/day)	PM10 (lbs/day)	PM2.5 (lbs/day)
Grubbing/Land Clearing	10.47	13.00	1.18	0.03	10.56	2.57
Grading/Excavation	25.52	44.18	3.65	0.08	11.77	3.60
Drainage/Utilities/Sub- Grade	25.68	29.98	2.99	0.05	11.36	3.33
Paving	11.79	11.36	1.04	0.03	0.6	0.49
Maximum Daily (lbs/day)	25.68	44.18	3.65	0.08	11.77	3.60
SJVAPCD Thresholds (lbs/day)	540	54	145	27	81	81
Project Total (tons/construction project)	2.91	4.17	0.37	0.01	1.30	0.39

Table 4. Construction Emissions from Construction Activity

Table 5. SJVAPCD Air Quality Threshold of Significance- Criteria Pollutants

Pollutant/ Precursor	Construction Emissions	Operational Emissions			
		Permitted Equipment and Activities	Non-Permitted Equipment and Activities		
СО	100 tons per year (~540 lbs per day)	100 tons per year (~540 lbs per day)	100 tons per year (~540 lbs per day)		
NOx	10 tons per year (~54 lbs per day)	10 tons per year (~54 lbs per day)	10 tons per year (~54 lbs per day)		
ROG	10 tons per year (~54 lbs per day)	10 tons per year (~54 lbs per day)	10 tons per year (~54 lbs per day)		
SOx	27 tons per year (~145 lbs per day)	27 tons per year (~145 lbs per day)	27 tons per year (~145 lbs per day)		
PM ₁₀	15 tons per year (~81 lbs per day)	15 tons per year (~81 lbs per day)	15 tons per year (~81 lbs per day)		
PM _{2.5}	15 tons per year (~81 lbs per day)	15 tons per year (~81 lbs per day)	15 tons per year (~81 lbs per day)		
Source: SJ	/APCD (2015)				

Emissions from construction activities associated with the Project alternatives would not exceed the SJVAPCD significance thresholds for criteria pollutants.

All construction activities would follow the SJVAPCD rules and would implement all appropriate air quality Best Management Practices (BMPs), including minimizing equipment idling time and use of water or similar chemical palliative to control fugitive dust. The implementation of **AQ-1** through **AQ-3** would also be used to minimize effects of impacts on air quality due to construction. These measures provide compliance guidelines for minimizing fugitive dust to protect sensitive receptors in the vicinity. With adherence to **AQ-1** through **AQ-3** construction emissions would result in a **Less Than Significant Impact.** No mitigation is required.

c) Expose sensitive receptors to substantial pollutant concentrations?

Alternative 1 through 3: Less than Significant. During construction, short-term degradation of air quality is expected from the release of particulate emissions (airborne dust) generated by excavation, grading, hauling, and other activities related to construction. Emissions from construction equipment powered by gasoline and diesel engines are also anticipated and would include CO, NO_X (Nitrogen Oxides), volatile organic compounds, directly emitted PM_{10} and $PM_{2.5}$, and toxic air contaminants such as diesel exhaust particulate matter.

Localized Construction Analysis

The nearest sensitive receptors are within 30 feet from the eastern limits of construction within the southern portion of the Project area. The SJVAPCD Air Quality Significance thresholds for construction (see **Table 5**), represent the maximum emissions from a project that will not cause or contribute to an air quality exceedance of the most stringent applicable federal or state ambient air quality standard at the nearest sensitive receptor, taking into consideration ambient concentrations in each source receptor area, project size, distance to the sensitive receptor, and other applicable criteria.

Construction emissions were estimated using the latest Sacramento Metropolitan Air Quality Management District's Road Construction Model (<u>http://www.airquality.org/ceqa/</u>, Version 8.1.0, SMAQMD 2016). Construction-related emissions for the Project are presented in **Table 4**. The emissions presented are based on the best information available at the time of calculations. The emissions represent the peak daily construction emissions that would be generated by construction of the proposed Project.

Toxic Air Contaminants

The greatest potential for toxic air contaminant emissions would be related to diesel particulate emissions associated with heavy equipment operations during grading and excavation activities. In addition, incidental amounts of toxic substances such as oils, solvents, and paints would be used during construction. These substances would comply with all applicable SJVAPCD rules for their manufacture and use. The Project alternatives would have no permanent impacts related to toxic air contaminants on sensitive receptors. Given the above analysis, the impact is considered to be a **Less Than Significant Impact**. No mitigation is required.

d) Result in other emissions (such as those leading to odors) adversely affecting a substantial number of people?

Alternative 1 through 3: Less than Significant Impact. The Project site is located adjacent to I-5 and would not produce sufficient quantities of other emissions that could lead to odors during construction that would affect the surrounding residents; therefore, the Project would have less than significant impacts on air quality and other emissions.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

The following measures would be implemented as part of the Project to minimize short term construction related air quality emissions. These measures are required regardless of whether the Project is constructed in two phases or as one complete project.

AQ-1: A person shall not discharge into the atmosphere from any single source of emission whatsoever, any air contaminant, other than uncombined water vapor, for a period or periods aggregating more than three (3) minutes in anyone (1) hour which is:

- As dark or darker in shade as that designated as No. 1 on the Ringelmann Chart, as published by the United States Bureau of Mines.
- Of such opacity as to obscure an observer's view to a degree equal to or greater than the smoke described in Section 5.1 of this rule.
- AQ-2: A person shall not discharge from any source whatsoever such quantities of air contaminants or other materials which cause injury, detriment, nuisance or annoyance to any considerable number of persons or to the public or which endanger the comfort, repose, health or safety of any such person or the public or which cause or have a natural tendency to cause injury or damage to business or property.
- AQ-3: Storage Piles and Bulk Materials have handling, storage, and transportation requirements that include applying water when handling materials, wetting or covering stored materials, and installing wind barriers to limit VDE. Also, limiting vehicle speeds, loading haul trucks with a freeboard of six inches or greater along with applying water to the top of the load, and covering the cargo compartments are effective measures for reducing VDE and carryout from vehicles transporting bulk materials.

FINDINGS

The Project would have Less than Significant Impacts relating to air quality.

2.4 BIOLOGICAL RESOURCES

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
 a) Have a substantial adverse effect, either directly or through habitat modifications, on any species identified as a candidate, sensitive, or special status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Game U.S. Fish and Wildlife Service, or NOAA Fisheries? 			\boxtimes	
b) Have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies, regulations or by the California Department of Fish and Game or US Fish and Wildlife Service?				\boxtimes
c) Have a substantial adverse effect on state or federally protected wetlands (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?				\boxtimes
d) Interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery sites?				\boxtimes
e) Conflict with any local policies or ordinances protecting biological resources, such as a tree preservation policy or ordinance?				\boxtimes
f) Conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan?			\boxtimes	

REGULATORY SETTING

This section describes the federal, state, and local plans, policies, and laws that are relevant to biological resources within the Biological Study Area (BSA). "Special status species" include any species that has been afforded special recognition by federal, state or local resources agencies (e.g., U.S. Fish and Wildlife Service [USFWS], California Department of Fish and Wildlife [CDFW], etc.), and/or resource conservation organizations (e.g., California Native Plant Society [CNPS]). The term "special-status species" excludes those avian species solely identified under Section 10 of the Migratory Bird Treaty Act (MBTA) for federal protection. The MBTA Section 10 protected species are afforded avoidance and minimization measures per state and federal requirements. The Project's California Natural Diversity Database (CNDDB), USFWS, National Marine Fisheries Service (NMFS) and CNPS species list, as well as the Project's species potential table is included in **Attachment C**.

Federal Regulations

National Environmental Policy Act

The National Environmental Policy Act (NEPA) provides an interdisciplinary framework for environmental planning by Federal agencies and contains action-forcing procedures to ensure that Federal agency decision makers take environmental factors into account. NEPA applies whenever a Federal agency proposes an action, grants a permit, or agrees to fund or otherwise authorize any other entity to undertake an action that could possibly affect environmental resources.

Federal Endangered Species Act

The Federal Endangered Species Act (FESA) of 1973 (16 United States Code [USC] section 1531 et seq.) provides for the conservation of endangered and threatened species listed pursuant to

Section 4 of the Act (16 USC section 1533) and the ecosystems upon which they depend. These species and resources have been identified by USFWS or NMFS.

Clean Water Act

The Clean Water Act (CWA) was enacted as an amendment to the Federal Water Pollutant Control Act of 1972, which outlined the basic structure for regulating discharges of pollutants to waters of the U.S. CWA serves as the primary Federal law protecting the quality of the nation's surface waters, including lakes, rivers, and coastal wetlands. The CWA empowers the U.S. EPA to set national water quality standards and effluent limitations, and includes programs addressing both point-source and non-point-source pollution. Point-source pollution originates or enters surface waters at a single, discrete location, such as an outfall structure or an excavation or construction site. Non-point-source pollution originates over a broader area and includes urban contaminants in storm water runoff and sediment loading from upstream areas. The CWA operates on the principle that all discharges into the nation's waters are unlawful unless they are specifically authorized by a permit; permit review is CWA's primary regulatory tool.

The United States Army Corps of Engineers (USACE) regulates discharges of dredged or fill material into waters of the U. S. These waters include wetlands and non-wetland bodies of water that meet specific criteria, including a direct or indirect connection to interstate commerce. The USACE regulatory jurisdiction pursuant to Section 404 of the CWA is founded on a connection, or nexus, between the water body in question and interstate commerce. This connection may be direct (through a tributary system linking a stream channel with traditional navigable waters used in interstate or foreign commerce) or may be indirect (through a nexus identified in USACE regulations).

The Regional Water Quality Control Board (RWQCB) has jurisdiction under Section 401 of the CWA and regulates any activity which may result in a discharge to surface waters. Typically, the areas subject to jurisdiction of the RWQCB coincide with those of USACE (i.e., waters of the U.S. including any wetlands). The RWQCB also asserts authority over "waters of the State" under waste discharge requirements pursuant to the Porter-Cologne Water Quality Control Act.

Executive Order 13112: Prevention and Control of Invasive Species

Executive Order (EO) 13112 (signed February 3, 1999) directs all Federal agencies to prevent and control introductions of invasive species in a cost-effective and environmentally sound manner. The EO and directives from the FHWA require consideration of invasive species in NEPA analyses, including their identification and distribution, their potential impacts, and measures to prevent or eradicate them.

Executive Order 13186: Migratory Bird Treaty Act

EO 13186 (signed January 10, 2001) directs each Federal agency taking actions that could adversely affect migratory bird populations to work with USFWS to develop a Memorandum of Understanding that will promote the conservation of migratory bird populations. Protocols developed under the Memorandum of Understanding will include the following agency responsibilities:

- Avoid and minimize, to the maximum extent practicable, adverse impacts on migratory bird resources when conducting agency actions;
- Restore and enhance habitat of migratory birds, as practicable; and
- Prevent or abate the pollution or detrimental alteration of the environment for the benefit of migratory birds, as practicable.

The EO is designed to assist Federal agencies in their efforts to comply with the MBTA (50 Code of Federal Regulations 10 and 21) and does not constitute any legal authorization to take migratory birds. Take is defined under the MBTA as "the action of or attempt to pursue, hunt, shoot, capture, collect, or kill" (50 Code of Federal Regulations [CFR] 10.12) and includes intentional take (i.e., take that is the purpose of the activity in question) and unintentional take (i.e., take that results from, but is not the purpose of, the activity in question).

State Regulations

California Environmental Quality Act

California State law created the CEQA to inform governmental decision-makers and the public about the potential, significant environmental effects of proposed activities and to work to reduce these negative environmental impacts. The City of Lathrop is the CEQA lead agency for this Project.

California Endangered Species Act

The California Endangered Species Act (CESA) (California Fish and Game (CFG) Code Section 2050 et seq.) requires the CDFW to establish a list of endangered and threatened species (Section 2070) and to prohibit the incidental taking of any such listed species except as allowed by the Act (Sections 2080-2089). In addition, CESA prohibits take of candidate species (under consideration for listing).

The CESA also requires the CDFW to comply with CEQA (Pub. Resources Code Section 21000 et seq.) when evaluating incidental take permit applications (CFG Code Section 2081(b) and California Code Regulations, Title 14, section 783.0 et seq.), and the potential impacts the project or activity for which the application was submitted may have on the environment. CDFW's CEQA obligations include consultation with other public agencies which have jurisdiction over the project or activity [California Code Regulations, Title 14, Section 783.5(d)(3)]. CDFW cannot issue an incidental take permit if issuance would jeopardize the continued existence of the species [CFG Code Section 2081(c); California Code Regulations, Title 14, Section 783.4(b)].

Section 1602: Streambed Alteration Agreement

Under CFG Code 1602, public agencies are required to notify CDFW before undertaking any project that will divert, obstruct, or change the natural flow, bed, channel, or bank of any river, stream, or lake. Preliminary notification and project review generally occurs during the environmental process. When an existing fish or wildlife resource may be substantially adversely affected, CDFW is required to propose reasonable project changes to protect the resources. These modifications are formalized in a Streambed Alteration Agreement that becomes part of the plans, specifications, and bid documents for the project.

Section 3503 and 3503.5: Bird and Raptors

CFG Code Section 3503 prohibits the destruction of bird nests and Section 3503.5 prohibits the killing of raptor species and destruction of raptor nests.

Section 3513: Migratory Birds

CFG Code Section 3513 prohibits the take or possession of any migratory non-game bird as designated in the MBTA or any part of such migratory non-game bird except as provided by rules and regulations adopted by the Secretary of the Interior under provisions of the MBTA.

Local Regulations

City of Lathrop 1991 General Plan and Environmental Impact Report

Part V – Resource Management Element

The Resource Management Element (RME) brings together two mandatory elements and one optional element into a single functional element of the General Plan, including Conservation and Open Space (mandatory) and Recreation (optional). In addition to providing important policies for the management of local resources, the RME is intended to aid the City in determining whether a proposed public or private project is likely to have a "significant effect" on the environment as defined by CEQA.

City of Lathrop Bicycle Transportation Plan

Within Sub-Plan Area #1, bicycle routes are planned to be included as part of the street system, with Class II striping provided as part of the roadway along the Roth Road, Lathrop Road and Louise Avenue arterials. Other routes within Sub-Plan Area #1 would be made a part of the roadway without striping. The Project will be in accordance with the City of Lathrop Bicycle Transportation Plan.

San Joaquin County Multi-Species Habitat Conservation and Open Space Plan

The key purpose of the San Joaquin County Multi-Species Habitat Conservation and Open Space Plan (SJMSCP), is to provide a strategy for balancing the need to conserve Open Space and the need to Convert Open Space to non-Open Space uses while protecting the region's agricultural economy; preserving landowner property rights and providing for the long-term management of plant, fish and wildlife species. The SJMSCP compensates for Conversions of Open Space for several activities, including transportation projects. Covered activities can be undertaken by both public and private individuals and agencies throughout San Joaquin County and within the County's incorporated cities of Escalon, Lathrop, Lodi, Manteca, Ripon, Stockton and Tracy. For transportation projects, public agencies including Caltrans and the San Joaquin Council of Governments (for November 14, 2000 1-2 transportation projects) also will undertake activities which will be covered by the SJMSCP. The Project is a covered activity within the SJMSCP.

2035 San Joaquin County General Plan

Section 3.4 Natural Resource and Cultural Resources.

The goal of this section is to provide the basis for open space preservation and the responsible use of open space resources in the County. This includes protecting and preserving important habitat for plant and wildlife species, protecting open space critical for percolation of rainfall for natural recharge of the underlying groundwater basin, and ensuring the development and maintenance of open space and recreation areas. The Project will be in accordance within the 2035 San Joaquin County General Plan.

AFFECTED ENVIRONMENT

Prior to field surveys, the BSA was defined as the proposed Project impact area plus a 50-foot buffer around all anticipated work areas. The Project impact area is defined as all areas that will be temporarily or permanently impacted by the Project, including proposed right of way, construction easements, cut and fill limits, potential staging areas, and access roads. The Project area is approximately 46 acres and the BSA encompasses approximately 61.9 acres and is approximately 1,700 feet from east to west and approximately 3,400 feet from north to south.

Online databases from USFWS, CDFW CNDDB, CNPS, and NMFS were queried for presence of potential threatened, endangered, rare or special status species within USGS 7.5-minute

quadrangles. Preliminary literature review and database searches identified 46 regional species of special concern with potential to occur in the vicinity of the Project area. Raw data returned from the database queries is provided in **Attachment C**.

General biological surveys and habitat assessments were conducted by Dokken Engineering biologist, Courtney Owens on March 11, 2020. General biological surveys included walking meandering transects, observing vegetation communities, compiling notes on observed flora and fauna, and assessing the potential for existing habitat within the BSA to support sensitive plants and wildlife. After biological surveys were conducted, each species' specific habitat requirements were compared to actual site conditions and habitat present, the potential for each species' occurrence was then determined (**Attachment C**).


No special-status species were observed or are presumed present within the BSA. Based on habitat assessments, soil maps, botanical surveys, and recorded occurrences of regional special status plant species, no special status plants have the potential to occur within the BSA; however, two special status wildlife species were determined to have potential of occurring within the BSA. Based on local documented occurrences and presence of suitable habitat within and/or directly adjacent to the BSA; burrowing owl (*Athene cunicularia*) and Swainson's hawk (*Buteo swainsoni*) have been determined to have potential of occurring within the BSA.

Dominant land cover and vegetative communities within the BSA consist of roadway and developed/ruderal vegetation (Figure 5).

Sensitive Wildlife Species

Burrowing Owl

The burrowing owl is not a state or federally listed species but is a CDFW species of special concern. The burrowing owl is found throughout open landscapes of North and South America and can be found in grasslands, rangelands, agricultural areas, deserts, or any other open dry area with low vegetation and is often associated with high densities of burrowing mammals such as prairie dogs, ground squirrels, and tortoises (Audubon 2020). The species is associated with friable soils for nest burrows as the nesting pair enlarge and maintain the existing burrow by digging with their beaks and kicking back soil with their feet. Burrows excavated by the owls may be up to 6-10 feet long, with the nest located at end. Nesting occurs from February to August. Burrowing owls hunt mostly at dusk and at night, but also hunt during the breeding season. The species mainly consumes insects and small mammals, but diets vary with season and location. Agriculture and development have significantly diminished the colonies of prairie dogs and other burrowing animals where burrowing owls once nested by the hundreds. Pesticides, collisions with vehicles, shooting, entanglement in loose fences and similar manmade hazards, and hunting by introduced predators (including domestic cats and dogs) are also major sources of mortality for the species. Populations have declined by about 33% between 1966 and 2015; however, burrowing owls have benefited from protective legislation, reintroduction and habitat protection programs, and artificial nest burrows (Audubon 2020). Due to the fact the species does not require large uninterrupted stretches of habitat, burrowing owls can benefit from the protection of relatively small patches of suitable land.






Figure 5 Land Cover Types within the Biological Study Area

Harlan Road Realignment Project City of Lathrop, San Joaquin County, California

Swainson's Hawk

The Swainson's hawk is a state listed threatened species. Swainson's hawk inhabits North America mainly in the spring and summer and winters in South America. Swainson's hawk is probably the longest migrant of any North American raptor. Swainson's Hawks favor open habitats for foraging. Although much of their native prairie and grassland habitat has been converted to crop and grazing land, these hawks have adjusted well to agricultural settings (Audubon 2020). Pairs often build nests in shelterbelts or other trees located near agricultural fields and pastures where they feed. Nesting trees include willow, black locust, oak, aspen, cottonwood, and conifers. Swainson's hawk may reuse a nest from a previous year, or refurbish a crow, raven, or magpie nest. In California, the Swainson's hawk breeds from late March to mid-August, with peak activity from late May to late July. Although Swainson's hawk are big enough to prey on rodents, snakes, and birds, at most seasons it feeds heavily on large insects instead. Flocks of hawks are often seen sitting on the ground in fields where there are many grasshoppers or caterpillars. Historic declines of this species occurred when farmers shot these and other hawks in the belief that they harmed livestock. More recent declines are due to a loss of prey and nesting sites. Continued consolidation of small farms, which offer shelterbelts of trees suitable for nest sites, into larger agribusiness operations eliminates nesting habitat and threatens breeding populations. The conversion of pastureland to soybean fields in Argentina has led to a loss of winter foraging habitat (Audubon 2020). Certain pesticides used in Argentina to control grasshoppers killed thousands of wintering Swainson's Hawks in the mid-1990s.

ENVIRONMENTAL CONSEQUENCES

The environmental consequences for biological resources are the same regardless of whether the Project is constructed in two phases or as one complete project.

a) Have a substantial adverse effect, either directly or through habitat modifications, on any species identified as candidate, sensitive, ore special status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Game U.S. Fish and Wildlife Service, or NOAA Fisheries?

Alternatives 1 through 3: Less than Significant. The Project alternatives would have less than significant impact on special status species. The following sensitive species have the potential to occur within the BSA:

Burrowing Owl

During the March 2020 biological surveys, potential suitable burrowing owl habitat was identified adjacent to the Project BSA. Suitable breeding habitat observed includes the abandon railroad and abandoned runway located approximately 1,500 feet to the east of the Project BSA. The CNDDB lists this occurrence as 0.3 miles to the southeast and was documented in 2016 near abandoned runway and railroad tracks. Burrowing owls have been detected at this adjacent site since 1981 and have been monitored yearly since 1997. This site also contains artificial burrows installed in 1999 to mitigate habitat loss from the construction of a large building (approximately 20 acres). Due to the fact that there is suitable habitat present adjacent to the BSA, coupled with the number of local documented occurrences and the documented historical importance of the adjacent site; the species has been determined to have a low to moderate potential of occurring within the BSA. No impacts to burrowing owls are anticipated as a result of the Project. Project related construction activities will remain well outside the suitable habitat for the species. To avoid all impacts to burrowing owls, a pre-construction nesting bird survey will be conducted in areas were vegetation removal is anticipated.

Swainson's Hawk

During the March 2020 biological surveys, suitable nesting habitat for Swainson's hawk was identified within the Project area and adjacent to the BSA. Suitable nesting habitat within the

Project area includes a variety of tall, scattered trees within residential yards and commercial properties south of Roth Road, along Harlan Road. Suitable nesting trees are also located along the northbound I-5 and exit 465, adjacent to the Project BSA. Additionally, suitable foraging habitat is found adjacent to the Project BSA. Open agriculture fields are located to the east and west of the Project area. Furthermore, there are several documented CNDDB occurrences within a 10-mile radius of the Project BSA, documented from 1988 to 2016. The closest documented occurrence is located approximately 0.7 miles to the south of the Project area near the Lathrop underpass and was recorded in 2011. The most recent CNDDB occurrence within a 10-mile radius of the BSA was recorded in 2016 and was documented along the Grant Line Canal approximately 9 miles to the southeast. Due to the fact there is suitable nesting trees within the BSA and suitable foraging habitat adjacent to the BSA, and given the number of local and recent documented occurrences; the species has been determined to have a low to moderate potential of occurring within the BSA. The Project would require the removal of a few trees; however, impacts to Swainson's hawk are not anticipated; a pre-construction nesting bird survey, during the nesting season, will be conducted in areas were vegetation removal is anticipated.

Measures **BIO-1** through **BIO-10**, listed below, will be implemented to avoid and minimize impacts to sensitive species.

b) Have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies, regulations or by the California Department of Fish and Game or U.S. Fish and Wildlife Service?

Alternatives 1 through 3: No Impact. The Project area lacks riparian habitat and other sensitive natural communities; therefore, impacts to these sensitive habitats are not anticipated. The following habitat occurs within the BSA (Figure 5):

<u>Roadway</u>

Roadways comprise approximately 6.3 acres (10.2%) of the BSA. The main roadways within the BSA are Roth Road, running east to west through the BSA, and Harlan Road, running north to south within the BSA. There are two other unnamed roads within the BSA that terminate into parking lots in the southern and northern portion of the BSA.

Developed/Ruderal Vegetation

The remaining of the BSA is categorized as developed or ruderal vegetation land cover. The developed land cover encompasses parking lots, buildings and residencies within the BSA. Furthermore, ruderal vegetation is present throughout the BSA, including landscaping, scattered trees and roadside vegetation. Ruderal vegetation within the BSA is dominated by weedy plant species that thrive in disturbed areas, such as roadsides with heavily compacted soils and little oxygen availability. Dominant weedy species within the BSA include black mustard (*Brassica nigra*), Mediterranean barley (*Hordeum marinum ssp. gussoneanum*) and ripgut brome (*Bromus diandrus*) (**Table 6**). The dominant tree species within the BSA are Mexican fan palm (*Washingtonia robusta*) and silver dollar gum (*Eucalyptus polyanthemos*). The developed/ruderal vegetation land cover encompasses approximately 55.6 acres (89.8%) of the BSA (**Attachment D**).

The land cover types within the BSA are categorized as highly disturbed and have been extensively converted through anthropomorphic activities and presently provide little to no habitat value for native species. BMPs will be implemented into final design to ensure the Project does not impact any local or adjacent resources.

Common Name	Scientific Name	Native (N)/Non-Native (X)
Black mustard	Brassica nigra	X (Invasive)
Cheeseweed	Malva parviflora	Х
Common mallow	Malva neglecta	Х
Curly dock	Rumex crispus	X (Invasive)
Dandelion	Taraxacum officinale	Х
Common (English) Ivy	Hedera helix	X (Invasive)
Fennel	Foeniculum vulgare	X (Invasive)
Field bindweed	Convolvulus arvensis	Х
Field mustard	Brassica rapa	X (Invasive)
Italian rye grass	Festuca perennis	X (Invasive)
Italian thistle	Carduus pycnocephalus	X (Invasive)
Mediterranean barley	Hordeum marinum ssp. gussoneanum	Х
Mexican fan palm	Washingtonia robusta	X (Invasive)
Milk thistle	Silybum marianum	X (Invasive)
Poison hemlock	Conium maculatum	X (Invasive)
Prickly lettuce	Lactuca serriola	Х
Red stem filaree	Erodium cicutarium	X (Invasive)
Ripgut brome	Bromus diandrus	X (Invasive)
Silver dollar gum	Eucalyptus polyanthemos	Х
Sow thistle	Sonchus asper	Х
Western morning glory	Calystegia occidentalis	Ν
Wild oat	Avena fatua	X (Invasive)
Yellow star thistle	Centaurea solstitialis	X (Invasive)

Table 6. Plant Species Observed within the BSA

c) Have a substantial adverse effect on state or federally protected wetlands (including, but not limited to marsh, vernal pool, coastal etc.) through direct removal, filling, hydrological interruption, or other means?

Alternatives 1 through 3: No Impact. The Project alternatives will not result in impacts to state or federally protected wetlands as no wetlands exist within or adjacent to the Project area (National Wetland Inventory 2020).

d) Interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery sites?

Alternatives 1 through 3: No Impact. The land cover within the BSA consists of urban and developed areas with ruderal vegetative cover and lacks quality habitat to support native wildlife species. This land cover is highly disturbed and fragmented due to commercial and residential development along Harlan Road and Roth Road. The proposed Project alternatives will not result in impacts to a wildlife or migration corridor. All Project related activities are anticipated to occur in developed areas or areas that have been highly disturbed by human activities.

e) Conflict with any local policies or ordinances protecting biological resources, such as a tree preservation policy or ordinance?

Alternatives 1 through 3: No Impact. The proposed Project alternatives are not anticipated to conflict with any local policies or ordinances protecting biological resources within the Project area. The proposed Project will be consistent with the City of Lathrop 1991 General Plan, City of Lathrop Bicycle Transportation Plan, the SJMSCP and the 2035 San Joaquin County General Plan. Additionally, the Project is a covered project (1-2 transportation projects) in the SJMSCP and will be adhering to all SJMSCP required measures.

f) Conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan?

Alternatives 1 through 3: Less Than Significant. The proposed Project is a covered activity within the SJMSCP. The BSA is within a Land Category A Zone. Category A/No-Pay Zone indicates parcels where Conversions of Open Space already have occurred (as of January 1, 2001) or where new Conversions of Open Spaces and would not require compensation because the subject parcel received a project approval prior to the Effective Date of the SJMSCP. Approved, for the purposes of this section means completion of the environmental review process (CEQA review) and approval of an entitlement through a public hearing process or issuance of an entitlement by a local planning agency if a public hearing is not required. There is no fee for SJMSCP Permitted Activities located within the No Pay Zone on the SJMSCP Compensation Zone Maps unless otherwise specified in pre-existing conditions of project approval.

The Project will comply with the SJMSCP as well as other state and local environmental regulations, and BMPs. Avoidance measures will be implemented to ensure no take of native birds or nests would occur during construction. Impacts would be reduced to less than significant.

AVOIDANCE, MINIMIZATION AND/OR MITIGATION MEASURES

The following avoidance and minimization measures along with BMPs have been incorporated into the Project design to minimize impacts to special status species to the greatest extent practicable. The following avoidance, minimization and mitigation measures are required regardless of whether the Project is constructed in two phases or as one complete project.

- **BIO-1:** Prior to the start of construction activities, the Project limits must be marked with high visibility fencing or staking to ensure construction will not further encroach into adjacent properties. The Project biologist will periodically inspect the fencing to ensure sensitive locations outside the limits of construction remain undisturbed. Fencing or staking will be maintained until the completion of all construction activities.
- **BIO-2:** All construction personnel shall be provided with environmental awareness training prior to being allowed to work on the job site. The training shall include an overview of special status species that have potential to occur within or adjacent to the Project area and Project specific protective measures that must be adhered to, including BMPs. The training will also include a description of the legal penalties for violating protective measures.
- **BIO-3:** If construction is initiated during the nesting bird season (February 15-August 31) a nesting bird survey shall be conducted by a qualified biologist within 14 days prior to construction initiation. Focused surveys must be performed by a qualified biologist

for the purposes of determining the presence/absence of active nest sites within the proposed impact area, including construction access routes and a 200-foot buffer (if feasible).

A minimum 50 foot no-disturbance buffer will be established around any active nest of migratory birds and a minimum 300 foot no-disturbance buffer will be established around any nesting raptor species. The contractor must immediately stop work in the nesting area until the appropriate buffer is established and is prohibited from conducting work that could disturb the birds (as determined by the Project biologist and in coordination with wildlife agencies) in the buffer area until a qualified biologist determines the young have fledged. A reduced buffer can be established if determined appropriate by the Project biologist and approved by CDFW.

- **BIO-4:** Vegetation clearing will only occur within the delineated Project boundaries. Where possible, trees will be identified for trimming rather than full removal with the guidance of the Project biologist.
- **BIO-5:** Exposed soils would be stabilized, through watering or other measures, to prevent the movement of dust at the Project site caused by wind and construction activities such as traffic and grading activities.
- **BIO-6:** All construction materials would be hauled off-site after completion of construction.
- **BIO-7:** Prior to arrival at the Project site and prior to leaving the Project site, construction equipment that may contain invasive plants and/or seeds must be cleaned to reduce the spreading of noxious weeds.
- **BIO-8:** The contractor must not apply rodenticide or herbicide within the Project area during construction.
- **BIO-9:** The contractor must dispose of all food-related trash in closed containers and must remove it from the Project area each day during construction. Construction personnel must not feed or attract wildlife to the Project area.
- **BIO-10:** Plastic monofilament netting shall not be used in straw wattles or other erosion control materials.

FINDINGS

The Project would have Less Than Significant Impacts relating to biological resources.

2.5 CULTURAL RESOURCES

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Cause a substantial adverse change in the significance of a historical resource as defined in §15064.5?				\boxtimes
b) Cause a substantial adverse change in the significance of an archaeological resource pursuant to §15064.5?			\boxtimes	
c) Disturb any human remains, including those interred outside of dedicated cemeteries?			\boxtimes	

REGULATORY SETTING

CEQA established statutory requirements for determining the significance of historical resources in Public Resources Code (PRC) Section 21084.1. The CEQA Guidelines (Section 10564.5[c]) also require consideration of potential Project impacts to "unique" archaeological sites that do not qualify as historical resources. The statutory requirements for unique archaeological sites that do not qualify as historical resources are established in PRC Section 21083.2. These two PRC sections operate independently to ensure that potentially significant effects on historical and archaeological resources are considered as part of a Project's environmental analysis. Historical resources, as defined in Section 15064.5(a) of the CEQA regulations, include 1) cultural resources listed in or eligible for listing in the California Register of Historical Resources (California Register); 2) cultural resources included in a local register of historical resources; 3) any object, building, structure, site, area, place, record, or manuscript which a lead agency determines to be historically significant or significant in one of several historic themes important to California's history and development.

Under CEQA, a Project may have a significant effect on the environment if the Project could result in a substantial adverse change in the significance of a historical resource, meaning the physical demolition, destruction, relocation, or alteration of the resource would be materially impaired. This would include any action that would demolish or adversely alter the physical characteristics of an historical resource that convey its historic significance and qualify it for inclusion in the California Register or in a local register or survey that meets the requirements of PRC Section 5020.1(I) and 5024.1(g). PRC Section 5024 also requires state agencies to identify and protect sate-owned resources that meet National Register of Historic Place (National Register) listing criteria. Sections 5024(f) and 5024.5 require state agencies to provide notice to and consult with the State Historic Preservation Officer (SHPO) before altering, transferring, relocation, or demolishing stateowned historical resources that are listed on or are eligible for inclusion in the National Register or are registered or eligible for registration as California Historical Landmarks.

CEQA and the CEQA Guidelines also recommend provisions be made for the accidental discovery of archaeological sites, historical resources, or Native American human remains during construction (PRC Section 21083.2(i) CCR Section 15064.5[d and f]).

AFFECTED ENVIRONMENT

The Area of Potential Effects (APE) was established as the area of direct and indirect effects and includes all proposed construction areas associated with roadway realignments (including the three alternatives in the northern portion of the Project), potential staging / contractor use areas, and utility relocations. Approximately 46-acres in area, the APE is identical to the Project area depicted in **Figure 3**.

Efforts to identify cultural resources within or adjacent to the APE included background research, a record search with the California Historical Resources Information System, Central California Information Center (CCIC) at California State University Stanislaus, consultation with the Native American Heritage Commission (NAHC), outreach to relevant Native American groups and individuals, and an archaeological pedestrian surface survey.

The CCIC record search for documented cultural resources and cultural resource investigations in the APE and surrounding one-mile radius was conducted on January 13, 2020, also examining the Office of Historic Preservation (OHP) Historic Properties Directory, OHP Determinations of Eligibility, and the California Inventory of Historical Resources. The results of the search indicate that there are no documented cultural resources within or adjacent the APE, and 59 resources identified within the one-mile search radius—all in association with the Sharpe Army Depot located approximately 1,000 feet east of the Project area. Two previous cultural resources investigations have been conducted within or adjacent to portions of the APE. One 2002 inventory conducted within the western portion of the APE included a linear segment along Harlan Road and a 2-acre area north of Roth Road. Conducted in 2015, the second investigation occurred north of Roth Road, immediately adjacent the eastern boundary of the APE. Neither of these investigations have been conducted within a one-mile radius of the APE, but apart from the cluster resources associated with the Sharpe Army Depot, no other cultural resources were documented in association with those efforts.

On January 27, 2020, the results of a request for a NAHC review of the Sacred Lands File were returned negative, indicating no known cultural resources that might be affected by the project. To help determine whether the Project may have an effect, PRC Section 21080.3.1 requires the CEQA lead agency to consult with any California Native American tribe that requests consultation and is traditionally and culturally affiliated with the geographic area of a proposed project.

On March 11, 2020, initial consultation letters were mailed to the Native American tribal governments who have previously submitted in writing to the County a request to be notified of projects within their traditionally and culturally affiliated area, pursuant to PRC Section 21080.3.1. The letters provided a summary of the project and requested information regarding comments or concerns the tribal governments might have about the project and whether any traditional cultural properties, Tribal Cultural Resources (TCR), or other resources of significance would be affected by implementation of the project. Letters were sent to Katherine Perez, Chairperson, *North Valley Yokuts Tribe*, and Mike Despain of the *Buena Vista Rancheria Me-Wuk Indians*.

On March 25, 2020, Richard Hawkins (Tribal Historic Preservation Office Coordinator) responded via e-mail, indicating that the *Buena Vista Rancheria Me-Wuk Indians* had no knowledge of cultural resources present in the APE and no objection to the project, but requested additional notification in the event that cultural resources are encountered during project implementation. Dokken staff Amy Dunay responded affirmatively to this request on March 25, 2020. To date, no other responses have been received.

On March 11, 2020, Archaeologist John Fogerty conducted a pedestrian surface survey of the APE. Where safely practicable, the surface survey was conducted via controlled transects spaced at no greater than 5 m. (16 ft.) intervals within and/or along the margins of the proposed realignment areas associated with S. Harlan and Roth Roads, as well as over available surface exposures throughout the APE.

Above all, the pedestrian survey established that the APE has been subject to extensive surface disturbance and modification as a result of residential, commercial, and industrial development

as well as the construction of I-5 and the Roth Road interchange between 1968 and 1970. Nearly all of the APE north of Roth Road has been paved over, with the exception of the northeastern APE corner, which contains a portion of a deeply excavated retention pond. South of Roth Road, the APE contains paved portions to a lesser extent, though what remains has been extensively graded, surfaced, and/or capped with imported gravel. No artifacts, archaeological features, or anthropogenic soils were observed within or adjacent to the APE as a result of the pedestrian survey.

A review of available parcel data and historic topographic maps and aerial imagery indicates that the APE was once largely agricultural land, hosting orchards and row crops throughout much of the APE north of Roth Road well into the mid-1990s. South of Roth Road, the APE was occupied with small, individual row crop agricultural efforts that progressed to the inclusion of more residential housing in the 1970s. Only one identified structure in the APE was determined to be greater than 50 years in age. Located at 11500 S. Harlan Road in the southern portion of the Project and within the proposed realignment area, this single-family residential structure was constructed in 1926. Evaluated by Stephen Mikesell of Mikesell Historical Consulting, the structure was determined to be ineligible for listing in the California Register of Historical Resources, under any of the applicable eligibility criteria.

DISCUSSION

The environmental consequences for cultural resources are the same regardless of whether the Project is constructed in two phases or as one complete project.

a) Cause a substantial adverse change in the significance of a historical resource as defined in §15064.5?

Alternatives 1 through 3: No Impact. Record searches with the CCIC and NAHC, outreach to relevant Native American groups, an archaeological pedestrian surface survey, and reviews of available parcel data, historic topographic maps, aerial imagery and literature were undertaken in an effort to identify cultural resources within or adjacent the APE. No historical resources as defined in §15064.5 were identified as a result of these efforts. As such, the Project would have no impact on historical resources as defined in §15064.5.

b) Cause a substantial adverse change in the significance of an archaeological resource pursuant to §15064.5?

Alternatives 1 through 3: Less than Significant. In an effort to identify archaeological resources that might be affected by the undertaking, a pedestrian survey, background research, and consultation with individuals and organizations were conducted. No archaeological resources were identified as a result of these efforts, and given the extensive disturbances associated with development within the APE, the likelihood of the Project encountering undiscovered archaeological deposits is remote.

At this time, no further archaeological study is recommended unless Project plans are modified to include areas not previously included in the APE. With the findings of the visual survey, record search, no impacts are anticipated for the Project related to archaeological resources. As with any project with prescribed surface disturbance, there is always the possibility that unknown cultural resources may be encountered during project construction. With the implementation of measure **CR-1** potential impacts from the Project would be less than.

c) Disturb any human remains, including those interred outside of dedicated cemeteries?

Alternative 1 through 3: Less than Significant. With any project, there is always the possibility that unmarked burials may be unearthed during construction. This impact is considered potentially significant. Implementation of Measure **CR-2** would reduce this to a less than significant.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

The following avoidance, minimization and mitigation measures are required regardless of whether the Project is constructed in two phases or as one complete project.

- **CR-1:** If previously unidentified cultural materials are unearthed during construction, work shall be halted in that area until a qualified archaeologist can assess the significance of the find and develop a plan for documentation and removal of resources if necessary. Additional archaeological survey will be needed if Project limits are extended beyond the present survey limits.
- **CR-2:** Section 5097.94 of the Public Resources Code and Section 7050.5 of the California Health and Safety Code protect Native American burials, skeletal remains and grave goods, regardless of age and provide method and means for the appropriate handling of such remains. If human remains are encountered, work should halt in that vicinity and the county coroner should be notified immediately. At the same time, an archaeologist should be contacted to evaluate the situation. If the human remains are of Native American origin, the coroner must notify the Native American Heritage Commission within twenty-four hours of such identification. CEQA details steps to be taken if human burials are of Native American origin.

FINDINGS

The Project would have Less Than Significant Impacts relating to cultural resources.

2.6 ENERGY

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Result in potentially significant environmental impact due to wasteful, inefficient, or unnecessary consumption of energy resources, during Project construction or operation?				\boxtimes
b) Conflict with or obstruct a state or local plan for renewable energy or energy efficiency?				\boxtimes

DISCUSSION

a) Result in potentially significant environmental impact due to wasteful, inefficient, or unnecessary consumption of energy resources, during Project construction or operation?

Alternatives 1 through 3: No Impact. The Project alternatives would comply with standard BMPs and the City of Lathrop 1991 General Plan and Environmental Impact Report and the San Joaquin County General Plan to ensure that no potentially significant environmental impacts will occur due to wasteful, inefficient, or unnecessary consumption of energy resources.

b) Conflict with or obstruct a state or local plan for renewable energy or energy efficiency?

Alternatives 1 through 3: No Impact. The proposed Project alternatives will not conflict with or obstruct any state or local plans for renewable energy or energy efficiency.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

No Impacts to energy are anticipated; therefore, no avoidance, minimization, and/or mitigation measures will be required.

2.7 GEOLOGY AND SOILS

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
 a) Expose people or structures to potential substantial adverse effects, including the risk of loss, injury, or death involving: 				
i) Rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault? Refer to Division of Mines and Geology Special Publication 42?				\boxtimes
ii) Strong seismic ground shaking?				\square
iii) Seismic-related ground failure, including liquefaction?				\square
iv) Landslides?				\square
b) Result in substantial soil erosion or the loss of topsoil?			\boxtimes	
c) Be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the Project, and potentially result in on- or off-site landslide, lateral spreading, subsidence, liquefaction or collapse?				\boxtimes
d) Be located on expansive soil, as defined in Table 18-1-B of the Uniform Building Code (1994), creating substantial risks to life or property?				\boxtimes
e) Have soils incapable of adequately supporting the use of septic tanks or alternative waste water disposal systems where sewers are not available for the disposal of waste water?				\boxtimes
f) Directly or indirectly destroy a unique paleontological resource or site or unique geologic feature?				\boxtimes

REGULATORY SETTING

For geologic and topographic features, the key federal law is the Historic Sites Act of 1935, which establishes a national registry of natural landmarks and protects "outstanding examples of major geological features." Topographic and geologic features are also protected under the CEQA.

This section also discusses geology, soils, and seismic concerns as they relate to public safety and Project design.

DISCUSSION

- a) Expose people or structures to potential substantial adverse effects, including the risk of loss, injury, or death involving:
 - i) Rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or based on other substantial evidence of a known fault? Refer to Division of Mines and Geology Special Publication 42?
 - ii) Strong seismic ground shaking?
 - iii) Seismic-related ground failure, including liquefaction?
 - iv) Landslides?

Alternatives 1 through 3: No Impact. The Project alternatives would not expose people or structures to potential substantial adverse effects, including risk of loss, injury, or death involving rupture of a known fault, strong seismic ground shaking, seismic-related ground failure, or landslides. The Project is not located within an Alquist Priolo Earthquake Fault Zone. The nearest seismic sources are the Vernalis Fault approximately 20 miles west of the Project site (California Department of Conservation 2010).

Landslides usually occur in locations with steep slopes and unstable soils. The vicinity of the Project area has not yet been mapped by the Seismic Hazards Zonation Program to determine landslide potential. However, the majority of the Project area is situated on flat or very gently sloping topography, with slopes of 0-2 percent, indicating the potential for slope failure is minimal to low (NRCS 2020). Seismic-related failure, including liquefaction, is also a less than significant impact because the potential is believed to be slight due to the predominantly flat, low-seismicity of the Project site. No impacts from landslides are anticipated to occur within the Project area. The Project vicinity does not contain a geologic unit or soil that is unstable or that would become unstable as a result of the Project. An on-or off-site landslide, lateral spreading, subsidence, liquefaction or collapse are not anticipated.

b) Result in substantial soil erosion or the loss of topsoil?

Alternatives 1 through 3: Less than Significant. The NRCS Web Soil Survey was used to identify soils within the Project area. Specific soil units within the Project area include Timor loamy sand, 0 to 2 percent slopes, Veritas fine sandy loam, 0 to 2 percent slopes. Soils within the Project area are generally sandy and are moderately well drained (NRCS 2020). The Project area does not contain and is not directly adjacent to any water resources. The Project would result in ground disturbance; however, this activity is not anticipated to substantially impact topsoil or results in soil erosion.

c) Be located on a geologic unit or soil that is unstable, or that would become unstable as a result of the Project, and potentially result in on- or off-site landslide, lateral spreading, subsidence, liquefaction or collapse?

Alternatives 1 through 3: No Impact. As stated in discussion a). The Project alternatives will not be located on soil that is known to be unstable or would become unstable as a result of the Project, and potentially result in on- or off-site landslide, lateral spreading, subsidence, liquefaction, or collapse. No impacts would occur and therefore no mitigation is required.

d) Be located on expansive soil, as defined in Table 18-1-B of the Uniform Building Code (1994), creating substantial risks to life or property?

Alternative 1 through 3: No Impact. Refer to discussion a). The Project alternatives will not be located on expansive soils creating substantial risks to life or property. No impacts would occur and therefore no mitigation is required.

e) Have soils incapable of adequately supporting the use of septic tanks or alternative waste water disposal systems where sewers are not available for the disposal of waste water?

Alternative 1 through 3: No Impact. The Project alternatives will not utilize septic tanks or an alternative wastewater disposal system on the site. Therefore, the Project would not result in impacts on soils that would be incapable of adequately supporting septic systems, and no mitigation is required.

f) Directly or indirectly destroy a unique paleontological resource or site or unique geologic feature?

Alternative 1 through 3: No Impact. No findings of unique paleontological resources or sites or unique geological features were identified during the record search and cursory pedestrian survey within the Project area; therefore, no impacts are anticipated for the Project alternatives related to paleontological resources.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

No avoidance, minimization or mitigation measures are required relating to geology or soils.

FINDINGS

The Project would have Less Than Significant Impact to geology and soils.

2.8 GREENHOUSE GAS EMISSIONS

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Generate greenhouse gas emissions, either directly or indirectly, that may have a significant impact on the environment?			\boxtimes	
b) Conflict with an applicable plan, policy or regulation adopted for the purpose of reducing the emissions of greenhouse gases?			\boxtimes	

REGULATORY SETTING

While climate change has been a concern since 1988, as evidenced by the establishment of the United Nations and World Meteorological Organization's Intergovernmental Panel on Climate Change (IPCC), the efforts devoted to greenhouse gas (GHG) emissions reduction and climate change research and policy have increased dramatically in recent years. These efforts are primarily concerned with the emissions of GHG related to human activity that include CO_2 , CH_4 , NO_x , nitrous oxide, tetrafluoromethane, hexafluoroethane, sulfur hexafluoride, HFC-23 (fluoroform), HFC-134a (s, s, s, 2 –tetrafluoroethane), and HFC-152a (difluoroethane).

In 2002, with the passage of Assembly Bill 1493 (AB 1493), California launched an innovative and pro-active approach to dealing with GHG emissions and climate change at the state level. AB 1493 requires the CARB to develop and implement regulations to reduce automobile and light truck GHG emissions. These stricter emissions standards were designed to apply to automobiles and light trucks beginning with the 2009-model year; however, in order to enact the standards California needed a waiver from the EPA. The waiver was denied by the EPA in December 2007 and efforts to overturn the decision has been unsuccessful. See *California v. Environmental Protection Agency*, 9th Cir. Jul. 25, 2008, No. 08-70011. On January 26, 2009, it was announced that EPA would reconsider their decision regarding the denial of California's waiver. On May 18, 2009, President Obama announced the enactment of a 35.5 mpg fuel economy standard for automobiles and light duty trucks which will take effect in 2012. On June 30, 2009 EPA granted California the waiver. California is expected to enforce its standards for 2012 to 2016. The granting of the waiver will also allow California to implement even stronger standards in the future. The state is expected to start developing new standards for the post-2016 model years later this year.

On June 1, 2005, Governor Arnold Schwarzenegger signed EO S-3-05. The goal of this EO is to reduce California's GHG emissions to: 1) 2000 levels by 2010, 2) 1990 levels by the 2020 and 3) 80 percent below the 1990 levels by the year 2050. In 2006, this goal was further reinforced with the passage of AB 32, the Global Warming Solutions Act of 2006. AB 32 sets the same overall GHG emissions reduction goals while further mandating that CARB create a plan, which includes market mechanisms, and implement rules to achieve "real, quantifiable, cost-effective reductions of GHGs." EO S-20-06 further directs state agencies to begin implementing AB 32, including the recommendations made by the state's Climate Action Team.

With EO S-01-07, Governor Schwarzenegger set forth the low carbon fuel standard for California. Under this executive order, the carbon intensity of California's transportation fuels is to be reduced by at least 10 percent by 2020.

Climate change and GHG reduction is also a concern at the federal level; however, at this time, no legislation or regulations have been enacted specifically addressing GHG emissions reductions and climate change. California, in conjunction with several environmental organizations and several other states, sued to force the EPA to regulate GHG as a pollutant

under the CAA (Massachusetts vs. [EPA] et al., 549 U.S. 497 (2007). The court ruled that GHG does fit within the CAA's definition of a pollutant, and that the EPA does have the authority to regulate GHG. Despite the Supreme Court ruling, there are no promulgated federal regulations to date limiting GHG emissions.^[1]

On December 7, 2009, the EPA Administrator signed two distinct findings regarding GHG under section 202(a) of the CAA:

- Endangerment Finding: The Administrator finds that the current and projected concentrations of the six key well-mixed GHG--carbon dioxide (CO₂), methane (CH₄), nitrous oxide (N₂O), hydrofluorocarbons (HFCs), perfluorocarbons (PFCs), and sulfur hexafluoride (SF6)--in the atmosphere threaten the public health and welfare of current and future generations.
- Cause or Contribute Finding: The Administrator finds that the combined emissions of these well-mixed GHG from new motor vehicles and new motor vehicle engines contribute to the GHG pollution which threatens public health and welfare.

These findings do not themselves impose any requirements on industry or other entities. However, this action is a prerequisite to finalizing the EPA's GHG emission standards for lightduty vehicles, which were jointly enforced by EPA and the Department of Transportation's National Highway Safety Administration on September 15, 2009.




Figure 6: California Greenhouse Gas Inventory

Source: CARB 2019

According to Recommendations by the Association of Environmental Professionals on How to Analyze GHG Emissions and Global Climate Change in CEQA Documents (March 5, 2007), an

^[1] <u>http://www.epa.gov/climatechange/endangerment.html</u>

individual project does not generate enough GHG emissions to significantly influence global climate change. Rather, global climate change is a cumulative impact. This means that a project may participate in a potential impact through its incremental contribution combined with the contributions of all other sources of GHG. In assessing cumulative impacts, it must be determined if a project's incremental effect is "cumulatively considerable." See CEQA Guidelines sections 15064(i)(1) and 15130. To make this determination the incremental impacts of the Project must be compared with the effects of past, current, and probable future projects. To gather sufficient information on a global scale of all past, current, and future projects in order to make this determination is a difficult if not impossible task.

As part of the California Greenhouse Gas Emission for 2000 to 2017, CARB released an updated version of the GHG inventory for California (2019). **Figure 6** is a graph that shows the changes in total GHG emissions for California from 2000 to 2017.

DISCUSSION

The environmental consequences for greenhouse gas emissions are the same regardless of whether the Project is constructed in two phases or as one complete project.

a) Generate greenhouse gas emissions, either directly or indirectly, that may have a significant impact on the environment?

Alternative 1 through 3: Less Than Significant. The Project is not anticipated to increase traffic volumes, VMT or substantially change traffic patterns. The Project would realign Harlan Road to accommodate future, planned and approved, improvements to the interchange at I-5 and Roth Road. GHG emissions can be divided into those produced during construction and those produced during operations. GHG emissions produced during operations are those that result from potentially increased traffic volumes or changes in automobile speeds. **Table 7** displays estimated GHG operational emissions under all Project alternatives. In the year 2040, under the build alternative, the Project would result in approximately 0.007 CO₂ ton/peak hour. Overall, the Project would not substantially increase or change traffic volumes, vehicle miles traveled or traffic patterns, and therefore would have less than significant impacts on operational GHG emissions.

Year	CO2 tons/peak hour
Existing	0.122
2040 No Build Alternative	0.09
2040 Build Alternative	0.129
Source: EMFAC, CARB 2020	

Furthermore, construction GHG emissions include emissions produced as a result of material processing, emissions produced by on-site construction equipment, and emissions arising from traffic delays due to construction (**Table 8**). The Project would result in a temporary increase of 1.096 tons of GHG emissions during construction activities. However, work would be short-term in duration and is not anticipated to result in significant adverse construction GHG emissions. The emission of GHGs during construction of the proposed Project would be negligible and therefore less than significant.

Time Span	Existing	Future (Year 2040) No Build Build	
-	(Year 2019)		
Annually	1.096 tons	0.804 tons	1.420 tons
Based on CT-EMFAC Versi	on 6.0.0.29548 (2017)		

Table 8. Annual CO₂ Emission for the Project Alternatives

b) Conflict with an applicable plan, policy or regulation adopted for the purpose of reducing the emissions of greenhouse gases?

Alternative 1 through 3: Less than Significant. The Project is a planned project identified in the City of Lathrop General Plan and is in accordance with the RTP. The Project is not anticipated to have substantial impacts related to GHG emissions in a way that would conflict with applicable plans, policies or regulations adopted for reducing GHG. Impacts would be Less Than Significant.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

In addition to the Air Quality measures **AQ-1** through **AQ-3**, the following measures will also be included in the Project to further minimize the GHG emissions and potential climate change impacts from the Project. This minimization measure is required regardless of whether the Project is constructed in two phases or as one complete project.

GHG-1: The project would incorporate the use of energy-efficient lighting, such as LED traffic signals. LED bulbs cost \$60 to \$70 each, but last five to six years, compared to the one-year average lifespan of the incandescent bulbs previously used. The LED bulbs themselves consume 10 percent of the electricity of traditional lights, which will also help reduce the Project's CO2 emissions.

FINDINGS

The Project would have Less Than Significant Impacts relating to greenhouse gas emissions.

2.9 HAZARDS AND HAZARDOUS MATERIALS

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Create a significant hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials?			\boxtimes	
b) Create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment?			\boxtimes	
c) Emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school?				\boxtimes
d) Be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, would it create a significant hazard to the public or the environment?				\boxtimes
e) For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the Project result in a safety hazard or excessive noise for people residing or working in the Project area?				\boxtimes
f) Impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan?				\boxtimes
g) Expose people or structures to a significant risk of loss, injury or death involving wildland fires, including where wildlands are adjacent to urbanized areas or where residences are intermixed with wildlands?				\boxtimes

REGULATORY SETTING

Hazardous materials and hazardous wastes are regulated by many state and federal laws. These include not only specific statutes governing hazardous waste, but also a variety of laws regulating air and water quality, human health and land use.

Hazardous waste in California is regulated primarily under the authority of the federal Resource Conservation and Recovery Act of 1976 and the California Health and Safety Code. Other California laws that affect hazardous waste are specific to handling, storage, transportation, disposal, treatment, reduction, cleanup, and emergency planning.

Worker health and safety and public safety are key issues when dealing with hazardous materials that may affect human health and the environment. Proper disposal of hazardous material is vital if it is disturbed during Project construction.

AFFECTED ENVIRONMENT

This section presents results of an Initial Site Assessment (ISA) for properties associated with the Project. The purpose of the ISA is to evaluate the Subject Properties for the presence of Recognized Environmental Conditions (RECs) and/or Activity and Use Limitations (AULs), which are:

REC: "...the presence or the likely presence of any hazardous substances or petroleum hydrocarbons on the (Subject Property) that indicate an existing release, a past release, or a

material threat of a release of any hazardous substances or petroleum hydrocarbons into structures or into the ground, groundwater, or surface water of the subject property."

AUL: "...an explicit recognition by a federal, tribal, state, or local agency that residual levels of hazardous substances or petroleum hydrocarbons may be present on the property, and that unrestricted use of the property may not be acceptable."

The properties assessed for this ISA (Subject Properties) includes existing public right-of-way, and existing adjacent parcels throughout the length of the Project (**Appendix A**).

A summary of the published lists of known hazardous substance sites was provided by Environmental Data Resources (EDR). EDR reviewed standard federal, state, and local listings of known sites within a one-mile radius. A total of 17 properties within 1/8 mile of the Project area were listed on various non-release-related databases. Non-release-related databases refers to, "those that may report use, storage, or disposal of hazardous substances and/or petroleum products or other environmental conditions, but do not report releases of such" (Geocon 2020). Given this information, the 17 identified properties are unlikely to have caused a REC and therefore were no included in other analysis. **Table 9** and **Figure 7** below summarizes properties within ¼ of a mile of the Project site that potentially contain RECs and that are listed on release-related databases.

Location/Site Name	Listing Acronym	Approximate Distance from Site	Summary	Release Information/ Cleanup	Cleanup Status
Moorman Manufacturing 250 E. Roth Road Lathrop, CA 95330	HIST UST, SWEEPS UST, EMI	150 feet southeast (upgradient)	Leaks of underground gasoline and diesel storage tank	Not Reported	N/A
Beneto, Inc. 10842 Harlan Road French Camp, CA 95231	LUST, UST, CERS	850 feet north (downgradient)	Release of diesel in soil	Regulated by the Central Valley RWQCB, no anticipated RECs	Completed
Lathrop Quinones Army 400 East Roth Road French Camp, CA 95231	ENVIROSTOR, RCRA-SQG, FINDS, ECHO, CERS HAZ WASTE, CERS	1,033 feet east/southeast (upgradient)	Former vehicle maintenance facility	No contaminants detected; no further action required	N/A
Granite Construction 10500 Harland Road French Camp, CA 95231	LUST, EMI, HIST CORTESE, CERS	1,150 feet north/northeast (cross- gradient)	Release of gasoline into aquifer used for drinking water	Regulated by the Central Valley RWQCB, no anticipated RECs	Completed
Union Pacific Railroad	CPS-SLIC	Harlan Road, 1,000 feet east	Spill or release of oil/tar	Remediation was completed on August 31, 1988, no anticipated RECs	Completed

Table 9: REC Evidence

Location/Site Name	Listing Acronym	Approximate Distance from Site	Summary	Release Information/ Cleanup	Cleanup Status
So Pacific Railroad	SEMS- ARCHIVE	Harlan Road, 1,000 feet east	Not qualified for National Priorities List, no release noted	No anticipated RECs	N/A
Southern Pacific Transportation Co	CA BOND EXP. PLAN	Harlan Road, 1,000 feet east	Vault containing road oil, vault and soil was removed in 1988	No anticipated RECs	N/A
Defense Distribution Region west	CPS-SLIC	724 Acres at Roth Road	Leaking underground storage tanks, contaminants detected at concertation less than Maximum Contamination Levels	No anticipated RECs	N/A
Sedan Avenue Property	CPS-SLIC	Sedan Ave, 0.5 miles north	Location is 7 miles from the Project	No anticipated RECs	N/A

.....




Figure 7: Potential RECs in the Project Area

DISCUSSION

The environmental consequences for hazards and hazardous materials are the same regardless of whether the Project is constructed in two phases or as one complete project.

a) Create a significant hazard to the public or the environment through the routine transport, use, or disposal of hazardous materials?

Alternatives 1 through 3: Less than Significant. The Project alternatives would involve the use of heavy equipment for grading, hauling, and material handling. Use of this equipment may require the use of fuels and other common materials that have hazardous properties (e.g., fuels are flammable). These materials would be used in accordance with all applicable laws and regulations and, if used properly, would not pose a hazard to people, animals, or plants. All refueling of construction vehicles and equipment would occur within the Project limits. The use of hazardous materials would be temporary, and the Project would not include a permanent use or source of hazardous materials. By complying with measure **HAZ-1** the Project would have a less than significant impact from temporary construction equipment and activities.

b) Create a significant hazard to the public or the environment through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment?

Alternative 1 through 3: Less than Significant. Potential hazardous materials during construction activities can occur due to upset within the Project area. Potentially hazardous materials identified adjacent to the Project area include heavy metals in shallow soil from aerially deposited lead (ADL). Based on site observations and review of the database records search, REC's are not expected to occur at the Project site; however additional testing will be required to determine the potential presence and concentration of ADL at the Project site.

Naturally Occurring Asbestos

Naturally Occurring Asbestos (NOA) can occur in serpentine rock. The most common forms of NOA minerals are chrysotile, actinolite, and tremolite. A review of the "General Location Guide for Ultramafic Rocks in California – Areas likely to Contain Naturally Occurring Asbestos" (DOC Open-file Report 2000-19, 2000) indicated that NOA was not mapped on, or in the near vicinity of the Project area. No impacts from asbestos containing materials are anticipated.

Aerially Deposited Lead

ADL is known to be present within soils near major roadways in operation prior to 1980, when lead was discontinued as a gasoline additive in the State of California. Harlan Road was constructed in between 1968 and 1982, indicating the possibility for ADL to be present. Additional testing may be required to determine the potential presence and concentration of ADL at the Project site.

With any project that involves excavation, there is a possibility of encountering unknown hazardous contamination during construction. With the implementation measure **HAZ-2**, Project impacts from upset or accident conditions will be reduced to a less than significant.

c) Emit hazardous emissions or handle hazardous or acutely hazardous materials, substances, or waste within one-quarter mile of an existing or proposed school?

Alternative 1 through 3: No Impact. No schools are located within one-quarter mile of the Project site. No impact would occur.

d) Be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, would it create a significant hazard to the public or the environment?

Alternative 1 through 3: No Impact. Geotracker, SWRCB data management system for sites that may impact ground water quality, was used to find active hazardous waste sites within the Project vicinity. A review of Geotracker indicated that there is one site within the Project area (Beneto Inc., Loc Case #0001685) that contained hazardous waste. However, the cleanup status is complete, and the case is closed. No other known hazardous waste sites are located in the Project area. Other sites near the Project area are included in the record search by EDR and outlined in the ISA. Therefore, no impacts are anticipated regarding significant hazards to the public as a result of the Project alternatives.

e) For a project located within an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the Project result in a safety hazard or excessive noise for people residing or working in the Project area?

Alternative 1 through 3: No Impact. The Project alternatives would not result in a safety hazard for people residing or working in the Project area as the Project is not within an airport land use plan or within two miles of a public airport or public use airport. There is an airport approximately 1.4 miles south of the Project area operated by the Defense Depot San Joaquin Sharpe; however, this facility is not open to the public for air transport. Therefore, there would be no impact related to safety of the public in the Project area.

f) Impair implementation of or physically interfere with an adopted emergency response plan or emergency evacuation plan?

Alternative 1 through 3: No Impact. The Project alternatives will not impar or interfere with any adopted emergency response plans or emergency evacuation plans. Harlan Road would remain accessible to vehicles during construction. No road closures are anticipated and there would be no change in emergency access. Therefore, no impacts to emergency response plans or emergency evacuations plans are anticipated as a result of the Project.

g) Expose people or structures to a significant risk of loss, injury or death involving wildland fires, including where wildlands are adjacent to urbanized areas or where residences are intermixed with wildlands?

Alternative 1 through 3: No Impact. The Project alternatives would not expose people or structures to a significant risk of loss, injury, or death involving wildland fires, and no wildlands are adjacent to or within the Project area; therefore, no impacts are anticipated.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

The following avoidance, minimization and mitigation measures are required regardless of whether the Project is constructed in two phases or as one complete project.

- **HAZ-1:** As is the case for any project that proposes excavation, the potential exists for unknown hazardous contamination to be revealed during Project construction. For any previously unknown hazardous waste/material encountered during construction, the appropriate procedures, in accordance with state law, shall be followed.
- **HAZ-2:** Phase II testing will be conducted prior to the onset of construction to determine if aerially deposited lead, or other heavy metals, are present within the Project area.

The results of Phase II testing will determine if additional avoidance, minimization or mitigation measures are required.

FINDINGS

The Project would have Less Than Significant Impacts relating to hazards and hazardous materials.

2.10 HYDROLOGY AND WATER QUALITY

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Violate any water quality standards or waste discharge requirements or otherwise substantially degrade surface or ground water quality?			\boxtimes	
b) Substantially decrease groundwater supplies or interfere substantially with groundwater recharge such the Project may impede sustainable groundwater management of the basin?				\boxtimes
c) Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river or through the addition of impervious surfaces, in a manner which would:				
(i) result in substantial erosion or siltation on- or off-site;				\boxtimes
 (ii) substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or offsite; 				\boxtimes
(iii) create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff; or			\boxtimes	
(iv) impede or redirect flood flows?				\boxtimes
d) In flood hazard, tsunami, or seiche zones, risk release of pollutants due to Project inundation?				\boxtimes
e) Conflict with or obstruct implementation of a water quality control plan or sustainable groundwater management plan?			\boxtimes	

REGULATORY SETTING

Section 401 of the CWA requires water quality certification from the State Water Resources Control Board (SWRCB) or from a RWQCB when the project requires a CWA Section 404 permit. Section 404 of the CWA requires a permit from the USACE to discharge dredged or fill material into waters of the U.S.

Along with CWA Section 401, CWA Section 402 establishes the National Pollutant Discharge Elimination System (NPDES) permit for the discharge of any pollutant into waters of the U.S. The federal EPA has delegated administration of the NPDES program to the SWRCB and nine RWQCBs. The SWRCB and RWQCB also regulate other waste discharges to land within California through the issuance of waste discharge requirements under authority of the Porter-Cologne Water Quality Act.

The City, in collaboration with San Joaquin County, Tracy, Lodi, Manteca and Patterson prepared a Multi-Agency Post-Construction Stormwater Standards Manual to provide consistent guideline requirements under the Statewide Small Municipal Separate Storm Sewer System (MS4) NPDES Permit. The City was assigned Permit No. 2013-0001-DWQ.

AFFECTED ENVIRONMENT

<u>Hydrology</u>

The Project site falls within Central Valley, Region 5, of the RWQCB. The Project is within the Middle San Joaquin-Lower Merced-Lower Stanislaus watershed (USGS 2020). There are no hydrologic resources within or directly adjacent to the Project area. The Project area is highly developed and consistent mostly of impermeable surfaces.

Groundwater

The Project is located within the San Joaquin Valley groundwater basin and the San Joaquin Valley Tracy sub-basin. The San Joaquin Valley groundwater basin contains 9 sub-basins and lies within the San Joaquin River and Tulare Lake Hydrologic Regions covering approximately 8.88 million acres (Central Valley RWCQB 2006). Groundwater in this region is primarily used for agricultural and urban entities and accounts for approximately 48% of the groundwater used in California.

The Tracy sub-basin extends from Wilton south toward Firebaugh, encompassing Stockton, Modesto, Turlock and Merced. Depth of groundwater in the Project vicinity ranges from 3.84 to 21.23 feet above mean sea level and groundwater flow is predominantly towards the west/northwest (ISA 2020). The Tracy sub-basin is classified as a medium priority, by the California Department of Water Resources, due to poor water quality throughout the basin. Local agencies within the sub-basin, including Banta-Carbona Irrigation District, Byron-Bethany Irrigation District, City of Lathrop, City of Tracy, County of San Joaquin, Stewart Tract and West Side Irrigation District, are required to develop and implement a Groundwater Sustainability Plan by January 31, 2022. The plan must address the sustainability of the groundwater basin for longterm use.

<u>Flooding</u>

The Project area is within the Federal Emergency Management Agency (FEMA) Zone X, designated as an area with reduced flood risk due to a levee. A FIRMette map displaying FEMA Flood Zone classifications and flood extents within the Project area is included in **Attachment E**. A levee west of the Project area protects the area from flooding that may result from the San Joaquin River.

DISCUSSION

The environmental consequences for water quality are the same regardless of whether the Project is constructed in two phases or as one complete project.

a) Violate any water quality standards or waste discharge requirements or otherwise substantially degrade surface or ground water quality?

Alternative 1 through 3: Less than Significant. The Project alternatives will disturb greater than one acre, therefore a Construction Storm Water General Permit is required, consistent with Construction General Permit Order No. 2009-009-DWQ (amended 2012-0006-DWQ), issued by the SWRCB to address storm water runoff. The permit will address clearing, grading, grubbing, and disturbances to the ground, such as stockpiling, or excavation. This permit will also require the City to prepare and implement a Stormwater Pollution Prevention Plan (SWPPP) with the intent of keeping all products of erosion from moving off site into receiving waters. The SWPPP includes BMPs to prevent construction pollutants from entering storm water runoff. Measures **WQ-1** and **WQ-2** are required to ensure the Project grading will conform to SWRCB standards and in doing so will ensure the Project impacts will be less than significant.

b) Substantially decrease groundwater supplies or interfere substantially with groundwater recharge such the Project may impede sustainable groundwater management of the basin?

Alternative 1 through 3: No Impact. The Project alternatives would not directly or indirectly result in the construction of uses that would utilize groundwater supplies. Therefore, there would be no impact related to depletion of groundwater supplies or interference with groundwater recharge.

c) Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river or through the addition of impervious surfaces, in a manner which would:

(i) result in substantial erosion or siltation on- or off-site;

(ii) substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or offsite;

(iii) create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff; or

(iv) impede or redirect flood flows?

Alternative 1 through 3: Less Than Significant. The Project alternatives will create some impervious surfaces; however, a portion of the realignment area includes existing roadway and areas of compacted soil. Furthermore, the Project is proposed in the City's General Plan and the surrounding storm drains are proposed to accommodate additional stormwater runoff that may result from roadway improvements in the Project vicinity. The Project alternatives would not be changing the amount of existing impermeable surfaces within the Project area in a manner that would result in erosion or siltation on or offsite. Furthermore, impervious surfaces, as a result of the Project, would not increase the capacity of runoff water that would result in flooding or exceed the capacity of the existing stormwater drainage system. No flood flows would be impeded or redirected as a result of the Project.

d) In flood hazard, tsunami, or seiche zones, risk release of pollutants due to Project inundation?

Alternative 1 through 3: No Impact. The Project alternatives would not create a potential situation for inundation by sieche, tsunami, or mudflow. The Project is located in a predominantly flat landscape and is not located in proximity to a large body of water, and is not near coastal waters; therefore, no impacts would occur.

e) Conflict with or obstruct implementation of a water quality control plan or sustainable groundwater management plan?

Alternative 1 through 3: Less than Significant. The Project alternatives will not conflict with implementation of a water quality control plan. A sustainable groundwater management plan is being prepared for the San Joaquin Valley Tracy sub-basin. As noted above, the Project is subject to NPDES regulations since these improvements will exceed one acre. The Project would adhere to all applicable BMPs and water quality standards.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

Implementation of avoidance and minimization measures **WQ-1** and **WQ-2** will reduce the water quality impacts to **Less Than Significant**. These measures are required regardless of whether the Project is constructed in two phases or as one complete project.

- **WQ-1:** To conform to water quality requirements, the SWPPP must include the following:
 - Any necessary equipment washing must occur where the water cannot flow into drainage systems. The project specifications will require the contractor to operate under an approved spill prevention and clean-up plan;
 - Construction work must be conducted according to site-specific construction plans that minimize the potential for sediment input to groundwater;
 - Raw cement, concrete or concrete washings, asphalt, paint or other coating material, oil or other petroleum products, or any other substances that could be hazardous shall be prevented from contaminating the soil;
 - Any concrete rubble, asphalt, or other debris from construction must be taken to an approved disposal site.
- **WQ-2:** Contract specifications will include the following BMPs, where applicable, to reduce erosion during construction:
 - Implementation of the Project will require approval of a site-specific SWPPP that would implement effective measures to protect water quality, which may include a hazardous spill prevention plan and additional erosion prevention techniques;
 - Existing vegetation will be protected in place where feasible to provide an effective form of erosion and sediment control;
 - Stabilizing materials will be applied to the soil surface to prevent the movement of dust from exposed soil surfaces on construction sites as a result of wind, traffic, and grading activities.

FINDINGS

The Project would have Less Than Significant Impact relating to hydrology and water quality.

2.11 LAND USE AND PLANNING

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Physically divide an established community?				\boxtimes
b) Cause a significant environmental impact due to a conflict with any land use plan, policy, or regulation adopted for the purpose of avoiding or mitigating an environmental effect?				\boxtimes

AFFECTED ENVIRONMENT

The Project is located in a developed area in the City of Lathrop. The Project area is located in a commercial area, but is surrounded by residential, industrial and areas planned for development. To the east of the Project area there is a residential neighborhood, this is outside of City's limits, and to the west is I-5. According to City of Lathrop General Plan, Zoning Map, the Project area is categorized as highway commercial (**Figure 8**).

DISCUSSION

a) Physically divide an established community?

Alternative 1 through 3: No Impact. The Project alternatives would not divide an established community. The area is zoned for highway commercial, although there are a few scattered residencies in the southern and northern portion of the Project area. However, these residencies do not function as an established community due to the surrounding land use. The proposed Project alternatives would realign Harlan Road but would not result in a division of an established community. No impacts would occur and therefore no mitigation is required.

b) Cause a significant environmental impact due to a conflict with any land use plan, policy, or regulation adopted for the purpose of avoiding or mitigating an environmental effect?

Alternative 1 through 3: No Impact. The Project alternatives do not conflict with any applicable land use plan, policy, or regulation of an agency adopted for the purpose of avoiding or mitigating an environmental effect. Therefore, the Project will not impact a land use plan, policy, or regulation.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

No impacts to land use and planning resources are anticipated as a result of the Project; therefore, no avoidance, minimization, and/or mitigation measures will be required.

FINDINGS

The Project would have **No Impacts** relating to land use and planning.

THIS PAGE INTENTIONALLY LEFT BLANK

.....




Figure 8 City of Lathrop General Plan Zoning Map Harlan Road Realignment Project City of Lathrop, San Joaquin County, California

2.12 MINERAL RESOURCES

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state?				\boxtimes
b) Result in the loss of availability of a locally-important mineral resource recovery site delineated on a local general plan, specific plan or other land use plan?				\boxtimes

AFFECTED ENVIRONMENT

The City of Lathrop General Plan classifies certain areas for conservation of mineral resources (City of Lathrop 1991). The Project area is not within a mineral resource area. Furthermore, according to the San Joaquin General Plan (San Joaquin County 2016), minerals found within the County include: sand and gravel aggregate with limited mining of peat, gold and silver. In the past, gold deposits have been found throughout the County's rivers and creeks. However, these deposits were dredge for gold during the gold rush in the 1840's. Currently, sand and gravel deposits constitute the only commercially significant extractive mineral resource in the region.

DISCUSSION

a) Result in the loss of availability of a known mineral resource that would be of value to the region and the residents of the state?

Alternative 1 through 3: No Impact. According to the City of Lathrop General Plan and the San Joaquin County General Plan (City of Lathrop 1991, San Joaquin County 2016), the Project area does not have any known mineral resources that would be of value to the region and the residents of the state; therefore, the Project alternatives will have no impact to known mineral resources, and no mitigation is required.

b) Result in the loss of availability of a locally-important mineral resource recovery site delineated on a local general plan, specific plan or other land use plan?

Alternative 1 through 3: No Impact. According to the City of Lathrop General Plan and the San Joaquin General Plan (City of Lathrop 1991, San Joaquin County 2016), the Project area does not have any areas that are listed as a locally-important mineral resource recovery site; therefore, the Project alternatives will have no impact and no mitigation is required.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

No avoidance, minimization, and/or mitigation measures will be required.

FINDINGS

The Project would have **No Impact** relating to mineral resources.

2.13 NOISE

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact	
a) Generation of a substantial temporary or permanent increase in ambient noise levels in the vicinity of the Project in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies?		\boxtimes			
b) Generation of excessive groundborne vibration or groundborne noise levels?		\boxtimes			
c) For a project located within the vicinity of a private airstrip or an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the Project expose people residing or working in the Project area to excessive noise levels?				\boxtimes	

REGULATORY SETTING

State Regulations

Section 216 of the California Streets and Highways Code

The proposed Project is subject to Section 216 of the California Streets and Highways Code. Section 216 of the California Streets and Highways Code relates to the noise effects of a proposed freeway project on public and private elementary and secondary schools. Under Section 216(c), a noise impact occurs if, as a result of a proposed freeway project, noise levels exceed 52 decible-A-weighted (dBA) A-weighted Equivalent Sound Level ($L_{eq}(h)$) in the interior of public or private elementary or secondary classrooms, libraries, multipurpose rooms, or spaces.

If a project results in a noise impact under this code, noise abatement must be provided to reduce classroom noise to a level that is at or below 52 dBA- $L_{eq}(h)$. Under Section 216(d), if the noise levels generated from freeway and roadway sources exceed 52 dBA- $L_{eq}(h)$ prior to the construction of the proposed freeway project, then noise abatement must be provided to reduce the noise to the level that existed prior to construction of the project.

Local Regulations

City of Lathrop General Plan Hazard Management Element

General Plan Noise Policy 1: Areas within the City shall be designated as noise-impacted if exposed to existing or projected future noise levels exterior to buildings exceeding 60 dB CNEL.

City of Lathrop Municipal Code

The following restrictions from the Lathrop Municipal Code (Title 8 Health and Safety, Chapter 8.20 Noise, Section 8.20.110) applies to construction noise:

It shall be unlawful for any person within a residential zone or within a radius of five hundred (500) feet therefrom, to operate equipment or perform any outside construction or repair work on buildings, structures or projects or to operate any pile driver, power shovel, pneumatic hammer, derrick, power hoist, or any other construction type device between the hours of ten p.m. of one day and seven a.m. of the next day, or eleven p.m. and nine a.m. Fridays, Saturdays and legal holidays, in such a manner that a reasonable person of normal sensitiveness residing in the area is caused discomfort or annoyance unless beforehand a permit therefore has been duly obtained from the office or body of the city having the function to issue permits of this kind. No permit shall be required to perform emergency work as defined in Sections 8.20.010 through 8.20.040. (Prior

code § 99.40).

AFFECTED ENVIRONMENT

The Project area is within a commercial area, adjacent to I-5 within the City of Lathrop. The noise environment near the Project is dominated by traffic sources. The primary existing noise sources in the Project area are transportation facilities. Traffic traveling on Harlan Road and I-5 is the main source of traffic noise in the Project vicinity.

Table 10 shows the existing noise levels in the Project area. **Table 10** also lists the location and type of development for each modeled receiver location. The ambient noise levels measured were used to establish the existing noise level at two locations within the Project area.

Receiver No.	Location	Type of Land Use	Number of Dwelling Units	Modeled Exterior Noise Level (CNEL)
R1	11674 Harlan Road	Residential	1	81
R2	11616 Harlan Road	Commercial	1	83
R3		Residential	1	83
R4		Residential	1	82
R5		Residential	1	75
R6		Residential	1	71
R7		Residential	1	75
R8		Residential	1	61
R9		Residential	1	60
R10		Residential	1	59
R11	Lathrop Sands Mobile Home	Residential	1	65
R12	Park	Residential	1	74
R13	11550 Harlan Road	Residential	1	70
R14		Residential	1	70
R15		Residential	1	65
R16		Residential	1	61
R17		Residential	1	65
R18		Residential	1	66
R19		Residential	1	60
R20		Residential	1	62
R21		Residential	1	70
R22	11265-1109 Harlan Road	Residential	1	70
R23	11265-1109 Harlan Road	Residential	1	75
R24	10879-11145 Harlan Road	Residential	1	64

Table 10. Existing Exterior Noise Levels

Source: Dokken Engineering NSR, June 2020

As shown in **Table 10**, exterior noise levels at every analyzed receiver are currently exposed to noise levels exceeding the City of Lathrop 60 dBA CNEL exterior noise level threshold and are considered impacted receivers.

It is assumed that standard residential design (with windows closed) will provide no more than 20 dBA of attenuation. **Table 11** shows the estimated interior noise levels at each noise receiver location representing a residence with exterior-to-interior noise attenuation.

Receiver No.	Location	Type of Land Use	Number of Dwelling Units	Modeled Interior Noise Level (CNEL)
R1	11674 Harlan Road	Residential	1	61
R2	11616 Harlan Road	Commercial	1	63
R3		Residential	1	63
R4		Residential	1	62
R5		Residential	1	55
R6		Residential	1	51
R7		Residential	1	55
R8		Residential	1	41
R9		Residential	1	43
R10		Residential	1	43
R11	Lathrop Sands Mobile Home	Residential	1	45
R12	Park	Residential	1	54
R13	11550 Harlan Road	Residential	1	50
R14		Residential	1	50
R15		Residential	1	45
R16		Residential	1	41
R17		Residential	1	45
R18		Residential	1	46
R19		Residential	1	40
R20		Residential	1	42
R21		Residential	1	50
R22	11265-1109 Harlan Road	Residential	1	50
R23	11265-1109 Harlan Road	Residential	1	55
R24	10879-11145 Harlan Road	Residential	1	44

Table 11. Existing Interior Noise Levels

DISCUSSION

The environmental consequences regarding noise impacts are the same regardless of whether the Project is constructed in two phases or as one complete project.

a) Generation of a substantial temporary or permanent increase in ambient noise levels in the vicinity of the Project in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies?

Alternative 1 through 3: Less than Significant with Mitigation Incorporated. A Noise Study Report, prepared for the Project, indicated that traffic noise levels are anticipated to increase ambient exterior and interior noise levels under future build conditions by 1 to 3 dB for all three build alternatives (**Appendix B**). The future 2040 traffic noise modeling results, summarized in **Table 10**, indicate that exterior noise levels would range between 61 dBA Community Noise Equivalent Level (CNEL) and 85 dBA CNEL without the proposed Project. Noise levels would increase by approximately 2 dB CNEL over the next twenty years in the Project area due to traffic growth.

Exterior noise levels under the Project alternatives would range between 61 dBA and 84 dBA CNEL in 2040. The new posted speed limit on Harlan Road would be reduced to 25 mph from 45 miles per hours (mph), which would potentially help alleviate some of the traffic noise impact. Nevertheless, noise level increases would range from 1 to 3 dB due to traffic growth and the realignment of Harlan Road placing traffic noise closer to existing residences. Exterior noise levels at every analyzed receiver would continue to be exposed to noise levels exceeding the City of Lathrop 60 dBA CNEL exterior noise level threshold under each of the three build alternatives and would be considered impacted receivers.

It is assumed that standard residential design (with windows closed) will provide no more than 20 dBA of attenuation. **Table 12** shows the estimated exterior noise levels at each noise receiver location representing a residence with exterior-to-interior noise attenuation for Phase I and Phase II under each of the three Project alternatives. The future 2040 build traffic noise modeling results for Phase I and all three build alternatives under Phase II are summarized in **Table 13** indicates that interior noise levels would range between 41 dBA CNEL and 63 dBA CNEL without the proposed Project.

Future interior noise level increases would range from 1 to 3 dB due to traffic growth and the realignment of Harlan Road placing traffic noise closer to existing residences.

Per Section 216 of the California Streets and Highways Code, "under Section 216(d), if the noise levels generated from freeway and roadway sources exceed 52 dBA-Leq(h) prior to the construction of the proposed freeway project, then noise abatement must be provided to reduce the noise to the level that existed *prior* to construction of the project."

The Project would increase noise levels by 3dBA, however through the use of rubberized asphalt noise levels would be decreased by at least 3 dBA.; therefore, reflecting the existing noise conditions within the Project vicinity. With the incorporation of **NOI-1**, listed below, impacts are expected to be less than significant with mitigation incorporated.

THIS PAGE LEFT INTENTIONALLY BLANK

.....

.....

Receiver No.	Noise Level for Existing (2019) (dBA CNEL)	Predicted Noise Level for Future No Build (2040) (dBA CNEL)	Interim Phase I (2040) (dBA CNEL)	Predicted Noise Level for Future Build Alt. 1 (2040) (dBA CNEL)	Predicted Noise Level for Future Build Alt. 2 (2040) (dBA CNEL)	Predicted Noise Level for Future Build Alt. 3 (2040) (dBA CNEL)
R1	81	83	83	83	83	83
R2	83	84	84	84	84	84
R3	83	85	84	84	84	84
R4	82	84	83	83	83	83
R5	75	77	76	76	76	76
R6	71	73	73	73	73	73
R7	75	77	77	77	77	77
R8	61	63	63	63	63	63
R9	60	62	62	62	62	62
R10	59	61	61	61	61	61
R11	65	67	67	67	67	67
R12	74	76	77	77	77	77
R13	70	72	73	73	73	73
R14	70	72	73	73	73	73
R15	65	67	68	68	68	68
R16	61	63	64	64	64	64
R17	65	67	67	67	67	67
R18	66	68	68	68	68	68
R19	60	62	63	63	63	63
R20	62	64	64	64	64	64
R21	70	72	72	72	72	72
R22	70	72	72	72	72	72
R23	75	77	77	77	77	77
R24	64	65	65	-	66	-

Table 12. Comparison of Estimated Exterior Noise Levels in Future (2040)

Receiver No.	Noise Level for Existing (2019) (dBA CNEL)	Predicted Noise Level for Future No Build (2040) (dBA CNEL)	Interim Phase I (2040) (dBA CNEL)	Predicted Noise Level for Future Build Alt. 1 (2040) (dBA CNEL)	Predicted Noise Level for Future Build Alt. 2 (2040) (dBA CNEL)	Predicted Noise Level for Future Build Alt. 3 (2040) (dBA CNEL)
R1	61	63	63	63	63	63
R2	63	64	64	64	64	64
R3	63	65	64	64	64	64
R4	62	64	63	63	63	63
R5	55	57	56	56	56	56
R6	51	53	53	53	53	53
R7	55	57	57	57	57	57
R8	41	43	43	43	43	43
R9	40	42	42	42	42	42
R10	39	41	41	41	41	41
R11	45	47	47	47	47	47
R12	54	56	57	57	57	57
R13	50	52	53	53	53	53
R14	50	52	53	53	53	53
R15	45	47	48	48	48	48
R16	41	43	44	44	44	44
R17	45	47	47	47	47	47
R18	46	48	48	48	48	48
R19	40	42	43	43	43	43
R20	42	44	44	44	44	44
R21	50	52	52	52	52	52
R22	50	52	52	52	52	52
R23	55	57	57	57	57	57
R24	44	45	46	-	46	-

Table 13. Comparison of Estimated Interior Noise Levels in Future	(2040)

b) Exposure of persons to or generation of excessive groundborne vibration or groundborne noise levels?

Alternative 1 through 3: Less than Significant. During construction of the Project, noise from construction activities may intermittently dominate the noise environment in the immediate area of construction. These temporary construction activities within the Project vicinity may increase groundborne vibration; however, construction impacts would be temporary and would be limited to daytime hours between the hours allowed by the City of Lathrop Municipal Code unless allowed otherwise by a permit issued by the City of Lathrop. **Table 14** summarizes vibration levels produced by construction equipment that is commonly used on roadway construction projects. Construction equipment is expected to generate noise levels ranging from 70 to 90 dB at a distance of 50 feet, and noise produced by construction equipment would be reduced over distance at a rate of about 6 dB per doubling of distance.

(in/sec)
-

Table 14. Vibration Source Levels for Construction Equipment

Source: Federal Transit Administration, 2006. See also:

<u>http://www.fhwa.dot.gov/environment/noise/construction_noise/handbook/handbook09.cfm</u> Peak particle velocity (PPV)

During construction, the equipment with the greatest potential for vibration impacts would be generated by vibratory rollers, which would compact soil over where the new realignment would occur. Vibratory rollers could cause continuous vibration levels up to 0.210 PPV to buildings within 25 feet of Harlan Road during construction. None of the buildings within 25 feet of where soil compaction would occur are considered extremely fragile, fragile, or historic buildings. The majority of buildings in the project vicinity that would be impacted are older residential and commercial use structures. Therefore, no buildings would be exposed to potentially damaging construction vibration levels from vibratory rollers exceeding the thresholds shown in **Table 15**.

Adherence to Chapter 8.20 of the Lathrop Municipal Code, any obtained construction noise permit issued by the City of Lathrop, and standard construction BMPs would ensure construction noise impacts are reduced to less than significant.

	Maximum PPV (in/sec)			
Structure and Condition	Transient Sources	Continuous/Frequent Intermittent Sources		
Extremely fragile historic buildings, ruins, ancient monuments	0.12	0.08		
Fragile buildings	0.2	0.1		
Historic and some old buildings	0.5	0.25		
Older residential structures	0.5	0.3		
New residential structures	1.0	0.5		
Modern industrial/commercial buildings	2.0	0.5		

Table 15. Guideline Vibration Damage Potential Threshold Criteria

Note: Transient sources create a single isolated vibration event, such as blasting or drop balls. Continuous/frequent intermittent sources include impact pile drivers, pogo-stick compactors, crack-and-seat equipment, vibratory pile drivers, and vibratory compaction equipment.

Source: Caltrans Transportation- and Construction-Induced Vibration Guidance Manual, June 2004

c) For a project located within the vicinity of a private airstrip or an airport land use plan or, where such a plan has not been adopted, within two miles of a public airport or public use airport, would the Project expose people residing or working in the Project area to excessive noise levels?

Alternative 1 through 3: No Impact. The proposed Project is located within two miles of a public or private airport or airstrip. The nearest air operations are the Sharpe Facility, San Joaquin Depot and Stockton Airport, located less than 1 mile southeast and approximately 3 miles northeast, respectively, of the proposed Project site. The proposed Project would result in no impacts to sensitive receptors from public or public use airports or private airstrips.

AVOIDANCE, MINIMIZATION, AND/OR ABATEMENT MEASURES

The following measure for noise impacts is required regardless of whether the Project is constructed in two phases or as one complete project.

NOI-1: Rubberized and/or open grade asphalt will be used on the southern portion of Harlan Road under all alternatives during Phase 1 and on the northern portion of Harlan Road, during Phase 2, if Alternative 2 is selected.

FINDINGS

The Project would have **Less Than Significant Impacts with Mitigation Incorporated** relating to noise.

2.14 POPULATION AND HOUSING

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Induce substantial population growth in an area, either directly (for example, by proposing new homes and businesses) or indirectly (for example, through extension of roads or other infrastructure)?			\boxtimes	
b) Displace substantial numbers of existing housing, necessitating the construction of replacement housing elsewhere?		\boxtimes		

REGULATORY SETTING

CEQA also requires the analysis of a project's potential to induce growth. CEQA guidelines, Section 15126.2(d), require that environmental documents "...discuss the ways in which the Project could foster economic or population growth, or the construction of additional housing, either directly or indirectly, in the surrounding environment..."

AFFECTED ENVIRONMENT


The Project area is zoned for commercial and highway use (City of Lathrop 1991); however, there are scattered residential properties. Under all proposed Project alternatives, two parcels containing residencies, located south of Roth Road, would require full property acquisition during Phase I of the Project, which would require owners/tenants to relocate as a result of the Project's right-of-way needs. Additionally, Alternatives 1 and 3 would also impact one residency north of Roth Road during Phase II of the Project (**Figure 9**). **Table 16** below summarizes the potential properties that may require relocation under the different Project alternatives.

	Number of		Impacts	
APN	Residencies Requiring Relocation	General Location	Alternative 1 and 3	Alternative 2
19602012	1	Approximately 730 feet south of Roth Road	Full acquisition and relocation during Phase I	Full acquisition and relocation during Phase I
19602010	2	Approximately 470 feet south of Roth Road	Full acquisition and relocation during Phase I	Full acquisition and relocation during Phase I
19333031	1	Approximately 600 feet north of Roth Road	Full acquisition and relocation during Phase II	No acquisition or relocation anticipated during Phase II. Access to the property would be maintained at its existing location from Harlan Road.

Table 16. Proposed Property Relocations

THIS PAGE LEFT INTENTIONALLY BLANK

.....



	1 inch = 250) feet			
)	250	500	750	1,000	1,250 Feet

Figure 9 Potential Property Relocations

Harlan Road Realignment Project City of Lathrop, San Joaquin County, California

DISCUSSION

The environmental consequences for population and housing are the same regardless of whether the Project is constructed in two phases or as one complete project.

a) Induce substantial population growth in an area, either directly (for example, by proposing new homes and businesses) or indirectly (for example, through extension of roads or other infrastructure)?

Alternatives 1 through 3: Less Than Significant. Proposed developments projects within San Joaquin County, the City of Manteca and the City of Lathrop will cause the I-5 interchange at Roth Road to operate at an unacceptable level. The Project is Phase 1 of the planned interchange improvements. The proposed Project alternatives would widen and realign Harlan Road to allow space for future improvements to the interchange. The zoning in the Project area is designated as highway and commercial (City of Lathrop General Plan 1991). The Project is in accordance with all local and regional general plans and proposed development for the vicinity.

b) Displace substantial numbers of existing housing, necessitating the construction of replacement housing elsewhere?

Alternative 1 through 3: Less Than Significant with Mitigation. Under Alternative 1 and 3, the Project would displace three residencies on two parcels south of Roth Road, in the southern portion of the Project area, as well as the one residency on one parcel north of Roth Road, in the northern portion of the Project area. Alternative 1 would have the greatest impact on the property north of Roth Road, whereas Alternative 3 would only impact a portion of the property; however, due to the location of the house, the residency would still be displaced.

Under Alternative 2, the Project would displace three residencies on two parcels south of Roth Road, in the southern portion of the Project area, but avoid the residency north of Roth Road, in the northern portion of the Project area.

The Project may require two construction phases due to available funding. If construction phases are required, Phase I would consist of all roadway improvements south of Roth Road as well as improvements along Roth Road. Phase II would include roadway improvements north of Roth Road. During Phase I, the stop sign at the existing Harlan/Roth Road would be maintained, but with the relocation of the south leg of Harlan Road to the new proposed signalized intersection.

The Project would have less than significant impacts to displacement of housing through the incorporation of measure **POP-1**.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

The Project would have less than significant impacts with mitigation incorporated relating to population and housing under the proposed Project alternatives. Alternative 1 and 3, would displace a total of four residencies and Alternative 2 would displace a total of three residencies. This measure is required regardless of whether the Project is constructed in two phases or as one complete project.

POP-1:

The Project shall comply with the Uniform Relocation Assistance Real Property Acquisition Policies Act of 1970, as amended in 1987. Relocation advisory assistance shall be provided to any person, business, farm, or nonprofit organization relocated as a result of acquisition of real property for public use for the Project.

FINDINGS

The Project would have Less Than Significant with Mitigation Incorporated relating to population and housing.

2.15 PUBLIC SERVICES

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Would the Project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for any of the public services:				
Fire protection?				\boxtimes
Police protection?				\square
Schools?				\boxtimes
Parks?				\boxtimes
Other public facilities?				\boxtimes

AFFECTED ENVIRONMENT

The nearest fire station, Lathrop-Manteca Fire Protection District, is located approximately 2.3 miles south of the Project area. The nearest police station, Lathrop Police Department, is located approximately 2.5 miles south of the Project area. The nearest school, Lathrop Elementary School, is located approximately 2.8 miles south of the Project area in the City of Lathrop. The nearest park, Apolinar Sangalang Park, is approximately 1.2 miles south of the Project area.

DISCUSSION

a) Would the Project result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times or other performance objectives for any of the public services: fire protection, police protection, schools, parks, and/or other public facilities?

Alternative 1 through 3: No Impact. There are no public services, including police and fire departments, schools, parks or other public services, located within the Project area. Project construction would not restrict access to any parks or other public facilities. Therefore, the Project alternatives will have no impact to these public services.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

The Project will have no impacts relating to public services; therefore, no avoidance, minimization, and/or mitigation measures will be required.

FINDINGS

The Project would have **No Impacts** relating to public services.

2.16 RECREATION

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Would the Project increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated?				\boxtimes
b) Does the Project include recreational facilities or require the construction or expansion of recreational facilities which might have an adverse physical effect on the environment?				\boxtimes

AFFECTED ENVIRONMENT

As stated in the previous section, the nearest park, Apolinar Sangalang Park, is approximately 1.2 miles south of the Project area.

DISCUSSION

a) Would the Project increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated?

Alternative 1 through 3: No Impact. The Project alternatives would not increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated. Project construction would not impact any neighborhoods, regional parks or other recreational facilities. No impacts would occur.

b) Does the Project include recreational facilities or require the construction or expansion of recreational facilities which might have an adverse physical effect on the environment?

Alternative 1 through 3: No Impact. The Project does not include other recreational facilities, nor does it require the construction or expansion of other recreational facilities; therefore, no impact would occur as a result of the Project.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

No impact to recreation facilities would occur; therefore, no avoidance, minimization, and/or mitigation measures will be required.

FINDINGS

The Project would have **No Impact** relating to recreation.

2.17 TRANSPORTATION/TRAFFIC

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Conflict with a program, plan, ordinance, or policy addressing the circulation system, including transit, roadway, bicycle and pedestrian facilities?			\boxtimes	
b) Would the Project conflict or be inconsistent with CEQA Guidelines section 15064.3, subdivision (b)?				\boxtimes
 c) Substantially increase hazards due to a geometric design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)? 				\boxtimes
d) Result in inadequate emergency access?				\boxtimes

AFFECTED ENVIRONMENT

Harlan Road, within the Project area, is considered an arterial road, meaning this roadway primarily carries traffic from collector roads to freeways or expressways. As identified in the City's General Plan, an arterial road is constructed for 4-6 lanes of traffic. According to City of Lathrop General Plan, the Project is a planned improvement as part of the improvements from Roth Road to Airport Way.

DISCUSSION

The environmental consequences for transportation and traffic are the same regardless of whether the Project is constructed in two phases or as one complete project.

a) Conflict with a program, plan, ordinance, or policy addressing the circulation system, including transit, roadway, bicycle and pedestrian facilities?

Alternative 1 through 3: Less Than Significant. The Project would not conflict with an applicable plan, ordinance or policy establishing measures of effectiveness for the performance of the circulation system. This takes into account all modes of transportation including mass transit and non-motorized travel and relevant components of the circulation system, including but not limited to intersections, streets, highways and freeways, pedestrians and bicycle paths, and mass transit. The Project is listed in the City's General Plan.

The proposed Project along Harlan Road will include three travel lanes and a center two-way left turn lane south of Roth Road and two travel lanes with a center lane north of Roth Road. This lane configuration will incorporate the ultimate improvements necessary for Harlan Road within the Project area. Harlan Road will conform to the existing section at the beginning and end of the realigned portion; ultimate Harlan Road improvements past these conforms will take place as a future City project.

The Project may require two construction phases due to available funding. If construction phases are required, Phase I would consist of roadway improvements south of Roth Road and Phase II would include roadway improvements north of Roth Road. During Phase I the stop sign at the existing Harlan/Roth Road would be maintained, but with the relocation of the south leg to a new signalized intersection.

Vehicle access along Harlan Road would be modified during construction, but no road closures are anticipated. The implementation of **TRA-1** would reduce Project impacts during constriction related to roadway, bicycle, pedestrian and other transportation facilities to less than significant.

b) Would the Project conflict or be inconsistent with CEQA Guidelines section 15064.3, subdivision (b)?

Alternative 1 through 3: Less Than Significant. CEQA Guidelines section 15064.3 describes specific considerations for evaluating a project's transportation impacts. Generally, vehicle miles traveled is the most appropriate measure of transportation impacts. For the purposes of this section, "vehicle miles traveled" refers to the amount and distance of automobile travel attributable to a project. Subdivision (b) defines the criteria for analyzing transportation impacts. A daily operational emissions analysis was conducted for the Project (see Table 3 in Section 2.3 for results). Per section 15064.3 (b)(2), transportation projects that have no impact on vehicle miles traveled are presumed to cause a less than significant transportation impact, and as there will be no changes in the roadway, the Project will have **No Impact** to vehicle miles traveled.

c) Substantially increase hazards due to a geometric design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)?

Alternative 1 through 3: No Impact. The Project would not substantially increase hazards due to a design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment). Design features would comply with City and County standards as appropriate. The Project alternatives would not increase hazards due to design features or incompatible uses; therefore, no impact would occur, and no mitigation is required.

d) Result in inadequate emergency access?

Alternative 1 through 3: No Impact. The Project alternatives would realign Harlan Road and increase the width of the road, resulting in improved access for emergency vehicles. Harlan Road would remain accessible to vehicles during construction. No road closures are anticipated and there would be no change in emergency access. Therefore, no impacts to emergency access are anticipated.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

The following measure is required whether the Project is constructed in two phases or as one complete project.

TRA-1: Temporary impacts to traffic flow as a result of construction activities would be minimized through signage and a traffic control plan.

FINDINGS

The Project would have Less Than Significant incorporated relating to transportation/traffic.

2.18 TRIBAL CULTURAL RESOURCES

TRIBAL CULTURAL RESOURCES:

Would the Project cause a substantial adverse change in the significance of a tribal cultural resource, defined in Public Resources Code section 21074 as either a site, feature, place, cultural landscape that is geographically defined in terms of the size and scope of the landscape, sacred place, or object with cultural value to a California Native American tribe, and that is:

a) Listed or eligible for listing in the California Register of Historical Resources, or in a local register of historical resources as defined in Public Resources Code section 5020.1(k), or

b) A resource determined by the lead agency, in its discretion and supported by substantial evidence, to be significant pursuant to criteria set forth in subdivision (c) of Public Resources Code Section 5024.1. In applying the criteria set forth in subdivision (c) of Public Resource Code Section 5024.1, the lead agency shall consider the significance of the resource to a California Native American tribe.

Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
		\boxtimes	
		\boxtimes	

REGULATORY SETTING

Effective July 1, 2015, CEQA was revised to include early consultation with California Native American tribes and consideration of tribal cultural resources (TCRs). These changes were enacted through Assembly Bill 52 (AB 52). By including TCRs early in the CEQA process, AB 52 intends to ensure that local and Tribal governments, public agencies, and project proponents would have information available, early in the project planning process, to identify and address potential adverse impacts to TCRs. CEQA now establishes that a "project with an effect that may cause a substantial adverse change in the significance of a TCR is a project that may have a significant effect on the environment" (PRC § 21084.2).

To help determine whether a project may have such an adverse effect, the PRC requires a lead agency to consult with any California Native American tribe that requests consultation and is traditionally and culturally affiliated with the geographic area of a proposed project. The consultation must take place prior to the determination of whether a negative declaration, mitigated negative declaration, or environmental impact report is required for a project (PRC § 21080.3.1). Consultation must consist of the lead agency providing formal notification, in writing, to the tribes that have requested notification or proposed projects within their traditionally and culturally affiliated area. AB 52 stipulates that the NAHC shall assist the lead agency in identifying the California Native American tribes that are traditionally and culturally affiliated within the project area. If the tribe wishes to engage in consultation on the project, the tribe must respond to the lead agency within 30 days of receipt of the formal notification. Once the lead agency receives the tribe's request to consult, the lead agency must then begin the consultation process within 30 days. If a lead agency determines that a project may cause a substantial adverse change to TCRs, the lead agency must consider measures to mitigate that impact. Consultation concludes when either: 1) the parties agree to measures to mitigate or avoid a significant effect, if a significant effect exists, on a TCR, or 2) a party, acting in good faith and after reasonable effort, concludes that mutual agreement cannot be reached (PRC § 21080.3.2). Under existing law, environmental documents must not include information about the locations of an archaeological site or sacred lands or any other information that is exempt from public disclosure pursuant to the Public Records act. TCRs are also exempt from disclosure. The term "tribal cultural resource" refers to either of the following:

Sites, features, places, cultural landscapes, sacred places, and objects with cultural value to a California Native American tribe that are either of the following:

- Included or determined to be eligible for inclusion in the California Register of Historical Resources
- Included in a local register of historical resources as defined in subdivision (k) of California Public Resources Code (PRC) Section 5020.1
- A resource determined by a California lead agency, in its discretion and supported by substantial evidence, to be significant pursuant to criteria set forth in subdivision (c) of the PRC Section 5024.1.

AFFECTED ENVIRONMENT

The Area of Potential Effects (APE) was established as the area of direct and indirect effects and includes all proposed construction areas associated with roadway realignments (including the three alternatives in the northern portion of the Project), potential staging / contractor use areas, and utility relocations. Approximately 46-acres in area, the APE is identical to the Project Area depicted in **Figure 3**.

Efforts to identify cultural resources within or adjacent to the APE included background research, a record search with the California Historical Resources Information System, Central California Information Center (CCIC) at California State University Stanislaus, consultation with the Native American Heritage Commission (NAHC), and an archaeological pedestrian surface survey. No cultural resources were identified within or adjacent the APE (refer to *Section 2.5* of this document for greater detail on these efforts).

On March 11, 2020, initial consultation letters were mailed to the Native American tribal governments who have previously submitted in writing to the County a request to be notified of projects within their traditionally and culturally affiliated area, pursuant to PRC Section 21080.3.1. The letters provided a summary of the project and requested information regarding comments or concerns the tribal governments might have about the project and whether any TCRs would be affected by implementation of the project. Letters were sent to Katherine Perez, Chairperson, North Valley Yokuts Tribe, and Mike Despain of the Buena Vista Rancheria Me-Wuk Indians.

On March 25, 2020, Richard Hawkins (Tribal Historic Preservation Office Coordinator) responded via e-mail, indicating that the Buena Vista Rancheria Me-Wuk Indians had no knowledge of cultural resources present in the APE and no objection to the project, but requested additional notification in the event that cultural resources are encountered during project implementation. Dokken staff Amy Dunay responded affirmatively to this request on March 25, 2020. To date, no other responses have been received.

DISCUSSION

The environmental consequences for tribal cultural resources are the same regardless of whether the Project is constructed in two phases or as one complete project.

a) Listed or eligible for listing in the California Register of Historical Resources, or in a local register of historical resources as defined in Public Resources Code section 5020.1(k)

Alternative 1 through 3: Less than Significant. The Project is not anticipated to cause a substantial adverse change in the significance of a TCR listed or eligible for listing in the California Register of Historical Resources, or in a local register of historic resources as defined in Public Resources Code section 5020.1(k). No cultural resources were identified during the visual survey, the record search, or by the Native American tribal governments. No impacts are anticipated for

the Project related to archaeological resource; however, with any Project requiring ground disturbance, there is always the possibility that unmarked cultural resources may be unearthed during construction. This impact would be considered potentially significant. Implementation of Measure **CR-1** and **CR-2** would result in **Less Than Significant Impact**.

b) A resource determined by the lead agency, in its discretion and supported by substantial evidence, to be significant pursuant to criteria set forth in subdivision (c) of Public Resources Code Section 5024.1. In applying the criteria set forth in subdivision (c) of Public Resource Code Section 5024.1, the lead agency shall consider the significance of the resource to a California Native American tribe.

Alternative 1 through 3: Less than Significant. The Project is not anticipated to cause a substantial adverse change to a TCR pursuant to criteria set forth in subdivision (c) of Public Resources Cod Section 5024.1. No cultural resources were identified during the visual survey, record search, or by the Native American tribal governments. No impacts are anticipated for the Project related to archaeological resource; however, with any Project requiring ground disturbance, there is always the possibility that unmarked cultural resources may be unearthed during construction. This impact would be considered potentially significant. Implementation of Measure CR-1 and CR-2 would result in Less Than Significant.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

Mitigation Measures **CR-1** and **CR-2** within Section 2.5 will be implemented for any impacts relating to Tribal Cultural Resources regardless of whether the Project is constructed in two phases or as one complete project.

FINDINGS

The Project would have Less Than Significant Impact relating to Tribal Cultural Resources.

2.19 UTILITIES AND SERVICE SYSTEMS

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Require or result in the relocation or construction of new or expanded water, wastewater treatment or storm water drainage, electric power, natural gas, or telecommunications facilities, the construction or relocation of which could cause significant environmental effects?				
b) Have sufficient water supplies available to serve the Project and reasonably foreseeable future development during normal, dry and multiple dry years?				\boxtimes
c) Result in a determination by the wastewater treatment provider which serves or may serve the Project that it has adequate capacity to serve the Project's projected demand in addition to the provider's existing commitments?				
d) Generate solid waste in excess of State or local standards, or in excess of the capacity of local infrastructure, or otherwise impair the attainment of solid waste reduction goals?			\boxtimes	
e) Comply with federal, state, and local statutes and regulations related to solid waste?			\boxtimes	

DISCUSSION

a) Require or result in the relocation or construction of new or expanded water, wastewater treatment or storm water drainage, electric power, natural gas, or telecommunications facilities, the construction or relocation of which could cause significant environmental effects?

Alternatives 1 through 3: Less Than Significant. The Project alternatives would realign Harlan Road and would not include the construction of any wastewater-generating uses. The Project would not result in additional wastewater flows. There are existing overhead electric and communication utility lines along Harlan Road/Roth Road that will need to be relocated if impacted. Utilities within the Project area include Ahtna Environmental Inc., AT&T, City of Lathrop utility lines, Comcast and PG&E. If relocation of any of these utilities is required, close coordination with the local utility companies will occur in order to coordinate the permanent relocation of these utilities as part of the Project. Relocation of utilities would remain in the Project vicinity, which is a developed area. Therefore, the Project would have a less than significant impact on relocations of utilities and no mitigation is required.

b) Have sufficient water supplies available to serve the Project and reasonably foreseeable future development during normal, dry and multiple dry years?

Alternatives 1 through 3: No Impact. The Project alternatives would realign the existing Harlan Road and would not result in the need for new or expanded water supplies. No impacts would occur as a result of the Project, and no mitigation is required.

c) Result in a determination by the wastewater treatment provider which serves or may serve the Project that it has adequate capacity to serve the Project's projected demand in addition to the provider's existing commitments?

Alternative 1 through 3: No Impact. The Project alternatives would realign Harlan Road and would not include the construction of any wastewater-generating uses. The Project would not

increase population in the Project vicinity, and there would be no additional wastewater flows as a result of Project development; therefore, the Project would not result in the need for new or expanded wastewater facilities. No impact would occur, and no mitigation is required.

d) Generate solid waste in excess of State or local standards, or in excess of the capacity of local infrastructure, or otherwise impair the attainment of solid waste reduction goals?

Alternative 1 through 3: Less Than Significant. The Project alternatives would not generate substantial solid waste during operation. Solid waste may be generated during construction; however, the amount will not exceed landfill capacities. This would not affect landfill capacity because the amounts would not be substantial and would occur only during the construction period. Therefore, impacts associated with the Project would be considered less than significant and no mitigation is required.

e) Comply with federal, state, and local statutes and regulations related to solid waste?

Alternative 1 through 3: Less Than Significant. The Project alternatives would comply with federal, state, and local statutes and regulations related to solid waste; therefore, impacts associated with compliance with federal, state, and local statutes and regulations related to solid waste would be considered less than significant and no mitigation is required.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

No avoidance, minimization, and/or mitigation measures are required for utilities and service systems.

FINDINGS

The Project would have Less Than Significant Impacts relating to utilities and service systems.

2.20 WILDFIRE

If located in or near state responsibility areas or lands classified as very high fire hazard severity zones: Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Substantially impair an adopted emergency response plan or emergency evacuation plan?				\boxtimes
b) Due to slope, prevailing winds, and other factors, exacerbate wildfire risks, and thereby expose Project occupants to, pollutant concentrations from a wildfire or the uncontrolled spread of a wildfire?				\boxtimes
c) Require the installation or maintenance of associated infrastructure (such as roads, fuel breaks, emergency water sources, power lines or other utilities) that may exacerbate fire risk or that may result in temporary or ongoing impacts to the environment?				\boxtimes
d) Expose people or structures to significant risks, including downslope or downstream flooding or landslides, as a result of runoff, post-fire slope instability, or drainage changes?				\boxtimes

AFFECTED ENVIRONMENT

The Project is located within a local responsibility area; however, it is not within a designated fire hazard severity zone (SJMap 2004).

DISCUSSION

a) Substantially impair an adopted emergency response plan or emergency evacuation plan?

Alternative 1 through 3: No Impact. The Project alternatives would not substantially impair an adopted emergency response plan or emergency evacuation plan as access through the Project area would remain open to traffic during construction. Additionally, the Project is not located within an area designated as a fire hazard severity zone. No impact would occur, and no mitigation is required.

b) Due to slope, prevailing winds, and other factors, exacerbate wildfire risks, and thereby expose Project occupants to, pollutant concentrations from a wildfire or the uncontrolled spread of a wildfire?

Alternatives 1 through 3: No Impact. The Project alternatives would not exacerbate wildfire risks as the Project would not change any of the existing slopes. The Project is in a developed area and lacks habitat that would be prone to the spread of wildfires, such as open areas of vegetation. The Project would not expose any Project occupants to pollutants or an uncontrolled spread of a wildfire.

c) Require the installation or maintenance of associated infrastructure (such as roads, fuel breaks, emergency water sources, power lines or other utilities) that may exacerbate fire risk or that may result in temporary or ongoing impacts to the environment?

Alternative 1 through 3: No Impact. The Project alternatives would widen and realign Harlan Road, which would create improved access for emergency vehicles. The existing and realigned road would require continued maintenance; however, general maintenance is not anticipated to exacerbate fire risk or result in temporary or ongoing impacts to the environment. Therefore, no impact would occur.

d) Expose people or structures to significant risks, including downslope or downstream flooding or landslides, as a result of runoff, post-fire slope instability, or drainage changes?

Alternative 1 through 3: No Impact. The Project alternatives would not expose people or structures to downslope or downstream flooding or landslides as the Project is within a relatively flat area with slopes ranging from 0 to 2 percent (NRCS 2020). Furthermore, the Project would not create a steep slope that would expose people or structures to flooding or landslides. The Project will create some impervious surfaces; however, a portion of the realignment area includes existing roadway and areas of compacted soil. Furthermore, the Project is proposed in the City's General Plan and the storm drains are proposed to accommodate additional stormwater runoff that may result from roadway improvements in the Project vicinity. The Project is not located within a designated fire hazard severity zone, and no impacts related to significant risks to people or structures are anticipated.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

No avoidance, minimization, and/or mitigation measures are required for wildfires.

FINDINGS

The Project would have No Impacts relating to wildfires.

2.21 MANDATORY FINDINGS OF SIGNIFICANCE

Would the Project:	Potentially Significant Impact	Less Than Significant with Mitigation	Less Than Significant Impact	No Impact
a) Does the Project have the potential to degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self- sustaining levels, threaten to eliminate a plant or animal community, substantially reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory?			\boxtimes	
b) Does the Project have impacts that are individually limited, but cumulatively considerable? ("Cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, the effects of other current projects, and the effects of probable future projects)?			\boxtimes	
c) Does the Project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?		\boxtimes		

DISCUSSION

a) Does the Project have the potential to degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, substantially reduce the number or restrict the range of a rare or endangered plant or animal or eliminate important examples of the major periods of California history or prehistory?

Alternative 1 through 3: Less Than Significant. Implementation of the Project alternatives would not substantially degrade the quality of the existing environment. Potential impacts related to wildlife species, populations and sensitive habitat communities have been identified and discussed in the Biological Resources (Section 2.4). The mitigation measures have been identified related to individual resource-specific impacts. The Project has the potential to have impacts to the Swainson's hawk and burrowing owl due to disturbance related to construction activities and the potential removal of trees within the BSA; however, avoidance and minimization measures would reduce the level of all Project-related impacts to less than significant levels. Therefore, impacts are considered less than significant.

b) Does the Project have impacts that are individually limited, but cumulatively considerable? ("Cumulatively considerable" means that the incremental effects of a Project are considerable when viewed in connection with the effects of past Projects, the effects of other current Projects, and the effects of probable future Projects)?

Alternative 1 through 3: Less Than Significant. The Project alternatives would not have adverse environmental impacts at a significant level. All potential significant impacts of the Project would be addressed with avoidance, minimization and mitigation. Past projects near the Project site have been cleared through the CEQA process and potentially significant impacts from those previous projects would have already been mitigated for. No cumulative effects are anticipated because no resources would be adversely affected by the Project. Future projects within the Project vicinity, consists of improving the interchange for I-5 at Roth Road and continuing road improvements from Roth Road to Airport Way. These proposed projects have been discussed in the City's General Plan and are within an existing developed area zoned for commercial and

highway use. Therefore, cumulatively considerable effects of the Project would be less than significant.

c) Does the Project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?

Alternative 1 through 3: Less than Significant with Mitigation Incorporated. The Project alternatives would not cause significant adverse effects to human beings, either directly or indirectly with mitigation incorporated. Potential impacts have been identified related to Noise and Population and Housing. Mitigation measures have been identified related to individual resource-specific impacts. Mitigation measures would reduce the level of all Project-related impacts to less than significant levels. Therefore, impacts are considered Less than Significant with Mitigation Incorporated.

AVOIDANCE, MINIMIZATION, AND/OR MITIGATION MEASURES

- NOI-1:
- Rubberized and/or open grade asphalt will be used on the southern portion of Harlan Road under all alternatives during Phase 1 and on the northern portion of Harlan Road, during Phase 2, if Alternative 2 is selected.
- **POP-1:** The Project shall comply with the Uniform Relocation Assistance Real Property Acquisition Policies Act of 1970, as amended in 1987. Relocation advisory assistance shall be provided to any person, business, farm, or nonprofit organization relocated as a result of acquisition of real property for public use for the Project.

3.0 Comments and Coordination

This chapter summarizes the City's efforts to identify, address and resolve Project-related issues through early and continuing coordination.

3.1 Consultation and Coordination with Public Agencies

Coordination with the following agencies was initiated for the Harlan Road Realignment Project:

Native American Heritage Commission (NAHC)

3.2 Public Participation

A public coordination meeting was held March 3, 2020 and ongoing coordination with directly affected property owners has been occurring throughout 2019 and 2020. The public comment period for the Project will occur from November 25, 2020 to December 31, 2020. All comments will be incorporated into the Final Initial Study/Mitigated Negative Declaration and added as **Attachment H**. Any additions or corrections to the ISMND subsequent to public comments will be addressed within the final document.

4.0 List of Preparers

Dokken Engineering

Sarah Holm, Senior Environmental Planner John Fogerty, Environmental Planner/ Archaeologist Hanna Sheldon, Environmental Planner / Biologist Ken Chen, Environmental Planner / Noise and Air Specialist

City of Lathrop

Michael King Director of Public Works City of Lathrop

5.0 References

- Audubon. 2020. National Audubon Society. Available at: https://www.audubon.org/ (accessed: June 15, 2020).
- Caltrans 2020. Scenic Highways. Available at: <https://dot.ca.gov/programs/design/laplandscape-architecture-and-community-livability/lap-liv-i-scenic-highways> (accessed: June 18, 2020).
- Cal-IPC. 2020. Online California Invasive Plant Inventory Database. Available at: http://www.cal-ipc.org/paf/> (accessed: June 1, 2020).
- California Air Resources Board (CARB) 2005. Air Quality and Land Use Handbook: A Community Health Perspective. Available at: (accessed: June 15, 2020).
- California Department of Conservation. 2010. Fault Activity Map of California. Available at: (accessed: June 10, 2020).
- California Natural Diversity Database (CNDDB) 2020. California Natural Diversity Database, Rarefind 5. Available at:<http://www.dfg.ca.gov/biogeodata/cnddb/> (accessed: June 10, 2020).
- California Air Resources Board (CARB) 2016. Ambient Air Quality Standards. Available at: http://www.arb.ca.gov/research/aaqs/aaqs2.pdf> (accessed: June 10, 2020).
- Central Valley RWQCB. 2006. Groundwater Quality. Available at: https://www.waterboards.ca.gov/centralvalley/water_issues/irrigated_lands/archives/exist_cond_rpt/draft_existing_conditions_rpt/ch04_pt3.pdf> (accessed: June 16, 2020).
- City of Lathrop. 1991. General Plan and Environmental Impact Report. Available at: https://www.ci.lathrop.ca.us/sites/default/files/fileattachments/planning_division/page/5251/1991_lathrop_general_plan_and_eir.pdf (accessed: June 15, 2020).
- City of Lathrop. 1995. City of Lathrop Bicycle Transportation Plan. Available at: http://www.ci.lathrop.ca.us/sites/default/files/fileattachments/community_development/page/5556/bicycle_transportation_plan_adopted_8-9-95.pdf (accessed: June 15, 2020).
- CNPS. 2020. Inventory of Rare and Endangered Plants. Available at: (accessed: June 10, 2020).
- Department of Conservation (DOC), Division of Mines and Geology 2000. A General Location Guide for Ultramafic Rocks in California – Areas More Likely to Contain Naturally Occurring Asbestos. Available at: https://ww3.arb.ca.gov/toxics/asbestos/ofr_2000-019.pdf> (accessed: June 16, 2020).

Dokken Engineering. 2020. Noise Study Report- Harlan Road Realignment Project.

- EMFAC. 2020. California Air Resources Board. Available at: https://arb.ca.gov/emfac/ (accessed: June 19, 2020).
- Federal Highway Administration, 2004. FHWA Traffic Noise Model, Version 2.5
- Geocon 2020. Initial Site Assessment- Harlan Road at Roth Road Realignment.
- Geotracker. 2020. State Water Resources Control Board. Available at: https://geotracker.waterboards.ca.gov/> (Accessed: June 17, 2020).
- National Wetland Inventory. 2020. Wetlands Mapper. Available at: (accessed: June 11, 2020).
- NCRS. 2020. Web Soil Survey, Natural Resource Conservation Service, Available at: http://websoilsurvey.sc.egov.usda.gov/App/WebSoilSurvey.aspx (accessed: March 12, 2020).
- NMFS. 2020. California Species List Tools. Available at: http://www.westcoast.fisheries.noaa.gov/maps_data/california_species_list_tools. http://www.westcoast.fisheries.noaa.gov/maps_data/california_species_list_tools. http://www.westcoast.fisheries.noaa.gov/maps_data/california_species_list_tools. http://www.westcoast.fisheries.noaa.gov/maps_data/california_species_list_tools.
- SJVAPCD 2019. San Joaquin Valley Air Pollution Control District 2019 Annual Report: Indirect Source Review Program. Available at http://www.valleyair.org/isr/Documents/2019-Annual-Report.pdf> (accessed: June 15, 2020)
- SJMap 2004. San Joaquin County GIS Map Server- Very High Fire Hazard Severity. Available at: https://www.sjmap.org/nhd/> (accessed: June 16, 2020).
- SJMSCP 2000. San Joaquin County Multi-Species Habitat Conservation and Open Space Plan. Available at: < https://casjcog2.civicplus.com/DocumentCenter/View/5/Habitat-Planpdf?bidId=> (accessed: June 15, 2020).
- San Joaquin County. 2016. San Joaquin County General Plan. Available at: < https://www.sjgov.org/commdev/cgi-bin/cdyn.exe?grp=planning&htm=gp2035 > (accessed: June 10, 2020)
- SMAQMD. 2014. Sacramento Metropolitan Air Quality Management District- Construction Emissions Model. Available at: < https://www.valleyair.org/ISR/ISRResources.htm> (accessed: June 18, 2020).
- USFWS. 2020. Information for Planning and Consultation. Available at: < https://ecos.fws.gov/ipac/> (accessed: June 10, 2020).
- USGS. 2020. Science in Your Watershed- California's Central Valley. Available at: (accessed: June 16, 2020).

Attachment A: NRCS Soil Report



United States Department of Agriculture

Natural Resources Conservation

Service

A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

Custom Soil Resource Report for San Joaquin County, California



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (https://offices.sc.egov.usda.gov/locator/app?agency=nrcs) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/? cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface	2
How Soil Surveys Are Made	
Soil Map	
Soil Map	
Legend	
Map Unit Legend	
Map Unit Descriptions	11
San Joaquin County, California	
254—Timor loamy sand, 0 to 2 percent slopes	13
266—Veritas fine sandy loam, 0 to 2 percent slopes	
References	17

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report Soil Map



	MAP L	EGEND		MAP INFORMATION
Area of Int	terest (AOI) Area of Interest (AOI)	8	Spoil Area Stony Spot	The soil surveys that comprise your AOI were mapped at 1:24,000.
Soils	Soil Map Unit Polygons	00 V	Very Stony Spot Wet Spot	Warning: Soil Map may not be valid at this scale.
ĩ	Soil Map Unit Lines Soil Map Unit Points	۵ •	Other Special Line Features	Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of
అ	Point Features Blowout Borrow Pit	Water Fea	tures Streams and Canals	contrasting soils that could have been shown at a more detailed scale.
×	Clay Spot	Transport +++	ation Rails	Please rely on the bar scale on each map sheet for map measurements.
◇ ¥	Closed Depression Gravel Pit Gravelly Spot	~	Interstate Highways US Routes	Source of Map: Natural Resources Conservation Service Web Soil Survey URL: Coordinate System: Web Mercator (EPSG:3857)
۵ ۸	Landfill Lava Flow	~	Major Roads Local Roads -	Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts
大 小 次	Marsh or swamp Mine or Quarry	Backgrou	Background Aerial Photography	distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.
0	Miscellaneous Water Perennial Water			This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.
~ +	Rock Outcrop Saline Spot			Soil Survey Area: San Joaquin County, California Survey Area Data: Version 13, Sep 16, 2019
**	Sandy Spot Severely Eroded Spot			Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.
 ک	Sinkhole Slide or Slip			Date(s) aerial images were photographed: Mar 11, 2019—Mar 14, 2019
ø	Sodic Spot			The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

	- 1	1	
Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
254	Timor loamy sand, 0 to 2 percent slopes	4.5	8.6%
266	Veritas fine sandy loam, 0 to 2 percent slopes	47.8	91.4%
Totals for Area of Interest		52.3	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however,

onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

San Joaquin County, California

254—Timor loamy sand, 0 to 2 percent slopes

Map Unit Setting

National map unit symbol: hhwy Elevation: 20 to 40 feet Mean annual precipitation: 11 inches Mean annual air temperature: 61 degrees F Frost-free period: 270 days Farmland classification: Farmland of statewide importance

Map Unit Composition

Timor and similar soils: 85 percent *Minor components:* 15 percent *Estimates are based on observations, descriptions, and transects of the mapunit.*

Description of Timor

Setting

Landform: Fan skirts Landform position (two-dimensional): Footslope Landform position (three-dimensional): Tread Down-slope shape: Linear Across-slope shape: Linear Parent material: Alluvium derived from granitic rock sources

Typical profile

Ap - 0 to 14 inches: loamy sand *Bk - 14 to 56 inches:* loamy sand *2Bkqm - 56 to 60 inches:* cemented

Properties and qualities

Slope: 0 to 2 percent
Depth to restrictive feature: 40 to 60 inches to duripan
Natural drainage class: Moderately well drained
Runoff class: Negligible
Capacity of the most limiting layer to transmit water (Ksat): Very low (0.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: Rare
Frequency of ponding: None
Calcium carbonate, maximum in profile: 5 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Low (about 3.5 inches)

Interpretive groups

Land capability classification (irrigated): 3s Land capability classification (nonirrigated): 4s Hydrologic Soil Group: A Hydric soil rating: No

Minor Components

Bisgani

Percent of map unit: 3 percent

Landform: Alluvial fans Hydric soil rating: Yes

Grangeville

Percent of map unit: 3 percent Hydric soil rating: No

Veritas

Percent of map unit: 3 percent Hydric soil rating: No

Tinnin

Percent of map unit: 2 percent Hydric soil rating: No

Unnamed, mod fine text above hardpan Percent of map unit: 2 percent Hydric soil rating: No

Unnamed, hardpan above 40 inches

Percent of map unit: 2 percent Hydric soil rating: No

266—Veritas fine sandy loam, 0 to 2 percent slopes

Map Unit Setting

National map unit symbol: hhxb Elevation: 20 to 80 feet Mean annual precipitation: 11 inches Mean annual air temperature: 61 degrees F Frost-free period: 270 days Farmland classification: Prime farmland if irrigated

Map Unit Composition

Veritas and similar soils: 85 percent Minor components: 15 percent Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Veritas

Setting

Landform: Fan skirts Landform position (two-dimensional): Footslope Landform position (three-dimensional): Tread Down-slope shape: Linear Across-slope shape: Linear Parent material: Alluvium derived from mixed rock sources

Typical profile

A - 0 to 15 inches: fine sandy loam *Bk - 15 to 54 inches:* fine sandy loam *2Bqm - 54 to 70 inches:* cemented

Properties and qualities

Slope: 0 to 2 percent
Depth to restrictive feature: 40 to 60 inches to duripan
Natural drainage class: Moderately well drained
Runoff class: Very low
Capacity of the most limiting layer to transmit water (Ksat): Very low (0.00 to 0.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 3 percent
Salinity, maximum in profile: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)
Available water storage in profile: Moderate (about 7.6 inches)

Interpretive groups

Land capability classification (irrigated): 2s Land capability classification (nonirrigated): 4s Hydrologic Soil Group: A Hydric soil rating: No

Minor Components

Grangeville

Percent of map unit: 4 percent Hydric soil rating: No

Unnamed, mod fine textured surface Percent of map unit: 4 percent

Hydric soil rating: No

Bisgani

Percent of map unit: 2 percent Landform: Alluvial fans Hydric soil rating: Yes

Jahant

Percent of map unit: 1 percent Hydric soil rating: No

Madera

Percent of map unit: 1 percent Hydric soil rating: No

Tinnin

Percent of map unit: 1 percent Hydric soil rating: No

Unnamed, w/ mod fine texture above hardpan Percent of map unit: 1 percent

Hydric soil rating: No

Unnamed, w/ hardpan above 40 inches

Percent of map unit: 1 percent *Hydric soil rating:* No Custom Soil Resource Report

References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/ nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/ home/?cid=nrcs142p2 053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. http://www.nrcs.usda.gov/wps/portal/nrcs/ detail/national/landuse/rangepasture/?cid=stelprdb1043084

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/ nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/? cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

Attachment B: CT EMFAC and Road Construction Emissions Model Results

File Name:	San Joaquin (SJV) - 2019 - Exiting North Harlan.EC
CT-EMFAC Version:	6.0.0.29548
Run Date:	6/18/2020 6:24:18 PM
Area:	San Joaquin (SJV)
Analysis Year:	2019
Season:	Annual
Vehicle Category Truck 1 Truck 2 Non-Truck	VMT FractionDiesel VMT FractionAcross CategoryWithin Category0.0400.5690.1300.9760.8300.010
Road Length:	0.25 miles
Volume:	282 vehicles per hour
Number of Hours:	1 hours
Avg. Idling Time:	0 minutes per vehicle
Tot. Idling Time:	0.00 hours
VMT Distribution by 5 10 15 20 25 30 35 40 45 50 55 60 65 70	Speed (mph): 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 100.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00%

===

	Running Exhaust	Idling Exhaust	Running Loss	Tire Wear	Brake Wear	Total	Total
Pollutant Name	(grams)	(grams)	(grams)	(grams)	(grams)	(grams)	(US tons)
HC	3.1	0.0	3.0	-	-	6.1	<0.001
ROG	2.8	0.0	3.2	-	-	6.0	<0.001
TOG	3.7	0.0	3.2	-	-	6.8	<0.001
CO	67.7	0.0	-	-	-	67.7	<0.001
NOx	46.4	0.0	-	-	-	46.4	<0.001
C02	31,680.0	0.0	-	-	-	31,680.0	0.035
CH4	0.6	0.0	-	-	-	0.6	<0.001
PM10	0.4	0.0	-	0.8	3.2	4.4	<0.001
PM2.5	0.4	0.0	-	0.2	1.4	2.0	<0.001
Benzene	<0.1	0.0	<0.1	-	-	0.1	<0.001
Acrolein	<0.1	0.0	-	-	-	<0.1	<0.001
Acetaldehyde	0.1	0.0	-	-	-	0.1	<0.001
Formaldehyde	0.2	0.0	-	-	-	0.2	<0.001
Butadiene	<0.1	0.0	0.0	-	-	<0.1	<0.001
Naphthalene	<0.1	0.0	<0.1	-	-	<0.1	<0.001
POM	<0.1	0.0	-	-	-	<0.1	<0.001
Diesel PM	0.4	0.0	-	-	-	0.4	<0.001
DEOG	1.3	0.0	-	-	-	1.3	<0.001
			==END============				

File Name: CT-EMFAC Version: Run Date: Area: Analysis Year: Season:	San Joaquin (SJV) - 2019 - Existingl.EC 6.0.0.29548 6/18/2020 6:19:33 PM San Joaquin (SJV) 2019 Annual
Vehicle Category Truck 1 Truck 2 Non-Truck	VMT FractionDiesel VMT FractionAcross CategoryWithin Category0.0400.5690.1300.9760.8300.010
Road Length: Volume: Number of Hours: Avg. Idling Time: Tot. Idling Time: VMT Distribution by 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75	0.35 miles 502 vehicles per hour 1 hours 0 minutes per vehicle 0.00 hours Speed (mph): 0.00%

	Running Exhaust	Idling Exhaust	Running Loss	Tire Wear	Brake Wear	Total	Total
Pollutant Name	(grams)	(grams)	(grams)	(grams)	(grams)	(grams)	(US tons)
HC	7.7	0.0	7.5	-	-	15.2	<0.001
ROG	7.1	0.0	8.0	-	-	15.1	<0.001
TOG	9.1	0.0	8.0	-	-	17.1	<0.001
CO	168.8	0.0	-	-	-	168.8	<0.001
NOx	115.7	0.0	-	-	-	115.7	<0.001
C02	78,952.9	0.0	-	-	-	78,952.9	0.087
CH4	1.6	0.0	-	-	-	1.6	<0.001
PM10	1.1	0.0	-	1.9	7.9	11.0	<0.001
PM2.5	1.1	0.0	-	0.5	3.4	4.9	<0.001
Benzene	0.2	0.0	<0.1	-	-	0.3	<0.001
Acrolein	<0.1	0.0	-	-	-	<0.1	<0.001
Acetaldehyde	0.3	0.0	-	-	-	0.3	<0.001
Formaldehyde	0.6	0.0	-	-	-	0.6	<0.001
Butadiene	<0.1	0.0	0.0	-	-	<0.1	<0.001
Naphthalene	<0.1	0.0	<0.1	-	-	<0.1	<0.001
POM	<0.1	0.0	-	-	-	<0.1	<0.001
Diesel PM	0.9	0.0	-	-	-	0.9	<0.001
DEOG	3.3	0.0	-	-	-	3.3	<0.001
			==FND==================================				

File Name:	San Joaquin (SJV) - 2040 - No Build North Harlan.EC
CT-EMFAC Version:	6.0.0.29548
Run Date:	6/18/2020 6:28:01 PM
Area:	San Joaquin (SJV)
Analysis Year:	2040
Season:	Annual
Vehicle Category Truck 1 Truck 2 Non-Truck	VMT FractionDiesel VMT FractionAcross CategoryWithin Category0.0400.6530.1300.9770.8300.012
Road Length:	0.25 miles
Volume:	254 vehicles per hour
Number of Hours:	1 hours
Avg. Idling Time:	0 minutes per vehicle
Tot. Idling Time:	0.00 hours
VMT Distribution by 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75	Speed (mph): 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 100.00% 0.00%

Tota	Total	Brake Wear	Tire Wear	Running Loss	Idling Exhaust	Running Exhaust	
(US tons	(grams)	(grams)	(grams)	(grams)	(grams)	(grams)	Pollutant Name
<0.00	2.1	-	-	1.0	0.0	1.1	HC
<0.00	2.1	-	-	1.1	0.0	1.0	ROG
<0.00	2.3	-	-	1.1	0.0	1.3	TOG
<0.00	21.6	-	-	-	0.0	21.6	CO
<0.00	6.5	-	-	-	0.0	6.5	NOx
0.02	20,930.8	-	-	-	0.0	20,930.8	C02
<0.00	0.2	-	-	-	0.0	0.2	CH4
<0.00	3.6	2.8	0.7	-	0.0	<0.1	PM10
<0.00	1.5	1.2	0.2	-	0.0	<0.1	PM2.5
<0.00	<0.1	-	-	<0.1	0.0	<0.1	Benzene
<0.00	<0.1	-	-	-	0.0	<0.1	Acrolein
<0.00	<0.1	-	-	-	0.0	<0.1	Acetaldehyde
<0.00	<0.1	-	-	-	0.0	<0.1	Formaldehyde
<0.00	<0.1	-	-	0.0	0.0	<0.1	Butadiene
<0.00	<0.1	-	-	<0.1	0.0	<0.1	Naphthalene
<0.00	<0.1	-	-	-	0.0	<0.1	POM
<0.00	<0.1	-	-	-	0.0	<0.1	Diesel PM
<0.00	0.5	-	-	-	0.0	0.5	DEOG

File Name:	San Joaquin (SJV) - 2040 - No Build.EC
CT-EMFAC Version:	6.0.0.29548
Run Date:	6/18/2020 6:20:57 PM
Area:	San Joaquin (SJV)
Analysis Year:	2040
Season:	Annual
Vehicle Category Truck 1 Truck 2 Non-Truck	VMT Fraction Diesel VMT Fraction Across Category Within Category 0.040 0.653 0.130 0.977 0.830 0.012
Road Length:	0.35 miles
Volume:	525 vehicles per hour
Number of Hours:	1 hours
Avg. Idling Time:	0 minutes per vehicle
Tot. Idling Time:	0.00 hours
VMT Distribution by	Speed (mph):
5	0.00%
10	0.00%
15	0.00%
20	0.00%
20 25 30 35 40 45 50 55 60 65 70 75	0.00% 0.00% 0.00% 0.00% 100.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00%

	Running Exhaust	Idling Exhaust	Running Loss	Tire Wear	Brake Wear	Total	Total
Pollutant Name	(grams)	(grams)	(grams)	(grams)	(grams)	(grams)	(US tons)
HC	3.1	0.0	2.8	-	-	5.9	<0.001
ROG	2.9	0.0	3.0	-	-	6.0	<0.001
TOG	3.7	0.0	3.0	-	-	6.7	<0.001
CO	62.6	0.0	-	-	-	62.6	<0.001
NOx	18.8	0.0	-	-	-	18.8	<0.001
C02	60,567.6	0.0	-	-	-	60,567.6	0.067
CH4	0.6	0.0	-	-	-	0.6	<0.001
PM10	0.2	0.0	-	2.0	8.2	10.4	<0.001
PM2.5	0.2	0.0	-	0.5	3.5	4.2	<0.001
Benzene	<0.1	0.0	<0.1	-	-	0.1	<0.001
Acrolein	<0.1	0.0	-	-	-	<0.1	<0.001
Acetaldehyde	0.1	0.0	-	-	-	0.1	<0.001
Formaldehyde	0.3	0.0	-	-	-	0.3	<0.001
Butadiene	<0.1	0.0	0.0	-	-	<0.1	<0.001
Naphthalene	<0.1	0.0	<0.1	-	-	<0.1	<0.001
POM	<0.1	0.0	-	-	-	<0.1	<0.001
Diesel PM	0.1	0.0	-	-	-	0.1	<0.001
DEOG	1.4	0.0	-	-	-	1.4	<0.001
			==END============				

File Name: CT-EMFAC Version: Run Date: Area: Analysis Year: Season:	San Joaquin (SJV) - 2040 - Build North Harlan.EC 6.0.0.29548 6/18/2020 6:29:11 PM San Joaquin (SJV) 2040 Annual
Vehicle Category	VMT Fraction Diesel VMT Fraction Across Category Within Category
Truck 1	0.040 0.653
Truck 2	0.130 0.977
Non-Truck	0.830 0.012
Road Length:	0.25 miles
Volume:	254 vehicles per hour
Number of Hours:	1 hours
Avg. Idling Time:	0 minutes per vehicle
Tot. Idling Time:	0.00 hours
VMT Distribution by Sp 5 10 15 20 25	<pre>beed (mph): 0.00% 0.00% 0.00% 0.00% 0.00% 100.00%</pre>
30	0.00%
35	0.00%
40	0.00%
45	0.00%
50	0.00%
55	0.00%
60	0.00%
65	0.00%
70	0.00%
75	0.00%

	Running Exhaust	Idling Exhaust	Running Loss	Tire Wear	Brake Wear	Total	Total
Pollutant Name	(grams)	(grams)	(grams)	(grams)	(grams)	(grams)	(US tons)
HC	2.4	0.0	1.9	-	-	4.3	<0.001
ROG	2.4	0.0	2.0	-	-	4.4	<0.001
TOG	3.0	0.0	2.0	-	-	5.0	<0.001
CO	33.9	0.0	-	-	-	33.9	<0.001
NOx	22.0	0.0	-	-	-	22.0	<0.001
C02	27,265.7	0.0	-	-	-	27,265.7	0.030
CH4	0.4	0.0	-	-	-	0.4	<0.001
PM10	0.1	0.0	-	0.7	2.8	3.7	<0.001
PM2.5	0.1	0.0	-	0.2	1.2	1.5	<0.001
Benzene	<0.1	0.0	<0.1	-	-	<0.1	<0.001
Acrolein	<0.1	0.0	-	-	-	<0.1	<0.001
Acetaldehyde	0.1	0.0	-	-	-	0.1	<0.001
Formaldehyde	0.3	0.0	-	-	-	0.3	<0.001
Butadiene	<0.1	0.0	0.0	-	-	<0.1	<0.001
Naphthalene	<0.1	0.0	<0.1	-	-	<0.1	<0.001
POM	<0.1	0.0	-	-	-	<0.1	<0.001
Diesel PM	<0.1	0.0	-	-	-	<0.1	<0.001
DEOG	1.6	0.0	-	-	-	1.6	<0.001
			=END===================================				

File Name: CT-EMFAC Version: Run Date: Area: Analysis Year: Season:	San Joaquin (SJV) - 2040 - Build South Harlan.EC 6.0.0.29548 6/18/2020 6:17:33 PM San Joaquin (SJV) 2040 Annual
Vehicle Category	VMT Fraction Diesel VMT Fraction Across Category Within Category
Truck 1	0.040 0.653
Truck 2	0.130 0.977
Non-Truck	0.830 0.012
Road Length: Volume:	0.4 miles 525 vehicles per hour
Number of Hours:	1 hours
Avg. Idling Time:	0 minutes per vehicle
Tot. Idling Time:	0.00 hours
VMT Distribution by 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75	Speed (mph): 0.00% 0.00% 0.00% 100.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00% 0.00%

Tota	Total	Brake Wear	Tire Wear	Running Loss	Idling Exhaust	Running Exhaust	
(US tons	(grams)	(grams)	(grams)	(grams)	(grams)	(grams)	Pollutant Name
<0.00	14.2	-	-	6.1	0.0	8.1	HC
<0.00	14.6	-	-	6.6	0.0	8.0	ROG
<0.00	16.5	-	-	6.6	0.0	9.9	TOG
<0.00	112.0	-	-	-	0.0	112.0	CO
<0.00	72.8	-	-	-	0.0	72.8	NOx
0.09	90,170.0	-	-	-	0.0	90,170.0	C02
<0.00	1.4	-	-	-	0.0	1.4	CH4
<0.00	12.1	9.3	2.3	-	0.0	0.4	PM10
<0.00	5.0	4.0	0.6	-	0.0	0.4	PM2.5
<0.00	0.3	-	-	<0.1	0.0	0.2	Benzene
<0.00	<0.1	-	-	-	0.0	<0.1	Acrolein
<0.00	0.4	-	-	-	0.0	0.4	Acetaldehyde
<0.00	0.8	-	-	-	0.0	0.8	Formaldehyde
<0.00	<0.1	-	-	0.0	0.0	<0.1	Butadiene
<0.00	<0.1	-	-	<0.1	0.0	<0.1	Naphthalene
<0.00	<0.1	-	-	-	0.0	<0.1	POM
<0.00	0.2	-	-	-	0.0	0.2	Diesel PM
<0.00	5.1	-	-	-	0.0	5.1	DEOG

Road Construction Emissions Model, Version 9.0.0

	mates for -> Harlar	in Road Realignme	ent Project (Phase 1)		Total	Exhaust	Fugitive Dust	Total	Exhaust	Fugitive Dust					
Project Phases (Pounds)	R	OG (Ibs/day)	CO (lbs/day)	NOx (lbs/day)	PM10 (lbs/day)	PM10 (Ibs/day)	PM10 (lbs/day)	PM2.5 (lbs/day)	PM2.5 (lbs/day)	PM2.5 (lbs/day)	SOx (Ibs/day)	CO2 (lbs/day)	CH4 (lbs/day)	N2O (Ibs/day)	CO2e (Ibs/da
Grubbing/Land Clearing		1.18	10.47	13.00	10.56	0.56	10.00	2.57	0.49	2.08	0.03	2,581.32	0.59	0.10	2,626.63
Grading/Excavation		3.65	25.52	44.18	11.77	1.77	10.00	3.60	1.52	2.08	0.08	8,094.44	1.70	0.41	8,257.85
Prainage/Utilities/Sub-Grade		2.99	25.68	29.98	11.36	1.36	10.00	3.33	1.25	2.08	0.05	5,109.91	1.00	0.08	5,157.55
Paving		1.04	11.79	11.36	0.60	0.60	0.00	0.49	0.49	0.00	0.03	3,081.56	0.48	0.21	3,157.45
laximum (pounds/day)		3.65	25.68	44.18	11.77	1.77	10.00	3.60	1.52	2.08	0.08	8,094.44	1.70	0.41	8,257.8
otal (tons/construction project)		0.37	2.91	4.11	1.30	0.18	1.12	0.39	0.15	0.23	0.01	758.55	0.15	0.03	771.48
Notes: Proje	ect Start Year ->	2021													
Project Ler	ngth (months) ->	12													
Total Project	t Area (acres) ->	27													
Maximum Area Disturbed	d/Day (acres) ->	1													
Water	Truck Used? ->	Yes						_							
	То	otal Material Imp Volume (Daily VMT	(miles/day)									
	Phase	Soil	Asphalt	Soil Hauling	Asphalt Hauling	Worker Commute	Water Truck								
Cashkin	g/Land Clearing	41	0	90	0	280	40								
Grubbin															
	ding/Excavation	329	0	510	0	880	40								
Gra	• •		0		0										
Gra	ding/Excavation	329	0		0 0 270	880	40								
Gra	iding/Excavation ities/Sub-Grade Paving	329 0 0	0 163	510 0 0		880 600 480	40 40								
Grainage/Utili	iding/Excavation ities/Sub-Grade Paving re dust from watering a	329 0 0 and associated of	0 163 dust control measur	510 0 0 res if a minimum nur	nber of water trucks	880 600 480 are specified.	40 40 40	gitive dust emissions	s shown in columns .	l and K.					
Grai Drainage/Utilit M10 and PM2.5 estimates assume 50% control of fugitiv otal PM10 emissions shown in column F are the sum of e	iding/Excavation ities/Sub-Grade Paving re dust from watering a exhaust and fugitive du	329 0 0 and associated oust emissions sl	0 163 dust control measur hown in columns G	510 0 0 res if a minimum nur and H. Total PM2.5	nber of water trucks emissions shown in	880 600 480 are specified. Column I are the su	40 40 40 m of exhaust and fu	•							
Grai Drainage/Utili M10 and PM2.5 estimates assume 50% control of fugitiv otal PM10 emissions shown in column F are the sum of e O2e emissions are estimated by multiplying mass emissi Total Emission Estimates by I	iding/Excavation ities/Sub-Grade Paving re dust from watering a exhaust and fugitive du ions for each GHG by	329 0 0 and associated o ust emissions sl r its global warm	0 163 dust control measur hown in columns G ing potential (GWP)	510 0 0 res if a minimum nur and H. Total PM2.5	nber of water trucks emissions shown in	880 600 480 are specified. Column I are the su	40 40 40 m of exhaust and fu	•							
Gran Drainage/Utilit M10 and PM2.5 estimates assume 50% control of fugitive otal PM10 emissions shown in column F are the sum of e O2e emissions are estimated by multiplying mass emissi Total Emission Estimates by I roject Phases	iding/Excavation ities/Sub-Grade Paving re dust from watering a exhaust and fugitive di ions for each GHG by Phase for -> Harla	329 0 0 and associated o ust emissions sl r its global warm	0 163 dust control measur hown in columns G ing potential (GWP)	510 0 0 res if a minimum nur and H. Total PM2.5	nber of water trucks emissions shown in CO2, CH4 and N2O	880 600 480 are specified. Column I are the su , respectively. Total	40 40 40 m of exhaust and fu CO2e is then estima	ated by summing CO Total	2e estimates over a	I GHGs. Fugitive Dust	SOx (tons/phase)	CO2 (tons/phase)	CH4 (tons/phase)	N2O (tons/phase)	CO2e (MT/p
Gran Drainage/Utili M10 and PM2.5 estimates assume 50% control of fugitiv otal PM10 emissions shown in column F are the sum of e O2e emissions are estimated by multiplying mass emissi	iding/Excavation ities/Sub-Grade Paving re dust from watering a exhaust and fugitive di ions for each GHG by Phase for -> Harla	329 0 0 and associated (ust emissions sl i ts global warm In Road Realignme	0 163 dust control measur hown in columns G ing potential (GWP) ant Project (Phase 1)	510 0 es if a minimum nur and H. Total PM2.5), 1 , 25 and 298 for	nber of water trucks emissions shown in CO2, CH4 and N2O, Total	880 600 480 are specified. Column I are the su , respectively. Total Exhaust	40 40 40 m of exhaust and fu CO2e is then estima Fugitive Dust	ated by summing CO Total	2e estimates over al Exhaust	I GHGs. Fugitive Dust	SOx (tons/phase)	CO2 (tons/phase) 34.07	CH4 (tons/phase)	N2O (tons/phase)	CO2e (MT/p 31.45
Grai Drainage/Utili M10 and PM2.5 estimates assume 50% control of fugitive tal PM10 emissions shown in column F are the sum of e O2e emissions are estimated by multiplying mass emissi Total Emission Estimates by I roject Phases ons for all except CO2e. Metric tonnes for CO2e) rubbing/Land Clearing	iding/Excavation ities/Sub-Grade Paving re dust from watering a exhaust and fugitive di ions for each GHG by Phase for -> Harla	329 0 0 and associated of ust emissions sl i its global warm in Road Realignme G (tons/phase)	0 163 dust control measur hown in columns G ing potential (GWP) ent Project (Phase 1) CO (tons/phase)	510 0 es if a minimum nur and H. Total PM2.5), 1 , 25 and 298 for NOx (tons/phase)	nber of water trucks emissions shown in CO2, CH4 and N2O, Total PM10 (tons/phase)	880 600 480 are specified. Column I are the su , respectively. Total Exhaust PM10 (tons/phase)	40 40 20 m of exhaust and fu CO2e is then estima Fugitive Dust PM10 (tons/phase)	ted by summing CO Total PM2.5 (tons/phase)	2e estimates over al Exhaust PM2.5 (tons/phase)	l GHGs. Fugitive Dust PM2.5 (tons/phase)		. (() · · · · · · · · · · · · · · · · · · ·	. (
Gra Drainage/Utili M10 and PM2.5 estimates assume 50% control of fugitive otal PM10 emissions shown in column F are the sum of e O2e emissions are estimated by multiplying mass emission Total Emission Estimates by I roject Phases Total Emission Estimates by I robing/Land Clearing rading/Excavation	iding/Excavation ities/Sub-Grade Paving re dust from watering a exhaust and fugitive di ions for each GHG by Phase for -> Harla	329 0 0 and associated of ust emissions sl its global warm in Road Realignmo G (tons/phase) 0.02	0 163 dust control measur hown in columns G ing potential (GWP; ant Project (Phase 1) CO (tons/phase) 0.14	510 0 0 ers if a minimum nur and H. Total PM2.5), 1 , 25 and 298 for NOx (tons/phase) 0.17	nber of water trucks emissions shown in CO2, CH4 and N2O Total PM10 (tons/phase) 0.14	880 600 480 Column I are the su , respectively. Total Exhaust PM10 (tons/phase) 0.01	40 40 40 m of exhaust and fu CO2e is then estimate Fugitive Dust PM10 (tons/phase) 0.13	Total PM2.5 (tons/phase)	2e estimates over al Exhaust PM2.5 (tons/phase) 0.01	I GHGs. Fugitive Dust PM2.5 (tons/phase) 0.03	0.00	34.07	0.01	0.00	31.45
Gran Drainage/Utilit M10 and PM2.5 estimates assume 50% control of fugitiv otal PM10 emissions shown in column F are the sum of e coze emissions are estimated by multiplying mass emissi Total Emission Estimates by I roject Phases Fons for all except CO2e. Metric tonnes for CO2e)	iding/Excavation ities/Sub-Grade Paving re dust from watering a exhaust and fugitive di ions for each GHG by Phase for -> Harla	329 0 and associated ust emissions si its global warm n Road Realignme G (tons/phase) 0.02 0.19	0 163 dust control measur hown in columns G ing potential (GWP) ent Project (Phase 1) CO (tons/phase) 0.14 1.35	510 0 es if a minimum nur and H. Total PM2.5), 1 , 25 and 298 for NOx (tons/phase) 0.17 2.33	nber of water trucks emissions shown in CO2, CH4 and N2O Total PM10 (tons/phase) 0.14 0.62	880 600 480 are specified. Column I are the su respectively. Total Exhaust PM10 (tons/phase) 0.01 0.09	40 40 40 m of exhaust and fu CO2e is then estimat Fugitive Dust PM10 (tons/phase) 0.13 0.53	Total PM2.5 (tons/phase) 0.03 0.19	Exhaust PM2.5 (tons/phase) 0.01 0.08	I GHGs. Fugitive Dust PM2.5 (tons/phase) 0.03 0.11	0.00 0.00	34.07 427.39	0.01 0.09	0.00 0.02	31.45 395.5
Gran Drainage/Utilit M10 and PM2.5 estimates assume 50% control of fugitiv otal PM10 emissions shown in column F are the sum of e O2e emissions are estimated by multiplying mass emissio Total Emission Estimates by I roject Phases Cons for all except CO2e. Metric tonnes for CO2e) irrubbing/Land Clearing rrading/Excavation rrading/Excavation rrainage/Utilities/Sub-Grade	iding/Excavation ities/Sub-Grade Paving re dust from watering a exhaust and fugitive di ions for each GHG by Phase for -> Harla	329 0 and associated ust emissions sl its global warm In Road Realignmu G (tons/phase) 0.02 0.19 0.14	0 163 dust control measur nown in columns G ing potential (GWP) ent Project (Phase 1) CO (tons/phase) 0.14 1.35 1.19	510 0 es if a minimum nur and H. Total PM2.5), 1 , 25 and 298 for NOx (tons/phase) 0.17 2.33 1.38	nber of water trucks emissions shown in CO2, CH4 and N2O Total PM10 (tons/phase) 0.14 0.62 0.52	880 480 are specified. Column I are the su respectively. Total Exhaust PM10 (tons/phase) 0.01 0.09 0.06	40 40 40 m of exhaust and fu CO2e is then estima Fugitive Dust PM10 (tons/phase) 0.13 0.53 0.46	Total PM2.5 (tons/phase) 0.03 0.19 0.15	2e estimates over al Exhaust PM2.5 (tons/phase) 0.01 0.08 0.06	Fugitive Dust PM2.5 (tons/phase) 0.03 0.11 0.10	0.00 0.00 0.00	34.07 427.39 236.08	0.01 0.09 0.05	0.00 0.02 0.00	31.45 395.5 216.1

CO2e emissions are estimated by multiplying mass emissions for each GHG by its global warming potential (GWP), 1, 25 and 298 for CO2, CH4 and N2O, respectively. Total CO2e is then estimated by summing CO2e estimates over all GHGs.

The CO2e emissions are reported as metric tons per phase.

Road Construction Emissions Model, Version 9.0.0

	 Harlan Road Realignn 	nent Project (Phase 2)		Total	Exhaust	Fugitive Dust	Total	Exhaust	Fugitive Dust					
Project Phases (Pounds)	ROG (lbs/day)	CO (Ibs/day)	NOx (Ibs/day)	PM10 (Ibs/day)	PM10 (lbs/day)	PM10 (lbs/day)	PM2.5 (Ibs/day)	PM2.5 (lbs/day)	PM2.5 (Ibs/day)	SOx (lbs/day)	CO2 (lbs/day)	CH4 (lbs/day)	N2O (Ibs/day)	CO2e (lbs/da
Grubbing/Land Clearing	1.18	10.39	12.37	10.54	0.54	10.00	2.56	0.48	2.08	0.02	2,228.28	0.59	0.05	2,257.05
Grading/Excavation	3.64	25.36	42.92	11.73	1.73	10.00	3.58	1.50	2.08	0.08	7,388.36	1.70	0.29	7,518.68
Drainage/Utilities/Sub-Grade	2.99	25.68	29.98	11.36	1.36	10.00	3.33	1.25	2.08	0.05	5,109.91	1.00	0.08	5,157.55
Paving	1.03	11.69	10.56	0.57	0.57	0.00	0.48	0.48	0.00	0.03	2,611.87	0.47	0.14	2,665.74
Maximum (pounds/day)	3.64	25.68	42.92	11.73	1.73	10.00	3.58	1.50	2.08	0.08	7,388.36	1.70	0.29	7,518.6
Total (tons/construction project)	0.12	0.96	1.34	0.43	0.06	0.37	0.13	0.05	0.08	0.00	235.77	0.05	0.01	239.28
Notes: Project Start Year ->	2021													
Project Length (months) ->	4													
Total Project Area (acres) ->	22													
Maximum Area Disturbed/Day (acres) ->	1													
Water Truck Used? ->	Yes						_							
	Total Material In	nported/Exported		Daily MAT	(miles/day)									
	Volume	(yd³/day)		Daily VIVIT	(mies/day)									
Phase	Soil	Asphalt	Soil Hauling	Asphalt Hauling	Worker Commute	Water Truck								
Grubbing/Land Clearing	0	0	0	0	280	40								
Grading/Excavation	214	0	330	0	880	40								
Drainage/Utilities/Sub-Grade	0	0	0	0	600	40								
		96	0	150	480	40								
Paving M10 and PM2.5 estimates assume 50% control of fugitive dust from wate	ering and associated	00	res if a minimum nu	mber of water trucks	are specified.		1							
PM10 and PM2.5 estimates assume 50% control of fugitive dust from wate Fotal PM10 emissions shown in column F are the sum of exhaust and fugit	itive dust emissions s HG by its global warr	dust control measur shown in columns G ning potential (GWP	and H. Total PM2.5	emissions shown in	Column I are the su	CO2e is then estimation	•							
PM10 and PM2.5 estimates assume 50% control of fugitive dust from wate Total PM10 emissions shown in column F are the sum of exhaust and fugi CO2e emissions are estimated by multiplying mass emissions for each GH	HG by its global warr	dust control measur shown in columns G ning potential (GWP nent Project (Phase 2)	and H. Total PM2.5), 1 , 25 and 298 for	emissions shown in CO2, CH4 and N2C Total	Column I are the sur o, respectively. Total (Exhaust	CO2e is then estima Fugitive Dust	ated by summing CC	2e estimates over a Exhaust	II GHGs. Fugitive Dust					
PM10 and PM2.5 estimates assume 50% control of fugitive dust from wate Total PM10 emissions shown in column F are the sum of exhaust and fugit CO2e emissions are estimated by multiplying mass emissions for each GH Total Emission Estimates by Phase for -> Project Phases	itive dust emissions s HG by its global warr	dust control measur shown in columns G ning potential (GWP	and H. Total PM2.5	emissions shown in CO2, CH4 and N2C	Column I are the sur), respectively. Total (CO2e is then estimation	ated by summing CC	2e estimates over a Exhaust	II GHGs. Fugitive Dust	SOx (tons/phase)	CO2 (tons/phase)	CH4 (tons/phase)	N2O (tons/phase)	CO2e (MT/ph
PM10 and PM2.5 estimates assume 50% control of fugitive dust from wate Total PM10 emissions shown in column F are the sum of exhaust and fugit CO2e emissions are estimated by multiplying mass emissions for each GH Total Emission Estimates by Phase for -> Project Phases Tons for all except CO2e. Metric tonnes for CO2e)	HG by its global warr	dust control measur shown in columns G ning potential (GWP nent Project (Phase 2)	and H. Total PM2.5), 1 , 25 and 298 for	emissions shown in CO2, CH4 and N2C Total	Column I are the sur o, respectively. Total (Exhaust	CO2e is then estima Fugitive Dust	ated by summing CC	2e estimates over a Exhaust	II GHGs. Fugitive Dust	SOx (tons/phase)	CO2 (tons/phase) 9.80	CH4 (tons/phase)	N2O (tons/phase)	CO2e (MT/ph 9.01
PM10 and PM2.5 estimates assume 50% control of fugitive dust from wate Total PM10 emissions shown in column F are the sum of exhaust and fugi CO2e emissions are estimated by multiplying mass emissions for each GH Total Emission Estimates by Phase for -> Project Phases Tons for all except CO2e. Metric tonnes for CO2e) Grubbing/Land Clearing	HG by its global warr HG by its global warr Harlan Road Realignn ROG (tons/phase)	dust control measur shown in columns G ning potential (GWP nent Project (Phase 2) CO (tons/phase)	and H. Total PM2.5), 1 , 25 and 298 for NOx (tons/phase)	emissions shown in CO2, CH4 and N2C Total PM10 (tons/phase)	, column I are the sur , respectively. Total (Exhaust PM10 (tons/phase)	CO2e is then estim Fugitive Dust PM10 (tons/phase)	Total PM2.5 (tons/phase)	2e estimates over a Exhaust PM2.5 (tons/phase)	III GHGs. Fugitive Dust PM2.5 (tons/phase)	/		(*******		9.01
PM10 and PM2.5 estimates assume 50% control of fugitive dust from water Total PM10 emissions shown in column F are the sum of exhaust and fugit CO2e emissions are estimated by multiplying mass emissions for each GH Total Emission Estimates by Phase for -> Project Phases Tons for all except CO2e. Metric tonnes for CO2e) Grubbing/Land Clearing Grading/Excavation	itive dust emissions e HG by its global warr Harlan Road Realignn ROG (tons/phase) 0.01	dust control measure shown in columns G ning potential (GWP nent Project (Phase 2) CO (tons/phase) 0.05	and H. Total PM2.5), 1 , 25 and 298 for NOx (tons/phase) 0.05	emissions shown in CO2, CH4 and N2C Total PM10 (tons/phase) 0.05	Column I are the sur o, respectively. Total (Exhaust PM10 (tons/phase) 0.00	CO2e is then estima Fugitive Dust PM10 (tons/phase) 0.04	Total PM2.5 (tons/phase) 0.01	2e estimates over a Exhaust PM2.5 (tons/phase) 0.00	II GHGs. Fugitive Dust PM2.5 (tons/phase) 0.01	0.00	9.80	0.00	0.00	9.01
PM10 and PM2.5 estimates assume 50% control of fugitive dust from wate Total PM10 emissions shown in column F are the sum of exhaust and fugit CO2e emissions are estimated by multiplying mass emissions for each GH Total Emission Estimates by Phase for -> Project Phases Tons for all except CO2e. Metric tonnes for CO2e) Grubbing/Land Clearing Grubbing/Land Clearing Grading/Excavation Drainage/Utilities/Sub-Grade	itive dust emissions : HG by its global warr Harlan Road Realignn ROG (tons/phase) 0.01 0.06	dust control measuu shown in columns G ning potential (GWP nent Project (Phase 2) CO (tons/phase) 0.05 0.45	and H. Total PM2.5), 1 , 25 and 298 for NOx (tons/phase) 0.05 0.76	emissions shown in CO2, CH4 and N2C Total PM10 (tons/phase) 0.05 0.21	Column I are the sur p, respectively. Total (Exhaust PM10 (tons/phase) 0.00 0.03	CO2e is then estim Fugitive Dust PM10 (tons/phase) 0.04 0.18	Total PM2.5 (tons/phase) 0.01 0.06	Exhaust PM2.5 (tons/phase) 0.00 0.03	Fugitive Dust PM2.5 (tons/phase) 0.01 0.04	0.00	9.80 130.04	0.00 0.03	0.00 0.01	9.01 120.05
PM10 and PM2.5 estimates assume 50% control of fugitive dust from water Total PM10 emissions shown in column F are the sum of exhaust and fugit CO2e emissions are estimated by multiplying mass emissions for each GH Total Emission Estimates by Phase for ->	titive dust emissions i HG by its global warr Harlan Road Realignn ROG (tons/phase) 0.01 0.06 0.05	dust control measuu shown in columns G ning potential (GWP nent Project (Phase 2) CO (tons/phase) 0.05 0.45 0.40	and H. Total PM2.5), 1 , 25 and 298 for NOx (tons/phase) 0.05 0.76 0.46	emissions shown in CO2, CH4 and N2C Total PM10 (tons/phase) 0.05 0.21 0.17	Column I are the sur , respectively. Total (Exhaust PM10 (tons/phase) 0.00 0.03 0.02	Fugitive Dust PM10 (tons/phase) 0.04 0.18 0.15	Total PM2.5 (tons/phase) 0.01 0.06 0.05	2e estimates over a Exhaust PM2.5 (tons/phase) 0.00 0.03 0.02	III GHGs. Fugitive Dust PM2.5 (tons/phase) 0.01 0.04 0.03	0.00 0.00 0.00	9.80 130.04 78.69	0.00 0.03 0.02	0.00 0.01 0.00	9.01 120.05 72.06

Total PM10 emissions shown in column F are the sum of exhaust and fugitive dust emissions shown in columns G and H. Total PM2.5 emissions shown in Column I are the sum of exhaust and fugitive dust emissions shown in columns J and K.

CO2e emissions are estimated by multiplying mass emissions for each GHG by its global warming potential (GWP), 1, 25 and 298 for CO2, CH4 and N2O, respectively. Total CO2e is then estimated by summing CO2e estimates over all GHGs.

The CO2e emissions are reported as metric tons per phase.

Road Construction Emissions Model, Version 9.0.0

Daily Emission Estimates for ->	Harlan Road Realignn	nent Project		Total	Exhaust	Fugitive Dust	Total	Exhaust	Fugitive Dust					
Project Phases (Pounds)	ROG (lbs/day)	CO (lbs/day)	NOx (lbs/day)	PM10 (Ibs/day)	PM10 (Ibs/day)	PM10 (lbs/day)	PM2.5 (lbs/day)	PM2.5 (lbs/day)	PM2.5 (lbs/day)	SOx (lbs/day)	CO2 (lbs/day)	CH4 (lbs/day)	N2O (Ibs/day)	CO2e (Ibs/da
Grubbing/Land Clearing	1.18	10.39	12.37	10.54	0.54	10.00	2.56	0.48	2.08	0.02	2,228.28	0.59	0.05	2,257.05
Grading/Excavation	3.67	25.64	45.02	11.80	1.80	10.00	3.61	1.53	2.08	0.09	8,565.16	1.70	0.48	8,750.63
Drainage/Utilities/Sub-Grade	2.99	25.68	29.98	11.36	1.36	10.00	3.33	1.25	2.08	0.05	5,109.91	1.00	0.08	5,157.55
Paving	1.05	11.91	12.20	0.63	0.63	0.00	0.51	0.51	0.00	0.04	3,552.02	0.48	0.29	3,649.96
Maximum (pounds/day)	3.67	25.68	45.02	11.80	1.80	10.00	3.61	1.53	2.08	0.09	8,565.16	1.70	0.48	8,750.63
Total (tons/construction project)	0.37	2.91	4.17	1.30	0.18	1.12	0.39	0.16	0.23	0.01	788.06	0.15	0.04	802.37
Notes: Project Start Year ->	2021													
Project Length (months) ->	12													
Total Project Area (acres) ->	46													
Maximum Area Disturbed/Day (acres) ->	1													
Water Truck Used? ->	Yes													
	Total Material In	nported/Exported		Daily MAT	(miles/day)									
	Volume	(yd³/day)		Daily VIVI	(miles/day)									
Phase	Soil	Asphalt	Soil Hauling	Asphalt Hauling	Worker Commute	Water Truck								
Grubbing/Land Clearing	0	41	0	0	280	40								
Grading/Excavation	0	415	0	630	880	40								
Drainage/Utilities/Sub-Grade	0	0	0	0	600	40								
Paving	0	253	0	390	480	40								
PM10 and PM2.5 estimates assume 50% control of fugitive dust from wat Total PM10 emissions shown in column F are the sum of exhaust and fug CO2e emissions are estimated by multiplying mass emissions for each Gl	itive dust emissions s HG by its global warr	shown in columns G ning potential (GWF	and H. Total PM2.5	emissions shown in CO2, CH4 and N2C	Column I are the su), respectively. Total	CO2e is then estim	ated by summing CC	2e estimates over a	II GHGs.					
Total Emission Estimates by Phase for ->	 Harlan Road Realignn 	nent Project		Total	Exhaust	Fugitive Dust	Total	Exhaust	Fugitive Dust					
Project Phases	ROG (tons/phase)	CO (tons/phase)	NOx (tons/phase)	PM10 (tons/phase)	PM10 (tons/phase)	PM10 (tons/phase)	PM2.5 (tons/phase)	PM2.5 (tons/phase)	PM2.5 (tons/phase)	SOx (tons/phase)	CO2 (tons/phase)	CH4 (tons/phase)	N2O (tons/phase)	CO2e (MT/pha
					0.04	0.13	0.03	0.01	0.03	0.00	29.41	0.01	0.00	27.03
(Tons for all except CO2e. Metric tonnes for CO2e)	0.02	0.14	0.16	0.14	0.01	0.15								
(Tons for all except CO2e. Metric tonnes for CO2e) Grubbing/Land Clearing	0.02 0.19	0.14 1.35	0.16 2.38	0.14 0.62	0.01	0.53	0.19	0.08	0.11	0.00	452.24	0.09	0.03	419.15
(Tons for all except CO2e. Metric tonnes for CO2e) Grubbing/Land Clearing Grading/Excavation Drainage/Utilities/Sub-Grade								0.08 0.06	0.11 0.10	0.00 0.00	452.24 236.08	0.09 0.05	0.03	419.15 216.17
(Tons for all except CO2e. Metric tonnes for CO2e) Grubbing/Land Clearing Grading/Excavation Drainage/Utilities/Sub-Grade	0.19	1.35	2.38	0.62	0.10	0.53	0.19							
(Tons for all except CO2e. Metric tonnes for CO2e) Grubbing/Land Clearing Grading/Excavation	0.19 0.14	1.35 1.19	2.38 1.38	0.62 0.52	0.10 0.06	0.53 0.46	0.19 0.15	0.06	0.10	0.00	236.08	0.05	0.00	216.17

Total PM10 emissions shown in column F are the sum of exhaust and fugitive dust emissions shown in columns G and H. Total PM2.5 emissions shown in Column I are the sum of exhaust and fugitive dust emissions shown in columns J and K.

CO2e emissions are estimated by multiplying mass emissions for each GHG by its global warming potential (GWP), 1, 25 and 298 for CO2, CH4 and N2O, respectively. Total CO2e is then estimated by summing CO2e estimates over all GHGs.

The CO2e emissions are reported as metric tons per phase.

Attachment C: CNDDB, USFWS, NMFS and CNPS Species List and Species Potential Table





Query Criteria:

Quad IS (Lathrop (3712173) OR Manteca (3712172) OR Stockton East (3712182) OR Stockton West (3712183) OR Union Island (3712174) OR Holt (3712184))

Species	Element Code	Federal Status	State Status	Global Rank	State Rank	Rare Plant Rank/CDFW SSC or FP
alkali milk-vetch	PDFAB0F8R1	None	None	G2T1	S1	1B.2
Astragalus tener var. tener						
American badger	AMAJF04010	None	None	G5	S3	SSC
Taxidea taxus						
big tarplant	PDAST1C011	None	None	G1G2	S1S2	1B.1
Blepharizonia plumosa						
bristly sedge	PMCYP032Y0	None	None	G5	S2	2B.1
Carex comosa						
burrowing owl	ABNSB10010	None	None	G4	S3	SSC
Athene cunicularia						
California black rail	ABNME03041	None	Threatened	G3G4T1	S1	FP
Laterallus jamaicensis coturniculus						
California tiger salamander Ambystoma californiense	AAAAA01180	Threatened	Threatened	G2G3	S2S3	WL
caper-fruited tropidocarpum Tropidocarpum capparideum	PDBRA2R010	None	None	G1	S1	1B.1
Coastal and Valley Freshwater Marsh Coastal and Valley Freshwater Marsh	CTT52410CA	None	None	G3	S2.1	
Crotch bumble bee Bombus crotchii	IIHYM24480	None	Candidate Endangered	G3G4	S1S2	
Delta button-celery Eryngium racemosum	PDAPI0Z0S0	None	Endangered	G1	S1	1B.1
Delta mudwort Limosella australis	PDSCR10030	None	None	G4G5	S2	2B.1
Delta smelt Hypomesus transpacificus	AFCHB01040	Threatened	Endangered	G1	S1	
Delta tule pea Lathyrus jepsonii var. jepsonii	PDFAB250D2	None	None	G5T2	S2	1B.2
giant gartersnake Thamnophis gigas	ARADB36150	Threatened	Threatened	G2	S2	
Great Valley Valley Oak Riparian Forest Great Valley Valley Oak Riparian Forest	CTT61430CA	None	None	G1	S1.1	
heartscale	PDCHE040B0	None	None	G3T2	S2	1B.2
Atriplex cordulata var. cordulata						
least Bell's vireo	ABPBW01114	Endangered	Endangered	G5T2	S2	
Vireo bellii pusillus		2	5			
loggerhead shrike Lanius ludovicianus	ABPBR01030	None	None	G4	S4	SSC



Selected Elements by Common Name California Department of Fish and Wildlife California Natural Diversity Database



Species	Element Code	Federal Status	State Status	Global Rank	State Rank	Rare Plant Rank/CDFW SSC or FP
longfin smelt	AFCHB03010	Candidate	Threatened	G5	S1	
Spirinchus thaleichthys						
Mason's lilaeopsis	PDAPI19030	None	Rare	G2	S2	1B.1
Lilaeopsis masonii						
moestan blister beetle	IICOL4C020	None	None	G2	S2	
Lytta moesta						
palmate-bracted bird's-beak	PDSCR0J0J0	Endangered	Endangered	G1	S1	1B.1
Chloropyron palmatum						
recurved larkspur	PDRAN0B1J0	None	None	G2?	S2?	1B.2
Delphinium recurvatum						
riparian brush rabbit	AMAEB01021	Endangered	Endangered	G5T1	S1	
Sylvilagus bachmani riparius						
saline clover	PDFAB400R5	None	None	G2	S2	1B.2
Trifolium hydrophilum						
San Joaquin Pocket Mouse	AMAFD01060	None	None	G2G3	S2S3	
Perognathus inornatus						
San Joaquin spearscale	PDCHE041F3	None	None	G2	S2	1B.2
Extriplex joaquinana						
Sanford's arrowhead	PMALI040Q0	None	None	G3	S3	1B.2
Sagittaria sanfordii						
slough thistle	PDAST2E0U0	None	None	G1	S1	1B.1
Cirsium crassicaule						
song sparrow ("Modesto" population)	ABPBXA3010	None	None	G5	S3?	SSC
Melospiza melodia						
steelhead - Central Valley DPS	AFCHA0209K	Threatened	None	G5T2Q	S2	
Oncorhynchus mykiss irideus pop. 11						
Suisun Marsh aster	PDASTE8470	None	None	G2	S2	1B.2
Symphyotrichum lentum						
Swainson's hawk	ABNKC19070	None	Threatened	G5	S3	
Buteo swainsoni						
tricolored blackbird	ABPBXB0020	None	Threatened	G2G3	S1S2	SSC
Agelaius tricolor						
valley elderberry longhorn beetle	IICOL48011	Threatened	None	G3T2	S2	
Desmocerus californicus dimorphus						
watershield	PDCAB01010	None	None	G5	S3	2B.3
Brasenia schreberi						
western bumble bee	IIHYM24250	None	Candidate	G2G3	S1	
Bombus occidentalis			Endangered			
western pond turtle	ARAAD02030	None	None	G3G4	S3	SSC
Emys marmorata						
western spadefoot Spea hammondii	AAABF02020	None	None	G3	S3	SSC



Selected Elements by Common Name

California Department of Fish and Wildlife

California Natural Diversity Database



Species	Element Code	Federal Status	State Status	Global Rank	State Rank	Rare Plant Rank/CDFW SSC or FP
white-tailed kite	ABNKC06010	None	None	G5	S3S4	FP
Elanus leucurus						
woolly rose-mallow	PDMAL0H0R3	None	None	G5T3	S3	1B.2
Hibiscus lasiocarpos var. occidentalis						
Wright's trichocoronis	PDAST9F031	None	None	G4T3	S1	2B.1
Trichocoronis wrightii var. wrightii						
yellow-headed blackbird	ABPBXB3010	None	None	G5	S3	SSC
Xanthocephalus xanthocephalus						

Record Count: 44



United States Department of the Interior

FISH AND WILDLIFE SERVICE Sacramento Fish And Wildlife Office Federal Building 2800 Cottage Way, Room W-2605 Sacramento, CA 95825-1846 Phone: (916) 414-6600 Fax: (916) 414-6713



In Reply Refer To: Consultation Code: 08ESMF00-2020-SLI-2160 Event Code: 08ESMF00-2020-E-06610 Project Name: Harlan Road Realignment Project June 10, 2020

Subject: List of threatened and endangered species that may occur in your proposed project location, and/or may be affected by your proposed project

To Whom It May Concern:

The enclosed species list identifies threatened, endangered, proposed and candidate species, as well as proposed and final designated critical habitat, under the jurisdiction of the U.S. Fish and Wildlife Service (Service) that may occur within the boundary of your proposed project and/or may be affected by your proposed project. The species list fulfills the requirements of the Service under section 7(c) of the Endangered Species Act (Act) of 1973, as amended (16 U.S.C. 1531 *et seq.*).

Please follow the link below to see if your proposed project has the potential to affect other species or their habitats under the jurisdiction of the National Marine Fisheries Service:

http://www.nwr.noaa.gov/protected_species/species_list/species_lists.html

New information based on updated surveys, changes in the abundance and distribution of species, changed habitat conditions, or other factors could change this list. Please feel free to contact us if you need more current information or assistance regarding the potential impacts to federally proposed, listed, and candidate species and federally designated and proposed critical habitat. Please note that under 50 CFR 402.12(e) of the regulations implementing section 7 of the Act, the accuracy of this species list should be verified after 90 days. This verification can be completed formally or informally as desired. The Service recommends that verification be completed by visiting the ECOS-IPaC website at regular intervals during project planning and implementation for updates to species lists and information. An updated list may be requested through the ECOS-IPaC system by completing the same process used to receive the enclosed list.

The purpose of the Act is to provide a means whereby threatened and endangered species and the ecosystems upon which they depend may be conserved. Under sections 7(a)(1) and 7(a)(2) of the Act and its implementing regulations (50 CFR 402 *et seq.*), Federal agencies are required to utilize their authorities to carry out programs for the conservation of threatened and endangered species and to determine whether projects may affect threatened and endangered species and/or designated critical habitat.

A Biological Assessment is required for construction projects (or other undertakings having similar physical impacts) that are major Federal actions significantly affecting the quality of the human environment as defined in the National Environmental Policy Act (42 U.S.C. 4332(2) (c)). For projects other than major construction activities, the Service suggests that a biological evaluation similar to a Biological Assessment be prepared to determine whether the project may affect listed or proposed species and/or designated or proposed critical habitat. Recommended contents of a Biological Assessment are described at 50 CFR 402.12.

If a Federal agency determines, based on the Biological Assessment or biological evaluation, that listed species and/or designated critical habitat may be affected by the proposed project, the agency is required to consult with the Service pursuant to 50 CFR 402. In addition, the Service recommends that candidate species, proposed species and proposed critical habitat be addressed within the consultation. More information on the regulations and procedures for section 7 consultation, including the role of permit or license applicants, can be found in the "Endangered Species Consultation Handbook" at:

http://www.fws.gov/endangered/esa-library/pdf/TOC-GLOS.PDF

Please be aware that bald and golden eagles are protected under the Bald and Golden Eagle Protection Act (16 U.S.C. 668 *et seq.*), and projects affecting these species may require development of an eagle conservation plan (http://www.fws.gov/windenergy/ eagle_guidance.html). Additionally, wind energy projects should follow the wind energy guidelines (http://www.fws.gov/windenergy/) for minimizing impacts to migratory birds and bats.

Guidance for minimizing impacts to migratory birds for projects including communications towers (e.g., cellular, digital television, radio, and emergency broadcast) can be found at: http://www.fws.gov/migratorybirds/CurrentBirdIssues/Hazards/towers/towers.htm; http://www.towerkill.com; and http://www.fws.gov/migratorybirds/CurrentBirdIssues/Hazards/towers/correntBirdIssues/Hazards/towers/comtow.html.

We appreciate your concern for threatened and endangered species. The Service encourages Federal agencies to include conservation of threatened and endangered species into their project planning to further the purposes of the Act. Please include the Consultation Tracking Number in the header of this letter with any request for consultation or correspondence about your project that you submit to our office.

Attachment(s):

Official Species List

Official Species List

This list is provided pursuant to Section 7 of the Endangered Species Act, and fulfills the requirement for Federal agencies to "request of the Secretary of the Interior information whether any species which is listed or proposed to be listed may be present in the area of a proposed action".

This species list is provided by:

Sacramento Fish And Wildlife Office

Federal Building 2800 Cottage Way, Room W-2605 Sacramento, CA 95825-1846 (916) 414-6600

Project Summary

Consultation Code:	08ESMF00-2020-SLI-2160
Event Code:	08ESMF00-2020-E-06610
Project Name:	Harlan Road Realignment Project

Project Type: TRANSPORTATION

Project Description: Road realignment

Project Location:

Approximate location of the project can be viewed in Google Maps: <u>https://www.google.com/maps/place/37.854715335180714N121.27829596157076W</u>



Counties: San Joaquin, CA

Endangered Species Act Species

There is a total of 8 threatened, endangered, or candidate species on this species list.

Species on this list should be considered in an effects analysis for your project and could include species that exist in another geographic area. For example, certain fish may appear on the species list because a project could affect downstream species.

IPaC does not display listed species or critical habitats under the sole jurisdiction of NOAA Fisheries¹, as USFWS does not have the authority to speak on behalf of NOAA and the Department of Commerce.

See the "Critical habitats" section below for those critical habitats that lie wholly or partially within your project area under this office's jurisdiction. Please contact the designated FWS office if you have questions.

1. NOAA Fisheries, also known as the National Marine Fisheries Service (NMFS), is an office of the National Oceanic and Atmospheric Administration within the Department of Commerce.

Mammals

NAME	STATUS
Riparian Brush Rabbit <i>Sylvilagus bachmani riparius</i> No critical habitat has been designated for this species.	Endangered
Species profile: <u>https://ecos.fws.gov/ecp/species/6189</u>	
Reptiles	
NAME	STATUS

Giant Garter Snake *Thamnophis gigas* No critical habitat has been designated for this species. Species profile: https://ecos.fws.gov/ecp/species/4482

STATUS

Threatened

NAME	STATUS
California Red-legged Frog <i>Rana draytonii</i> There is final critical habitat for this species. Your location is outside the critical habitat. Species profile: <u>https://ecos.fws.gov/ecp/species/2891</u> Species survey guidelines: <u>https://ecos.fws.gov/ipac/guideline/survey/population/205/office/11420.pdf</u>	Threatened
California Tiger Salamander <i>Ambystoma californiense</i> Population: U.S.A. (Central CA DPS) There is final critical habitat for this species. Your location is outside the critical habitat. Species profile: <u>https://ecos.fws.gov/ecp/species/2076</u>	Threatened

Fishes

NAME	STATUS
Delta Smelt Hypomesus transpacificus	Threatened
There is final critical habitat for this species. Your location is outside the critical habitat.	
Species profile: <u>https://ecos.fws.gov/ecp/species/321</u>	

Insects

NAME	STATUS
Valley Elderberry Longhorn Beetle Desmocerus californicus dimorphus	Threatened
There is final critical habitat for this species. Your location is outside the critical habitat.	
Species profile: <u>https://ecos.fws.gov/ecp/species/7850</u>	
Habitat assessment guidelines:	
https://ecos.fws.gov/ipac/guideline/assessment/population/436/office/11420.pdf	

Crustaceans

NAME	STATUS
Vernal Pool Fairy Shrimp <i>Branchinecta lynchi</i> There is final critical habitat for this species. Your location is outside the critical habitat. Species profile: <u>https://ecos.fws.gov/ecp/species/498</u>	Threatened
Vernal Pool Tadpole Shrimp <i>Lepidurus packardi</i> There is final critical habitat for this species. Your location is outside the critical habitat. Species profile: <u>https://ecos.fws.gov/ecp/species/2246</u>	Endangered

Critical habitats

THERE ARE NO CRITICAL HABITATS WITHIN YOUR PROJECT AREA UNDER THIS OFFICE'S JURISDICTION.

From:	Courtney Owens
To:	"NMFSWCRCA Specieslist - NOAA Service Account"
Subject:	Harlan Road Realignment at Roth Road, San Joaquin County
Date:	Monday, January 6, 2020 11:48:17 AM

Project Name: Harlan Road Realignment at Roth Road CEQA Lead: The City of Lathrop

Quad Name Lathrop Quad Number 37121-G3 ESA Anadromous Fish SONCC Coho ESU (T) -CCC Coho ESU (E) -CC Chinook Salmon ESU (T) -CVSR Chinook Salmon ESU (T) -SRWR Chinook Salmon ESU (E) -NC Steelhead DPS (T) -CCC Steelhead DPS (T) -SCCC Steelhead DPS (T) -SC Steelhead DPS (T) -

CCV Steelhead DPS (T) -

Eulachon (T) -

sDPS Green Sturgeon (T) -

ESA Anadromous Fish Critical Habitat

X

X

X

X

SONCC Coho Critical Habitat -CCC Coho Critical Habitat -CC Chinook Salmon Critical Habitat -CVSR Chinook Salmon Critical Habitat -SRWR Chinook Salmon Critical Habitat -NC Steelhead Critical Habitat -CCC Steelhead Critical Habitat -SCCC Steelhead Critical Habitat -SC Steelhead Critical Habitat -SC Steelhead Critical Habitat -CCV Steelhead Critical Habitat -Eulachon Critical Habitat -Eulachon Critical Habitat -SDPS Green Sturgeon Critical Habitat -

Range Black Abalone (E) -

Range White Abalone (E) -

ESA Marine Invertebrates Critical Habitat

Black Abalone Critical Habitat - **ESA Sea Turtles**

East Pacific Green Sea Turtle (T) -Olive Ridley Sea Turtle (T/E) -Leatherback Sea Turtle (E) -North Pacific Loggerhead Sea Turtle (E) -

ESA Whales

Blue Whale (E) -Fin Whale (E) -Humpback Whale (E) -Southern Resident Killer Whale (E) -North Pacific Right Whale (E) -Sei Whale (E) -Sperm Whale (E) -

ESA Pinnipeds

Guadalupe Fur Seal (T) -Steller Sea Lion Critical Habitat -

Essential Fish Habitat

Coho EFH -

Chinook Salmon EFH -

Groundfish EFH -

Coastal Pelagics EFH -

Highly Migratory Species EFH -

MMPA Species (See list at left)

ESA and MMPA Cetaceans/Pinnipeds

See list at left and consult the NMFS Long Beach office 562-980-4000

X

MMPA Cetaceans -MMPA Pinnipeds -

Quad Name Stockton West

Quad Number 37121-H3

ESA Anadromous Fish

SONCC Coho ESU (T) -CCC Coho ESU (E) -CC Chinook Salmon ESU (T) -CVSR Chinook Salmon ESU (T) -SRWR Chinook Salmon ESU (E) -NC Steelhead DPS (T) - CCC Steelhead DPS (T) -SCCC Steelhead DPS (T) -SC Steelhead DPS (E) -CCV Steelhead DPS (T) -Eulachon (T) -

sDPS Green Sturgeon (T) -

ESA Anadromous Fish Critical Habitat

X

X

SONCC Coho Critical Habitat -CCC Coho Critical Habitat -CC Chinook Salmon Critical Habitat -CVSR Chinook Salmon Critical Habitat -SRWR Chinook Salmon Critical Habitat -NC Steelhead Critical Habitat -CCC Steelhead Critical Habitat -SC Steelhead Critical Habitat -SC Steelhead Critical Habitat -CCV Steelhead Critical Habitat -CCV Steelhead Critical Habitat -SDPS Green Sturgeon Critical Habitat - **K ESA Marine Invertebrates**

Range Black Abalone (E) -Range White Abalone (E) -

ESA Marine Invertebrates Critical Habitat

Black Abalone Critical Habitat -

ESA Sea Turtles

East Pacific Green Sea Turtle (T) -Olive Ridley Sea Turtle (T/E) -Leatherback Sea Turtle (E) -North Pacific Loggerhead Sea Turtle (E) -

ESA Whales

Blue Whale (E) -Fin Whale (E) -Humpback Whale (E) -Southern Resident Killer Whale (E) -North Pacific Right Whale (E) -Sei Whale (E) -Sperm Whale (E) -

ESA Pinnipeds

Guadalupe Fur Seal (T) -

Steller Sea Lion Critical Habitat -

Essential Fish Habitat

Coho EFH -

Chinook Salmon EFH -

Groundfish EFH -

X

Coastal Pelagics EFH -Highly Migratory Species EFH -

MMPA Species (See list at left) ESA and MMPA Cetaceans/Pinnipeds

See list at left and consult the NMFS Long Beach office 562-980-4000

X

MMPA Cetaceans -MMPA Pinnipeds -

Quad Name Stockton East

Quad Number 37121-H2

ESA Anadromous Fish

SONCC Coho ESU (T) -CCC Coho ESU (E) -

CC Chinook Salmon ESU (T) -

CVSR Chinook Salmon ESU (T) -

SRWR Chinook Salmon ESU (E) -

NC Steelhead DPS (T) -

CCC Steelhead DPS (T) -

SCCC Steelhead DPS (T) -

SC Steelhead DPS (E) -

CCV Steelhead DPS (T) -

Eulachon (T) -

sDPS Green Sturgeon (T) -

ESA Anadromous Fish Critical Habitat

SONCC Coho Critical Habitat -

CCC Coho Critical Habitat -

CC Chinook Salmon Critical Habitat -

CVSR Chinook Salmon Critical Habitat -

SRWR Chinook Salmon Critical Habitat -

NC Steelhead Critical Habitat -

CCC Steelhead Critical Habitat -

SCCC Steelhead Critical Habitat -

SC Steelhead Critical Habitat -

CCV Steelhead Critical Habitat -Eulachon Critical Habitat sDPS Green Sturgeon Critical Habitat -

ESA Marine Invertebrates

Range Black Abalone (E) -Range White Abalone (E) -

ESA Marine Invertebrates Critical Habitat

X

Black Abalone Critical Habitat -

ESA Sea Turtles

East Pacific Green Sea Turtle (T) -Olive Ridley Sea Turtle (T/E) -Leatherback Sea Turtle (E) -North Pacific Loggerhead Sea Turtle (E) -

ESA Whales

Blue Whale (E) -Fin Whale (E) -Humpback Whale (E) -Southern Resident Killer Whale (E) -North Pacific Right Whale (E) -Sei Whale (E) -Sperm Whale (E) -

ESA Pinnipeds

Guadalupe Fur Seal (T) -

Steller Sea Lion Critical Habitat -

Essential Fish Habitat

Coho EFH -

Chinook Salmon EFH -

Groundfish EFH -

Coastal Pelagics EFH -

Highly Migratory Species EFH -

MMPA Species (See list at left)

ESA and MMPA Cetaceans/Pinnipeds

See list at left and consult the NMFS Long Beach office 562-980-4000

MMPA Cetaceans -MMPA Pinnipeds -

Quad Name Manteca Quad Number 37121-G2

ESA Anadromous Fish

SONCC Coho ESU (T) -CCC Coho ESU (E) -CC Chinook Salmon ESU (T) -CVSR Chinook Salmon ESU (T) -SRWR Chinook Salmon ESU (E) -NC Steelhead DPS (T) -CCC Steelhead DPS (T) -SCCC Steelhead DPS (T) -SC Steelhead DPS (E) -CCV Steelhead DPS (T) -

sDPS Green Sturgeon (T) -

ESA Anadromous Fish Critical Habitat

SONCC Coho Critical Habitat -CCC Coho Critical Habitat -CC Chinook Salmon Critical Habitat -CVSR Chinook Salmon Critical Habitat -SRWR Chinook Salmon Critical Habitat -NC Steelhead Critical Habitat -CCC Steelhead Critical Habitat -SCCC Steelhead Critical Habitat -SC Steelhead Critical Habitat -CCV Steelhead Critical Habitat -Eulachon Critical Habitat -

ESA Marine Invertebrates

Range Black Abalone (E) -

Range White Abalone (E) -

ESA Marine Invertebrates Critical Habitat

Black Abalone Critical Habitat -

ESA Sea Turtles

East Pacific Green Sea Turtle (T) -

Olive Ridley Sea Turtle (T/E) -

Leatherback Sea Turtle (E) -

North Pacific Loggerhead Sea Turtle (E) -

ESA Whales

Blue Whale (E) -Fin Whale (E) -Humpback Whale (E) - Southern Resident Killer Whale (E) -North Pacific Right Whale (E) -Sei Whale (E) -Sperm Whale (E) -

ESA Pinnipeds

Guadalupe Fur Seal (T) -Steller Sea Lion Critical Habitat -

Essential Fish Habitat

Coho EFH -

Chinook Salmon EFH -

Groundfish EFH -

Coastal Pelagics EFH -

Highly Migratory Species EFH -

MMPA Species (See list at left)

ESA and MMPA Cetaceans/Pinnipeds

See list at left and consult the NMFS Long Beach office 562-980-4000

X

MMPA Cetaceans -MMPA Pinnipeds -

Regards,

Courtney S. Owens, M.S. Environmental Planner II/Biologist **DOKKEN ENGINEERING** 110 Blue Ravine Road, Suite 200, Folsom, CA 95630 Phone: (916) 858-0642 - Fax: (916) 858-0643



*The database used to provide updates to the Online Inventory is under construction. <u>View updates and changes made since May 2019 here</u>.

Plant List

18 matches found. Click on scientific name for details

Search Criteria

Found in Quads 3712184, 3712183, 3712182, 3712174 3712173 and 3712172;

© Modify Search Criteria Export to Excel Modify Columns 20 Modify Sort ■ Display Photos

Scientific Name	Common Name	Family	Lifeform	Blooming Period	CA Rare Plaı Rank	ntState Rank	Global Rank
<u>Astragalus tener var. tener</u>	alkali milk-vetch	Fabaceae	annual herb	Mar-Jun	1B.2	S1	G2T1
<u>Atriplex cordulata var.</u> <u>cordulata</u>	heartscale	Chenopodiaceae	annual herb	Apr-Oct	1B.2	S2	G3T2
<u>Blepharizonia plumosa</u>	big tarplant	Asteraceae	annual herb	Jul-Oct	1B.1	S1S2	G1G2
Brasenia schreberi	watershield	Cabombaceae	perennial rhizomatous herb (aquatic)	Jun-Sep	2B.3	S3	G5
Carex comosa	bristly sedge	Cyperaceae	perennial rhizomatous herb	May-Sep	2B.1	S2	G5
<u>Centromadia parryi ssp.</u> <u>rudis</u>	Parry's rough tarplant	Asteraceae	annual herb	May-Oct	4.2	S3	G3T3
Chloropyron palmatum	palmate-bracted bird's-beak	Orobanchaceae	annual herb (hemiparasitic)	May-Oct	1B.1	S1	G1
Cirsium crassicaule	slough thistle	Asteraceae	annual / perennial herb	May-Aug	1B.1	S1	G1
Delphinium recurvatum	recurved larkspur	Ranunculaceae	perennial herb	Mar-Jun	1B.2	S2?	G2?
Eryngium racemosum	Delta button-celery	Apiaceae	annual / perennial herb	Jun-Oct	1B.1	S1	G1
<u>Extriplex joaquinana</u>	San Joaquin spearscale	Chenopodiaceae	annual herb	Apr-Oct	1B.2	S2	G2
<u>Hibiscus lasiocarpos var.</u> <u>occidentalis</u>	woolly rose-mallow	Malvaceae	perennial rhizomatous herb (emergent)	Jun-Sep	1B.2	S3	G5T3
<u>Lathyrus jepsonii var.</u> j <u>epsonii</u>	Delta tule pea	Fabaceae	perennial herb	May- Jul(Aug- Sep)	1B.2	S2	G5T2
<u>Lilaeopsis masonii</u>	Mason's lilaeopsis	Apiaceae	perennial rhizomatous herb	Apr-Nov	1B.1	S2	G2
Sagittaria sanfordii	Sanford's arrowhead	Alismataceae	perennial rhizomatous herb (emergent)	May- Oct(Nov)	1B.2	S3	G3
Symphyotrichum lentum	Suisun Marsh aster	Asteraceae	perennial rhizomatous herb	(Apr)May- Nov	1B.2	S2	G2
<u>Trichocoronis wrightii var.</u> <u>wrightii</u>	Wright's trichocoronis	Asteraceae	annual herb	May-Sep	2B.1	S1	G4T3
Trifolium hydrophilum	saline clover	Fabaceae	annual herb	Apr-Jun	1B.2	S2	G2

Suggested Citation

California Native Plant Society, Rare Plant Program. 2020. Inventory of Rare and Endangered Plants of California (online edition, v8-03 0.39). Website http://www.rareplants.cnps.org [accessed 10 June 2020].

Search the Inventory Simple Search Advanced Search Glossary

Information About the Inventory About the Rare Plant Program CNPS Home Page About CNPS Join CNPS

Contributors

<u>The Califora Database</u> <u>The California Lichen Society</u> <u>California Natural Diversity Database</u> <u>The Jepson Flora Project</u> <u>The Consortium of California Herbaria</u> <u>CalPhotos</u>

Questions and Comments

rareplants@cnps.org

© Copyright 2010-2018 California Native Plant Society. All rights reserved.

Common Name	Species Name	Status		General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
Amphibian Species	s Rana draytonii	Fed: CA: CDFW:	T SSC	The California red-legged frog occupies a fairly distinct habitat, combining both specific water (aquatic) and upland (terrestrial) components. California red-legged frog habitat includes nearly any area within 1-2 miles of a breeding site that stays moist and cool throughout the summer; this includes non-breeding aquatic habitat in pools of slow- moving streams, perennial or ephemeral ponds, and upland sheltering habitat such as rocks, small mammal burrows, logs, densely vegetated areas, and even, man- made structures (i.e. culverts, livestock troughs, spring-boxes, abandoned sheds). Breeding sites are generally found in deep, still or slow-moving water (greater than 2.5 feet) and can have a wide range of edge and emergent cover amounts. California red-legged frogs can breed at sites with dense shrubby riparian or emergent vegetation, such as cattails, tules, or overhanging willows or can proliferate in ponds devoid of emergent vegetation and any apparent vegetative cover (i.e., stock ponds). Breeds from late November to late April Occurs from elevations near sea level to 5,200 ft.	A	Not expected to occur: The Project area lacks any water resources required by the species for breeding and lacks suitable moist upland habitat containing mammal burrows. Additionally, there are no CNDDB documented occurrence within a 10-mile radius of the BSA. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA. Section 7 Determination: No effect. Residencies
California tiger Salamander	Ambystoma Californiense	Fed: CA: CDFW:	т т 	Inhabits annual grasslands and the grassy understory of Valley-Foothill Hardwood communities. Requires underground refuges, especially ground squirrel burrows and vernal pools or other seasonal water sources for breeding	A	Not expected to occur: The Project area lacks valley grassland communities, vernal pools or other seasonal pools required for breeding. There are two CNDDB documented occurrences within a 10-mile radius of the BSA. The closest CNDDB occurrence is located approximately 4.5 miles southwest of the Project area along Highway 120 and was recorded in 1996. No individuals were detected

Common Name	Species Name	Status		Status		Status		General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
						during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.				
						Section 7 Determination: No effect.				
Western spadefoot	Spea hammondii	Fed: State: CDFW:	 SSC	Inhabits open areas with sandy or gravelly soils within mixed woodlands, grasslands, coastal sage scrub, chaparral, sandy washes, lowlands, river floodplains, alluvial fans, playas, alkali flats, foothills, and mountains. Burrows underground from most of the year and is active above ground during rainfall. Requires vernal, shallow, temporary pools formed by heavy winter rains for reproduction. These pools must be free of bullfrogs, fish, and crayfish. Breeds from late winter to March.	A	Not expected to occur: The BSA lacks suitable woodland, grassland, chaparral and river floodplain communities preferred by the species. The BSA is bordered by highly disturbed urban and developed areas. There are no documented CNDDB occurrences within a 10-mile radius of the BSA. Due to the lack of suitable habitat and the lack of local, recent CNDDB occurrences, the species is not expected to occur within the BSA.				
Avian Species		·	T							
Burrowing Owl	Athene cunicularia	Fed: State: CDFW:	 SSC	Species inhabits arid, open areas with sparse vegetation cover such as deserts, abandoned agricultural areas, grasslands, and disturbed open habitats. Requires friable soils for burrow construction (Below 5,300 feet).	A	Low-moderate potential of occurring: The Project BSA lacks friable soils and does not contain evidence of small mammal burrows. No individuals were detected during biological surveys. However, the BSA is adjacent to potentially suitable grassland habitat and agriculture lands. Additionally, there are several CNDDB documented occurrences within a 10-mile radius of the BSA. The closest CNDDB occurrence to the BSA is located approximately 0.3 miles to the southeast and was documented in 2016 near abandoned runway and railroad tracks. Burrowing owls have been detected at this adjacent site since 1981 and have been monitored yearly at this particular site since 1997. This site also contains artificial burrows installed in 1999 to mitigate habitat loss from the				

Common Name	Species Name	Stat	us	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
						construction of a large building (20 acres). Due to the fact there is no suitable habitat present within the BSA but habitat is found adjacent to the BSA, and given the number local documented occurrences and because of the documented historical importance of the adjacent site; the species has been determined to have a low-moderate potential of occurring within the BSA.
California black rail	Laterallus jamaicensis coturniculus	State:	 T/FP 	A rare, yearlong California resident of brackish and freshwater emergent wetlands in delta and coastal locations, including the San Francisco Bay area, Sacramento-San Joaquin Delta, Morro Bay, the Salton Sea, and lower Colorado River. The species is extirpated from San Diego County and the majority of coastal southern California. Occurs in tidal emergent wetlands dominated by pickleweed, in brackish marshes dominated by bulrushes with pickleweed, and in freshwater wetlands dominated by bulrushes, cattails, and saltgrass. Species prefers high wetland areas, away from areas experiencing fluctuating water levels. Requires vegetation providing adequate overhead cover for nesting. Eggs are laid from March through June.	A	Not expected to occur: The Project lacks brackish and freshwater emergent wetland habitat required by the species. Furthermore, there are no documented CNDDB occurrences within a 10-mile radius of the BSA. Due to the lack of suitable habitat requirements present and the lack of local and recent documented occurrences, the species is not expected to occur within the Project BSA.
Least Bell's vireo	Vireo bellii pusillus	State:	E E 	Summer resident of southern California inhabiting low riparian habitats in the vicinity of water and dry river bottoms. Prefers willows, baccharis, mesquite and other low, dense vegetation as nesting sites (below 2000 feet).	A	Not expected to occur: The Project BSA lacks a water resource, low riparian habitats, dry river bottom habitat or willows, baccharis, mesquite and other low, dense vegetation required for breeding. Additionally, there is only one documented CNDDB occurrence within a 10-mile radius of the Project area. The occurrence was recorded in 1878, approximately 6 miles north of the BSA near Stockton. Due to the lack of suitable habitat requirements present, the lack of

Common Name	Species Name	Status		General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
						local and recent documented occurrences, and because the species was not detected during surveys; the species is not expected to occur within the Project BSA. Section 7 Determination: No effect.
Loggerhead shrike	Lanius Iudovicianus	Fed: State: CDFW:	 SSC	The species is associated with open canopied valley foothill hardwood, valley foothill hardwood-conifer, valley foothill riparian, pinyon-juniper, juniper, desert riparian, and Joshua tree habitats. Inhabits open habitats with scattered shrubs, trees, posts, fences, utility lines, or other perches. Rarely found in urbanized areas, but will inhabit open cropland. Nests are built on stable branches in densly- foilaged shrubs or trees. Breeds from March through May.	A	Not expected to occur: The Project BSA lacks a water resource and associated riparian habitat required for the species. Additionally, there is only one documented CNDDB occurrences within a 10-mile radius of the Project area. The occurrence was recorded in 1878, approximately 6 miles north of the BSA near the corner of Nestle Way and Christopher Way. Due to the lack of suitable habitat requirements present, the lack of local and recent documented occurrences, and because the species was not detected during surveys; the species is not expected to occur within the Project BSA.
Song sparrow ("Modesto" population)	Melospiza melodia	Fed: State: CDFW:	 SSC	An endemic bird found exclusively in the north-central portion of the Central Valley, with highest densities in the Butte Sink and Sacramento- San Joaquin River Delta. The species is usually found in open brushy habitats, along the borders of ponds or streams, abandoned pastures, desert washes, thickets, or woodland edges. In addition, there is a strong affinity for emergent freshwater marshes dominated by tules and cattails, riparian willow thickets, and valley oak forests with a blackberry understory. Nests found in base of shrubs or clumps of grass, requiring low, dense vegetation for cover, usually near water. Breeds from March through August.	A	Not expected to occur: The Project BSA lacks a water resource, brushy habitats, abandoned pastures, desert washes, thickets, woodland edges valley or oak forests with a blackberry understory required by the species. There are two documented CNDDB occurrences within a 10-mile radius of the Project area. The closest occurrence was recorded in 1911, approximately 1.4 miles south of the BSA along the San Joaquin River. Due to the lack of suitable habitat requirements present, the lack of local and recent documented occurrences, and because the species was not detected during surveys; the species is not expected to occur within the Project BSA.

Common Name	Species Name	Sta	tus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
Swainson's hawk	Buteo swainsoni	Fed: CA: CDFW:	 T 	Inhabits grasslands with scattered trees, juniper-sage flats, riparian areas, savannahs, and agricultural or ranch lands with groves or lines of trees. Requires adjacent suitable foraging areas such as grasslands, alfalfa or grain fields that support a stable rodent prey base. Breeds March to late August.	HP	Low-moderate potential of occuring: The Project BSA contains scattered trees and has suitable grassland and agricultural habitat adjacent. Additionally, there are several documented CNDDB occurrences within a 10-mile radius of the Project BSA, documented from 1988 to 2016. The closest documented occurrence is located approximately 0.7 miles to the south of the Project area near the Lathrop underpass and was recorded in 2011. The most recent CNDDB occurrence within a 10-mile radius of the BSA was recorded in 2016 and was documented between along the Grant Line Canal approximately 9 miles to the southeast. No individuals were detected during biological surveys. Due to the fact there is suitable foraging and breeding habitat adjacent to the BSA and the number of local and recent documented occurrences, the species has been determined to have a low-moderate potential to occur within the Project BSA.
Tricolored blackbird	Agelaius tricolor	Fed: CA: CDFW:	 SSC	Inhabits freshwater marsh, swamp and wetland communities, but may utilize agricultural or upland habitats that can support large colonies, often in the Central Valley area. Requires dense nesting habitat that is protected from predators, is within 3- 5 miles from a suitable foraging area containing insect prey and is within 0.3 miles of open water. Suitable foraging includes wetland, pastureland, rangeland, at dairy farms, and some irrigated croplands (silage, alfalfa, etc.). Nests mid- march - early August.	A	Not expected to occur: The Project BSA is adjacent to suitable foraging habitat for the species but lacks freshwater marsh, swamp and wetland communities, as well as, dense vegetation required for breeding. There are two documented CNDDB occurrences within a 10-mile radius of the Project BSA. The closest CNDDB documented occurrences within a 10- mile radius was recorded in 1974 approximately 3 miles to the south of the BSA near Airport Way. No individuals were detected during biological surveys. Due to the fact there is no suitable breeding habitat present and because no individuals were detected during biological surveys the species is not

Common Name	Species Name	Sta	tus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
						expected to occur within the Project BSA.
White-tailed kite	Elanus leucurus	Fed: CA: CDFW:	 FP	Inhabits rolling foothills and valley margins with scattered oaks and river bottomlands or marshes next to deciduous woodland. Prefers open grasslands, meadows or marshes for foraging close to isolated, dense- topped trees for nesting and perching. In southern California, will roost in saltgrass and Bermuda grass. Often found near agricultural lands. Nests are placed near the tops of dense oak, willow, or other tree stands. Breeds February through October.	A	Not expected to occur: The Project BSA is adjacent to suitable foraging habitat for the species but lacks scattered oaks and river bottomlands or marshes next to deciduous woodland. There is only one documented CNDDB occurrence within a 10-mile radius of the Project BSA. The occurrence was recorded in 2002 approximately 5 miles to the north of the BSA near Stockton. No individuals were detected during biological surveys. Due to the lack of suitable breeding habitat and because no individuals were detected during biological surveys the species is not expected to occur within the Project BSA.
Yellow-headed blackbird	Xanthocephalus xanthocephalus	Fed: CA: CDFW:	 SSC	The species occurs primarily as a migrant and summer resident from April to early October. The species almost exclusively nests in marshes with tall emergent vegetation such as tules (Scirpus sp.) or cattails (Typha sp.), in open areas and edges over water at depths typically ranging from 1-4 feet deep. Frequently breeds within marshes edges of lakes, reservoirs, or larger ponds. Nesting colonies occur where large insects, such as Odonata, are present and emerging. Breeds from April-July.	A	Not expected to occur: The Project BSA lacks marshes with tall emergent vegetation required by the species. There is only one documented CNDDB occurrences within a 10-mile radius of the Project BSA. The occurrence was recorded in 1894, located approximately 1.7 miles to the south of the BSA near North Lapthrop Road. No individuals were detected during biological surveys. Due to the lack of suitable breeding habitat and because no individuals were detected during biological surveys, the species is not expected to occur within the Project BSA.
Fish Species						
Delta smelt	Hypomesus transpacificus	Fed: CA: CDFW:	T E 	Occurs within the Sacramento-San Joaquin Delta and seasonally within the Suisun Bay, Carquinez Strait and San Pablo Bay. Most often occurs in partially saline waters.	A	Not expected to occur: The Project area is not adjacent to the Sacramento- San Joaquin Delta, the Suisun Bay, Carquinez Strait or San Pablo Bay and no saline waters are present within the BSA. There is only one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence was recorded in 2004, approximately 8.5

Common Name	Species Name	Status	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
					miles to the north, near the mouth of the San Joaquin River. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Longfin smelt	Spirinchus thaleichthys	Fed: T CA: CDFW:	Within California, occurs slightly upstream from Rio Vista (on the Sacramento River in the Delta) including the Cache Slough region and Medford Island (on the San Joaquin River in the Delta) through Suisun Bay and Suisun Marsh, the San Pablo Bay, the main San Francisco Bay, South San Francisco Bay,the Gulf of the Farallones, Humboldt Bay, and the Eel river estuary & local coastal areas. Resides in California and are primarily an anadromous estuarine species that can tolerate salinities ranging from freshwater to nearly pure seawater. Prefers temperatures in the range of 16-18°C and salinities ranging from 15-30 ppt. Their spatial distribution within a bay or estuary is seasonally variable. Longfin smelt may also make daily migrations; remaining deep during the day and rising to the surface at night.	А	Section 7 Determination: No effect. Not expected to occur: The Project BSA lacks any type of water resource and is not adjacent to any estuary or coastal areas. There are two CNDDB documented occurrences within a 10- mile radius of the BSA. The closest occurrence was recorded in 2012, approximately 2 miles south of the BSA, within the San Joaquin River. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA. Section 7 Determination: No effect.
Steelhead - Central Valley DPS	Oncorhynchus mykiss irideus	Fed: T CA: CDFW:	South/central steeelhead utilize rivers and creeks from Pajaro River south to Santa Maria River. Spawning occurs in coastal watersheds while rearing occurs in freshwater or estuary habitats prior to migrating to the ocean in the winter and spring. Preferred spawning sites contain gravel substrate with sufficient water	A	Not expected to occur: The Project area does not contain aquatic habitat and is not adjacent to any rivers, creeks or near coastal watersheds. There are three CNDDB documented occurrences within a 10-mile radius of the BSA. The documented occurrences are within the lower San Joaquin River, which is approximately 3.5 miles west (2013), the

Common Name	Species Name	Status	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
			flow and riverine cover. Rearing habitat contains sufficient feeding with associated riparian forest containing willow and cottonwoods. Migration upstream for reproduction occurs from October-May with spawning occurring January - April.		lower Calaveras River, which is approximately 6.7 miles to the north (2010) and within the Sacramento-San Joaquin Delta approximately 2 miles west of the BSA (2012). No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA. Section 7 Determination: <i>No effect.</i>
sDPC Green Sturgeon	Acipenser medirostris	Fed: T CA: CDFW:	Most marine of the sturgeon species. Predominately spawns in the upper Sacramento River, with some recorded in the Rogue River, Klamath and Trinity Rivers (Klamath River basin). In the Sacramento River, green sturgeon spawn above Hamilton City up to Keswick Dam. Known to occupy other river bodies including the lower Feather River; spawning not recorded; no green sturgeon has ever been documented in the San Joaquin River or its tributaries. Large cobbles preferred for spawning, but may utilize a range of substrates from bedrock to sand. Spawning occurs March-July.	A	Not expected to occur: The Project area does not contain aquatic habitat and is not adjacent to any rivers, creeks or near coastal watersheds. Additionally, there are no CNDDB documented occurrences within a 10-mile radius of the BSA. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA. Section 7 Determination: No effect.
Invertebrate Specie	es				
Valley elderberry longhorn beetle	Desmocerus californicus dimorphus	Fed: T CA: CDFW:	Species requires elderberry shrubs as host plants. Typically occurs in moist valley oak woodlands associated with riparian corridors in the lower Sacramento River and upper San Joaquin River drainages. (Sea level-3,000 feet).	A	Not expected to occur: The Project area does not contain elderberry shrubs or moist valley oak woodlands and lacks riparian corridors. The BSA is not adjacent to the lower Sacramento River or near the upper San Joaquin River drainages. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The documented occurrence is located approximately 5 miles to the west, along wing levee Road and was recorded in 1984. No elderberry

Common Name	Species Name	Stat	tus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
						shrubs or individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA. Section 7 Determination: <i>No effect.</i>
Vernal pool fairy shrimp	Branchinecta lynchi	Fed: CA: CDFW:	T 	In California, species inhabits portions of Tehama county, south through the Central Valley, and scattered locations in Riverside County and the Coast Ranges. Species is associated with smaller and shallower cool-water vernal pools approximately 6 inches deep and short periods of inundation. In the southernmost extremes of the range, the species occurs in large, deep cool-water pools. Inhabited pools have low to moderate levels of alkalinity and total dissolved solids. The shrimp are temperature sensitive, requiring pools below 50 F to hatch and dying within pools reaching 75 F. Young emerge during cold-weather winter storms.	A	Not expected to occur: The Project area does not contain vernal pools. Additionally, there are no CNDDB documented occurrences within a 10- mile radius of the BSA. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA. Section 7 Determination: No effect.
Vernal pool tadpole shrimp Mammal Species	Lepidurus packardi	Fed: CA: CDFW:	E 	Inhabits vernal pools and swales containing clear to highly turbid waters such as pools located in grass bottomed swales of unplowed grasslands, old alluvial soils underlain by hardpan, and mud-bottomed pools with highly turbid water.	A	Not expected to occur: The Project area does not contain vernal pools or swales. Additionally, there are no CNDDB documented occurrences within a 10-mile radius of the BSA. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA. Section 7 Determination: No effect.

Common Name	Species Name	Sta	tus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
American Badger	Taxidea taxus	Fed: CA: CDFW:	 SSC	Prefers treeless, dry, open stages of most shrub and herbaceous habitats with friable soils and a supply of rodent prey. Species also inhabits forest glades, meadows, marshes, brushy areas, hot deserts, and mountain meadows. Species maintains burrows within home ranges estimated between 338-1,700 acres, dependent on seasonal activity. Burrows are frequently re- used, but new burrows may be created nightly. Young are born in March and April within burrows dug in relatively dry, often sandy, soil, usually in areas with sparse overstory cover. Species is somewhat tolerant of human activity, but is sensitive to automobile mortality, trapping, and persistent poisons (up to 12,000 feet).	A	Not expected to occur: The Project area lacks herbaceous habitats and natural habitat communities required by the species. Furthermore, there are no documented CNDDB occurrences within a 10-mile radius of the BSA. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Riparian brush rabbit	Sylvilagus bachmani riparius	Fed: CA: CDFW:	E E 	Lives in riparian oak forests with a dense understory of wild rose and native vines. Historically found along the San Joaquin River and once confined to the Caswell Memorial State Park, the species has been reintroduced to parts of it's historical range including the San Joaquin River National Wildlife Refuge and portions of the Delta. Grazes in grasslands, meadows, and riparian areas close to the brushy areas. Nest in shallow cavities in the ground. Breeding season is from December to May. Occurs from elevation near sea level to 3000ft.	HP	Not expected to occur: The Project BSA lacks oak forests with a dense understory of wild rose and native vines. Additionally, the Project BSA is not known to historically provide habitat for the species (the San Joaquin River, the Caswell Memorial State Park, San Joaquin River National Wildlife Refuge or the Delta). There are several documented CNDDB occurrences within a 10-mile radius of the Project BSA, documented from 2002 to 2010. The closest documented occurrence is located approximately 2 miles to the southeast of the Project area along the San Joaquin River and was recorded in 2004. The most recent CNDDB occurrence within a 10-mile radius of the BSA was recorded in 2010 and was documented along the San Joaquin River approximately 4 miles to the southwest. No individuals were detected during biological surveys. Due to the lack of suitable riparian habitat within the

Common Name	Species Name	Sta	tus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
						Project BSA and given that nearby riparian habitat is separated from the BSA due to urban development, the species is not expected to occur within the Project BSA.
						Section 7 Determination: No effect.
Reptile Species				Inhohita marah awamp watland		Not expected to ecoury The PSA door
Giant garter snake	Thamnophis gigas	Fed: CA: CDFW:	T T 	Inhabits marsh, swamp, wetland (including agricultural wetlands), sloughs, ponds, rice fields, low gradient streams and irrigation/drainage canals adjacent to uplands. Ideal habitat contains both shallow and deep water with variations in topography. Species requires adequate water during the active season (April-November), emergent, herbaceous wetland vegetation, such as cattails and bulrushes, for escape cover and foraging habitat and mammal burrows estivation. Requires grassy banks and openings in waterside vegetation for basking and higher elevation uplands for cover and refuge from flood waters during winter dormant season.	A	Not expected to occur: The BSA does lacks drainages and suitable aquatic habitat for the species. Additionally, there are no wetland marsh, swamp, wetland, sloughs, ponds, rice fields, low gradient streams or suitable upland habitat within the BSA. There are two CNDDB documented occurrences within a 10-mile radius of the BSA. The closest occurrence was recorded in 1880, approximately 6 miles to the north, near canals in West Stockton. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Western pond turtle	Emys marmorata	Fed: CA: CDFW:	 SSC	A fully aquatic turtle of ponds, lakes, rivers, streams, creeks, marshes, and irrigation ditches with aquatic vegetation. Suitable habitat includes woodland, forests, and grasslands. Requires logs, rocks, cattail mats, and exposed banks for basking. Suitable upland habitat (sandy banks or grassy open field) is required for reproduction, which begins in April and ends with egg laying as late as August (sea level to 4,700 feet).	A	Not expected to occur: The Project area lacks aquatic resources required by the species. Furthermore, there are no documented CNDDB occurrences within a 10-mile radius of the Project area. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Plant Species	Astrogalus topor vor	Ead		An appual borb inhabiting low ground		Not expected to excure The Preject
Alkali milk-vetch	Astragalus tener var. tener	Fed: CA:		An annual herb inhabiting low ground and alkaline soils of playas, alkaline	А	Not expected to occur: The Project area lacks alkaline soils or adobe clay.

Common Name	Species Name	Sta	tus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
		CNPS:	1B.2	flats, vernally moist meadows, vernal pools, and valley and foothill grassland of adobe clay. Flowers March–June (0-200 feet).		There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 7.5 miles to the north, documented near Smith's Canal in Stockton and was recorded in 1927. CNDDB notes state this individual population had been extirpated from the site. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Big tarplant	Blepharizonia plumosa	Fed: CA: CNPS:	 1B.1	An annual herb inhabiting dry hills and plains of valley and foothill grassland communities, often within clay soils. Flowers July-October (0- 1,660 feet).	A	Not expected to occur: The Project area lacks clay soils. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 7.5 miles to the north, documented near center of Stockton and was recorded in 1847. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local and recent documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Bristly sedge	Carex comosa	Fed: CA: CNPS:	 2B.1	A perennial grasslike herb native to California, inhabiting lake-margins and edges in freshwater wetlands, coastal prairie, valley grassland, foothill grassland, and wetland- riparian communities. Blooms May- September (0-2,050 feet).	A	Not expected to occur: The Project area does not contain lake-margins, edges in freshwater wetlands, coastal prairie, valley grassland, foothill grassland, and wetland-riparian communities. Additionally, there are no CNDDB documented occurrences within a 10-mile radius of the BSA. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected

Common Name	Species Name	Sta	tus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
						during surveys; the species is not expected to occur within the BSA.
Caper-fruited tropidocarpum	Tropidocarpum capparideum	Fed: CA: CNPS:	 1B.1	An annual herb native to California, inhabiting valley grassland communities. Blooms from March to April (16-1,223 feet).	A	Not expected to occur: The Project area lacks grassland habitat in which the species is known to occur. Furthermore, there are no CNDDB documented occurrences within a 10-mile radius of the BSA. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Delta button-celery	Eryngium racemosum	Fed: CA: CNPS:	 E 1B.1	An annual or perennial herb inhabiting seasonally flooded clay depressions in floodplains and riparian scrub within vernally mesic clay depressions. Flowers June- August (10-100 feet)	A	Not expected to occur: The Project area lacks clay depressions or riparian scrub habitat. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 3.5 miles to the south along in the vicinity of I-5 crossing of San Joaquin River and was recorded in 1984. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local or recent documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Delta mudwort	Limosella australis	Fed: CA: CNPS:	 2B.2	A perennial stoloniferous herb inhabiting low elevation muddy banks of riparian scrub, freshwater or brackish marshes and swamps, and intertidal flats. Flowers May-August (0-30 feet).	A	Not expected to occur: The Project area lacks muddy banks of riparian scrub and freshwater brackish marshes and swamps in which the species inhabits. Furthermore, there are no CNDDB documented occurrences within a 10- mile radius of the BSA. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Delta tule pea	Lathyrus jepsonii var. jepsonii	Fed: CA:		A perennial herb inhabiting freshwater and brackish marshes of	А	Not expected to occur: The Project area lacks freshwater and brackish

Common Name	Species Name	Sta	itus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
		CNPS:	1B.2	coastal and estuarine communities. Flowers May-September (0-20 feet).		marshes habitat. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 6.8 miles to the northwest on Rough Island and was recorded in 1903. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local or recent documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Heartscale	Atriplex cordulata var. cordulata	Fed: CA: CNPS:	 1B.2	An annual herb inhabiting saline or alkaline soils of chenopod scrub, meadows and seeps, and sandy valley and foothill grassland communities. Flowers June –July (0- 1,850 feet).	A	Not expected to occur: The Project area lacks saline or alkaline soils. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 6 miles to the north, near Stockton, and was recorded in 1896. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local or recent documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Large-flowered fiddleneck	Amsinckia grandiflora	Fed: CA: CNPS:	E E 1B.1	An annual herb inhabiting grassy slopes of cismontane woodland and valley and foothill grassland communities. Known fewer than 5 natural occurrences. Flowers March- May (880-1,800 feet).	A	Not expected to occur: The Project area does not contain grassy slopes of cismontane woodland and valley and foothill grassland communities. Additionally, there are no CNDDB documented occurrences within a 10- mile radius of the BSA. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Mason's lilaeopsis	Lilaeopsis masonii	Fed: CA:		A perennial rhizomatous herb found exclusively in the Sacramento-San	А	Not expected to occur: The Project area lacks freshwater and brackish

Common Name	Species Name	Sta	itus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
		CNPS:	1B.1	Joaquin River Delta and San Francisco Bay. Found in low elevation freshwater and brackish mashes adjacent to surface water. Flowers June-August (0-100 feet).		marshes required for survival of the species. Furthermore, there are no CNDDB documented occurrences within a 10-mile radius of the BSA. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Palmate-bracted bird's-beak	Chloropyron palmatum	Fed: CA: CNPS:	 1B.1	An annual hemiparasitic herb inhabiting alkaline flats, chenopod shrub, and valley and foothill grasslands. Flowers May-August (0- 509 feet).	A	Not expected to occur: The Project area does not contain alkaline flats, chenopod shrub, and valley and foothill grasslands habitat. Additionally, there are no CNDDB documented occurrences within a 10-mile radius of the BSA. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Recurved larkspur	Chloropyron palmatum	Fed: CA: CNPS:	E E 1B.1	A perennial herb inhabiting poorly drained, fine, alkaline soils in chenopod scrub, Atriplex scrub, cismontane woodland, and valley and foothill grassland communities. Flowers March-June (10-2,600 feet).	A	Not expected to occur: The Project area lacks alkaline soils in chenopod scrub, Atriplex scrub, cismontane woodland, and valley and foothill grassland communities. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 6 miles to the northeast, along Mariposa Avenue, and was recorded in 1937. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local or recent documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Saline clover	Trifolium hydrophilum	Fed: CA: CNPS:	 1B.2	An annual herb inhabiting marshes, swamps within valley and foothill	A	Not expected to occur: The Project area lacks marshes, swamps within valley and foothill grassland mesic or

Common Name	Species Name	Status	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
			grassland mesic or vernal pools. Blooms April – June (0-1,000 feet).		vernal pools communities. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 6 miles to the north, near Stockton, and was recorded in 1928. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local or recent documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
San Joaquin spearscale	Extriplex joaquinana	Fed: CA: CNPS: 1B.2	An annual herb inhabiting chenopod scrub, meadows and seeps, playas, valley and foothill grasslands. Blooms April – October (1- 2,800 feet).	A	Not expected to occur: The Project area lacks chenopod scrub, meadows and seeps, playas, valley and foothill grasslands communities. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 6 miles to the north, near Stockton, and was recorded in 1928. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local or recent documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Slough thistle	Cirsium crassicaule	Fed: CA: CNPS: 1B.1	An annual or perennial herb inhabiting freshwater marshes, chenopod scrub, swamps, sloughs, and riparian scrub. Flowers May- August (10-330 feet).	A	Not expected to occur: The Project area lacks freshwater marshes, chenopod scrub, swamps, sloughs and riparian scrub in which the species occurs. Furthermore, there are no CNDDB documented occurrences within a 10-mile radius of the BSA. Due to the fact there is no suitable habitat present, the lack of local documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Stanford's arrowhead	Sagittaria sanfordii	Fed: CA:	A perennial rhizomatous herb inhabiting freshwater marshes,	А	Not expected to occur: The Project area lacks freshwater marshes,

Common Name	Species Name	Sta	tus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
		CNPS:	1B.2	swamps, ponds, and ditches. Flowers May-October (0-2,130 feet).		swamps, ponds, and defined ditches. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 6 miles to the north, near Stockton, and was recorded in 1901. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the lack of local or recent documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Suisun Marsh aster	Symphyotrichum lentum	Fed: CA: CNPS:	 1B.2	A perennial rhizomatous herb inhabiting wetlands, freshwater marsh, and brackish-marsh communities. Flowers May- November (0-10 feet).	A	Not expected to occur: The Project area lacks wetlands, freshwater marsh, and brackish-marsh communities and is not located with the elevation range of the species. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 9 miles to the north, along the Calaveras River, and was recorded in 1926. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the Project area being outside the species known elevation range, the lack of local or recent documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Watershield	Brasenia schreberi	Fed: CA: CNPS:	 2B.3	A perennial rhizomatous aquatic herb inhabiting ponds, slow streams, and freshwater marsh and swamp communities. Flowers June- September (100-7,200 feet).	A	Not expected to occur: The Project area lacks ponds, slow streams, and freshwater marsh and swamp communities and is not located with the elevation range of the species. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 6 miles to the north, in Stockton. There is not record date for this occurrence. No individuals were detected during biological surveys. Due to the fact there

Common Name	Species Name	Sta	tus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
						is no suitable habitat present, the Project area being outside the species known elevation range, the lack of local or recent documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Woolly rose- mallow	Hibiscus lasiocarpos var. occidentalis	Fed: CA: CNPS:	 1B.2	A perennial rhizomatous herb inhabiting freshwater wetlands, wet banks, and marsh communities. Often found in-between riprap on levees. Flowers June-September (0- 400 feet).	A	Not expected to occur: The Project area freshwater wetlands, wet banks, and marsh communities. There are 4 CNDDB documented occurrence within a 10-mile radius of the BSA. The closest occurrence is located approximately 8 miles to the northwest, on Channel Island, and was recorded in 1986. The most recent documented occurrence was recorded in 2010 and was documented near the Tracy Boulevard Bridge, approximately 9 miles to the northeast. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the Project area being outside the species known elevation range, the lack of local or recent documented occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Wright's trichocoronis	Trichocoronis wrightii var. wrightii	Fed: CA: CNPS:	 2B.1	An annual herb found most often in marshes, swamps, meadows, vernal pools, and riparian habitat. Flowers May-September (30-1,500 feet).	A	Not expected to occur: The Project area lacks marshes, swamps, meadows, vernal pools, and riparian habitat and is just outside with the elevation range of the species. There is one CNDDB documented occurrence within a 10-mile radius of the BSA. The occurrence is located approximately 4 miles to the south, where I-5 crosses the San Joaquin River. There occurrence was recorded in 1914. No individuals were detected during biological surveys. Due to the fact there is no suitable habitat present, the Project area being outside the species known elevation range, the lack of local or recent documented

Common Name	Species Name	Sta	tus	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
						occurrences and because the species was not detected during surveys; the species is not expected to occur within the BSA.
Critical Habitat		1			I	
Steelhead - Central Valley DPS	Oncorhynchus mykiss irideus	Fed: CA: CDFW:	T 	NMFS designated Critical Habitat encompasses accessible reaches include approximately 8,935 net miles of riverine habitat and 470 miles of estuarine habitat (primarily in San Francisco-San Pablo Suisun Bays) in California.	A	Absent: A species list of threatened, endangered, proposed and candidate species that may be present in the Project action area was obtained from the NMFS in September 2019. Per NMFS, Critical Habitat for this species was listed be within the same USGS quad as the Project BSA. By using USFWS Environmental Conservation Online System, provided confirmation that the Project area is within designated Critical Habitat was made. Federally designated Critical Habitat for the species is not within the Project BSA.
						Section 7 Determination: No effect
sDSP Green Sturgeon	Acipenser medirostris	Fed: CA: CDFW:	T 	NMFS designated Critical Habitat as the mainstream Sacramento River downstream of Keswick Dam (including the Yolo and Sutter bypasses), the Feather River below Oroville Dam, the Yuba River below Dagueere Point Dam, and the Sacramento-San Joaquin Delta. In marine waters, designated critical habitat is: areas 60 fathom (360 feet) depth isobath from Monterey Bay to the U.SCanada border. In coastal bays and estuaries, designated critical habitat is: San Francisco Bay Estuary and Humboldt Bay in California. Coos, Winchester, Yaquina, and Nehalem bays in Oregon, Willapa and Grays Harbor in Washington, and the Lower Columbia River Estuary from the mouth to rkm 74.	A	Absent: A species list of threatened, endangered, proposed and candidate species that may be present in the Project action area was obtained from the NMFS in September 2019. Per NMFS, Critical Habitat for this species was listed be within the same USGS quad as the Project BSA. By using USFWS Environmental Conservation Online System, provided confirmation that the Project area is within designated Critical Habitat was made. Federally designated Critical Habitat for the species is not within the Project BSA. Section 7 Determination: No effect

Common Name	Species Name	Status	General Habitat Description	Habitat Present	Potential for Occurrence and Rationale
Chinook salmon	Oncorhynchus tshawytscha	Fed: T CA: T CDFW:	Salmon EFH includes all those streams, lakes, ponds, wetlands, and other water bodies currently or historically accessible to salmon in Washington, Oregon, Idaho, and California. Salmon EFH excludes areas upstream of longstanding naturally impassible barriers (i.e. natural waterfalls in existence for several hundred years), but includes aquatic areas above all artificial barriers except specifically named impassible dams.	A	Absent: A species list of threatened, endangered, proposed and candidate species that may be present in the Project action area was obtained from the National Marine Fisheries Service in March of 2020. Essential fish habitat for this species was determined to be within the same USGS quad as the Project BSA. Furthermore, NOAA's Essential Fish Mapper determined that the Project area is within EFH for the species.; however, because the Project area lacks any resources, EFH has been determined to not be directly within the Project area and will not be impacted. Section 7 Determination: No effect

Federal Designations (Fed): (FESA, USFWS) E: Federally listed, endangered T: Federally listed, threatened DL: Federally listed, delisted	State Designations (CA): (CESA, CDFW) E: State-listed, endangered T: State-listed, threatened				
Other Designations CDFW_SSC: CDFW Species of Special Concern CDFW_FP: CDFW Fully Protected CDFW_SA: CDFW Special Animal					
 <u>California Native Plant Society (CNPS) Designations:</u> *Note: according to CNPS (Skinner and Pavlik 1994), plants on Lists 1B and 2 meet definitions for listing as threatened or endangered under Section 1901, Chapter 10 of the California Fish and Game Code. This interpretation is inconsistent with other definitions. 1A: Plants presumed extinct in California. 1B: Plants rare and endangered in California and throughout their range. 2: Plants rare, threatened, or endangered in California but more common elsewhere in their range. 3: Plants about which need more information; a review list. 					
Plants 1B, 2, and 4 extension meanings: 1 Seriously endangered in California (over 80% of occurrences threatened / high degree and immediacy of threat) 2 Fairly endangered in California (20-80% occurrences threatened) 3 Not very endangered in California (<20% of occurrences threatened or no current threats known)					
Habitat Potential Absent [A] - No habitat present and no further work needed. Habitat Present [HP] - Habitat is, or may be present. The species may be present. Critical Habitat [CH] – Project is within designated Critical Habitat.					
Potential for Occurrence Criteria: Present: Species was observed on site during a site visit or focused survey.					

High: Habitat (including soils and elevation factors) for the species occurs on site and a known occurrence has been recorded within 5 miles of the site. Low-Moderate: Either low quality habitat (including soils and elevation factors) for the species occurs on site and a known occurrence exists within 5 miles of the site; or suitable habitat strongly associated with the species occurs on site, but no records were found within the database search.

Not expected to occur: Focused surveys were conducted and the species was not found, or species was found within the database search but habitat (including soils and elevation factors) do not exist on site, or the known geographic range of the species does not include the survey area.

Source: (CDFW 2019), (CNDDB 2019), (CNPS 2019), (Calflora 2019) (Jepson, 2nd Ed.), USFWS 2007, (Zeiner 1988-1990).



Representative Photograph 1: Representative of a portion of Harlan Road, facing north (taken March 2020).



Representative Photograph 2: Representative of the trees present within the Project area, facing southwest (taken March 2020).



Representative Photograph 3: Representative of the ruderal vegetation within the Project area, facing south (taken March 2020).




Representative Photograph 4: Representative of the developed areas within the Project area, facing west (taken March 2020).

National Flood Hazard Layer FIRMette



Legend



Attachment F: Mitigation Monitoring and Reporting Program

MM #	Mitigation Measure	Timing/ Implementation	Enforcement/ Monitoring	Verification and Comments (date and Signature)
Aestheti	cs			
VIS-1	Vegetation clearing would only occur within the delineated Project boundaries in an effort to minimize the impacts. Trees located in areas along the edge of the construction zone would be trimmed whenever possible and only those trees that lie within the active construction areas would be removed.	During construction	Contractor	
Air Qual	ity			
AQ-1	 A person shall not discharge into the atmosphere from any single source of emission whatsoever, any air contaminant, other than uncombined water vapor, for a period or periods aggregating more than three (3) minutes in anyone (1) hour which is: As dark or darker in shade as that designated as No. 1 on the Ringelmann Chart, as published by the United States Bureau of Mines. Of such opacity as to obscure an observer's view to a degree equal to or greater than the smoke described in Section 5.1 of this rule. 	During construction	Contractor	
AQ-2	A person shall not discharge from any source whatsoever such quantities of air contaminants or other materials which cause injury, detriment, nuisance or annoyance to any considerable number of persons or to the public or which endanger the comfort, repose, health or safety of any such person or the public or which cause or have a natural tendency to cause injury or damage to business or property.	During construction	Contractor	
AQ-3	Storage Piles and Bulk Materials have handling, storage, and transportation requirements that include applying water when	During construction	Contractor	

MM #	Mitigation Measure	Timing/ Implementation	Enforcement/ Monitoring	Verification and Comments (date and Signature)
	handling materials, wetting or covering stored materials, and installing wind barriers to limit VDE. Also, limiting vehicle speeds, loading haul trucks with a freeboard of six inches or greater along with applying water to the top of the load, and covering the cargo compartments are effective measures for reducing VDE and carryout from vehicles transporting bulk materials.			
Biologic	al Resources			
BIO-1	Prior to the start of construction activities, the Project limits must be marked with high visibility fencing or staking to ensure construction will not further encroach into adjacent properties. The Project biologist will periodically inspect the fencing to ensure sensitive locations outside the limits of construction remain undisturbed. Fencing or staking will be maintained until the completion of all construction activities.	Prior and during construction	Contractor and City	
BIO-2	All construction personnel shall be provided with environmental awareness training prior to being allowed to work on the job site. The training shall include an overview of special status species that have potential to occur within or adjacent to the Project area and Project specific protective measures that must be adhered to, including BMPs. The training will also include a description of the legal penalties for violating protective measures.	Prior and during construction	City	
BIO-3	If construction is initiated during the nesting bird season (February 15-August 31) a nesting bird survey shall be conducted by a qualified biologist within 14 days prior to construction initiation. Focused surveys must be performed by a qualified biologist for the purposes of determining the presence/absence of active nest sites	During construction	City	

MM #	Mitigation Measure	Timing/ Implementation	Enforcement/ Monitoring	Verification and Comments (date and Signature)
	 within the proposed impact area, including construction access routes and a 200-foot buffer (if feasible). A minimum 50 foot no-disturbance buffer will be established around any active nest of migratory birds and a minimum 300 foot no-disturbance buffer will be established around any nesting raptor species. The contractor must immediately stop work in the nesting area until the appropriate buffer is established and is prohibited from conducting work that could disturb the birds (as determined by the Project biologist and in coordination with wildlife agencies) in the buffer area until a qualified biologist determines the young have fledged. A reduced buffer can be established if determined appropriate by the Project biologist and approved by CDFW 			
BIO-4	Vegetation clearing will only occur within the delineated Project boundaries. Where possible, trees will be identified for trimming rather than full removal with the guidance of the Project biologist.	During construction	Contractor	
BIO-5	Exposed soils would be stabilized, through watering or other measures, to prevent the movement of dust at the Project site caused by wind and construction activities such as traffic and grading activities.	During to construction	Contractor	
BIO-6	All construction materials would be hauled off-site after completion of construction.	During construction	Contractor	
BIO-7	Prior to arrival at the Project site and prior to leaving the Project site, construction equipment that may contain invasive plants	Prior and during construction	Contractor	

MM #	Mitigation Measure	Timing/ Implementation	Enforcement/ Monitoring	Verification and Comments (date and Signature)
	and/or seeds must be cleaned to reduce the spreading of noxious weeds.			
BIO-8	The contractor must not apply rodenticide or herbicide within the Project area during construction.	During construction	Contractor	
BIO-9	The contractor must dispose of all food-related trash in closed containers and must remove it from the Project area each day during construction. Construction personnel must not feed or attract wildlife to the Project area.	During construction	Contractor	
BIO-10	Plastic monofilament netting shall not be used in straw wattles or other erosion control materials.	During construction	Contractor	
Cultural	Resources			
CR-1	If previously unidentified cultural materials are unearthed during construction, work shall be halted in that area until a qualified archaeologist can assess the significance of the find and develop a plan for documentation and removal of resources if necessary.	During construction	Contractor and City	

MM #	Mitigation Measure	Timing/ Implementation	Enforcement/ Monitoring	Verification and Comments (date and Signature)
	Additional archaeological survey will be needed if Project limits are extended beyond the present survey limits.			
CR-2	Section 5097.94 of the Public Resources Code and Section 7050.5 of the California Health and Safety Code protect Native American burials, skeletal remains and grave goods, regardless of age and provide method and means for the appropriate handling of such remains. If human remains are encountered, work should halt in that vicinity and the county coroner should be notified immediately. At the same time, an archaeologist should be contacted to evaluate the situation. If the human remains are of Native American origin, the coroner must notify the Native American Heritage Commission within twenty-four hours of such identification. CEQA details steps to be taken if human burials are of Native American origin.	During construction	Contractor and City	
Greenho	use Gas Emissions			
GHG-1	The project would incorporate the use of energy-efficient lighting, such as LED traffic signals. LED bulbs cost \$60 to \$70 each, but last five to six years, compared to the one-year average lifespan of the incandescent bulbs previously used. The LED bulbs themselves consume 10 percent of the electricity of traditional lights, which will also help reduce the Project's CO ₂ emissions.	During construction	Contractor and City	
Hazards	and Hazardous Materials			
HAZ-1	As is the case for any project that proposes excavation, the potential exists for unknown hazardous contamination to be revealed during Project construction. For any previously unknown hazardous waste/material encountered during construction, the appropriate procedures, in accordance with state law, shall be followed.	During construction	Contractor	

MM #	Mitigation Measure	Timing/ Implementation	Enforcement/ Monitoring	Verification and Comments (date and Signature)
HAZ-2	Phase II testing will be conducted prior to the onset of construction to determine if aerially deposited lead, or other heavy metals, are present within the Project area. The results of Phase II testing will determine if additional avoidance, minimization or mitigation measures are required.	Prior to construction	City	
Water Q	uality	I	L	
WQ-1	 To conform to water quality requirements, the SWPPP must include the following: Any necessary equipment washing must occur where the water cannot flow into drainage systems. The project specifications will require the contractor to operate under an approved spill prevention and clean-up plan; Construction work must be conducted according to site-specific construction plans that minimize the potential for sediment input to groundwater; Raw cement, concrete or concrete washings, asphalt, paint or other coating material, oil or other petroleum products, or any other substances that could be hazardous shall be prevented from contaminating the soil; Any concrete rubble, asphalt, or other debris from construction must be taken to an approved disposal site. 	During construction	Contractor	
WQ-2	Contract specifications will include the following BMPs, where applicable, to reduce erosion during construction:	During construction	Contractor	
	Implementation of the Project will require approval of a			

MM #	Mitigation Measure	Timing/ Implementation	Enforcement/ Monitoring	Verification and Comments (date and Signature)
	 site-specific SWPPP that would implement effective measures to protect water quality, which may include a hazardous spill prevention plan and additional erosion prevention techniques; Existing vegetation will be protected in place where feasible to provide an effective form of erosion and sediment control; Stabilizing materials will be applied to the soil surface to prevent the movement of dust from exposed soil surfaces on construction sites as a result of wind, traffic, and grading activities. 			
Noise				
NOI-1	Rubberized and/or open grade asphalt will be used on the southern portion of Harlan Road under all alternatives during Phase 1 and on the northern portion of Harlan Road, during Phase 2, if Alternative 2 is selected.	During construction	Contractor	
Populati	on and Housing	·		
POP-1	The Project shall comply with the Uniform Relocation Assistance Real Property Acquisition Policies Act of 1970, as amended in 1987. Relocation advisory assistance shall be provided to any	Prior and during construction	City	

MM #	Mitigation Measure	Timing/ Implementation	Enforcement/ Monitoring	Verification and Comments (date and Signature)
	person, business, farm, or nonprofit organization relocated as a result of acquisition of real property for public use for the Project.			

Attachment G: Distribution List

A Notice of Availability was distributed to all residences within a 500-foot radius of the Project area and to the following agencies and interested parties (unless a hardcopy is specified).

City of Lathrop Public Works Attn: Michael King Director of Public Works City of Lathrop 390 Towne Centre Drive Lathrop, CA 95330 (Hardcopy)

State Government

California State Clearinghouse P.O. Box 3044 Sacramento, CA 95812-3044 (Hardcopy)

Local Elected Officials and Local Agencies

San Joaquin County Public Works Department 1810 E Hazelton Avenue Stockton, CA 95205

San Joaquin Valley Air Pollution Control District 4800 Enterprise Way Modesto, CA 95356

Utilities

Ahtna Environmental Inc. Paul Marsden 1708 Anita Court Modesto, CA 95350

AT&T Sharon Dinnell and Robert Knecht 1116 M Street Modesto, CA 95354

City of Lathrop Michael King City of Lathrop 390 Towne Centre Drive Lathrop, CA 95330 Comcast- Stockton Kris Cook 6505 Tam O' Shanter Drive Stockton, CA 95210

Pacific Gas & Electric Distribution- Stockton David Loomis 1524 N. Carpenter Road Modesto, CA 95351

Other Interested Parties

Mark Ferguson Diamond Pet Foods 250 E. Roth Road Lathrop, CA 95330 209-662-0569 mferguson@diamondpet.com

Robert Tapley Aquos Pools 11137 Harlan Road French Camp, CA 95231 209-481-5515

Harold Tapley Aquos Pools 11137 Harlan Road French Camp, CA 95231 209-605-2015 harold@aquospools.com

Ryan Mathews Diamond Pet Foods 250 E. Roth Road Lathrop, CA 95330 209-983-4900 rmathews@diamondpet.com

Logan Coleman 11550 S. Harlan Road 925-437-3708 logantylermusician@gmail.com

Attention Interested Party at 134 Roth Road Lathrop, CA 95330 Cbsb20@yahoo.com Miguel Cerpus 11550 S. Harlan Road 209-513-1311

Hildo Villalobos 11550 S. Harlan Road 209-451-6865

Carlos Corpas 11550 S. Harlan Road 209-271-5605

Claudia Rivera 11550 S. Harlan Road

Irma Ruiz 11550 S. Harlan Road Brian Lynch

Brian Lynch Boral Roofing 957-233-3262 brianlynch@boral.com

Glenn Gebhardt City of Lathrop 390 Towne Centre Drive Lathrop, CA 95330

Rebecca Julien 10980 S. Harlan Road Lathrop, CA 95330 209-456-1647 Mbjulien72@gmail.com

Robert Julien 10980 S. Harlan Road Lathrop, CA 95330 209-993-6141

Rafael Lizardi 11550 S. Harlan Road Lathrop, CA 95330 408-849-1586


Juan Huaracha 11550 S. Harlan Road #11 Lathrop, CA 95330 209-430-0977 Hardeep Gill Fast Lane CV 116 Roth Road Lathrop, CA 95330 707-326-0369 hardeep@bggroopinc.com

Attachment H: Response to Public Comments



Comment	
1	Commenter: Matt Julien, Received December 31, 2020
	Amy Bakker
	Subject: FW: Comments RE: Harlan Road Realignment at Roth Road Project
	From: Matt Julien <u>bigshooter72@gmail.com</u> >
	Sent: Thursday, December 31, 2020 7:22 AM To: Michael King < <u>mking@ci.lathrop.ca.us</u> >
	Cc: mbjulien72@gmail.com Subject: Comments RE: Harlan Road Realignment at Roth Road Project
	Dear Mr. King:
	I received the Notice of Intent to Adopt Negative Declaration for the Harlan Road Realignment Project. The initial study prepared appears incomplete and should be revised and recirculated to address the issues raised in this message.
	My wife and I own the property located at 10980 S. Harlan Rd (APN: 19333031). The City has proposed condemning this property for purposes of the Harlan Road Realignment Project. The property has served as both our family's personal residence and the operational headquarters for my landscaping services business for over two decades. By way of history, this property previously sat in unincorporated San Joaquin County when these uses were established and only came into the City in about 2015.
	According to the initial study:
	Under Alternative 1 and 3, the Project would displace three residencies on two parcels south of Roth Road, in the southern portion of the Project area, as well as the one residency on one parcel north of Roth Road, in the northern portion of the Project area. Alternative 1 would have the greatest impact on the property north of Roth Road, whereas Alternative 3 would only impact a portion of the property; however, due to the location of the house, the residency would still be displaced. Under Alternative 2, the Project would displace three residencies on two parcels south of Roth Road, in the southern portion of the Project area, but avoid the residency north of Roth Road, in the northern portion of the Project area.
	The Project may require two construction phases due to available funding. If construction phases are required, Phase I would consist of all roadway improvements south of Roth Road as well as improvements along Roth Road. Phase II would include roadway improvements north of Roth Road. During Phase I, the stop sign at the existing Harlan/Roth Road would be maintained, but with the relocation of the south leg of Harlan Road to the new proposed signalized intersection.
	The Project would have less than significant impacts to displacement of housing through the incorporation of measure POP-1.
	1












D

The initial study also fails to address how or whether access to my property would be provided from either the private road or the realigned Harlan Road to the north. These are all potentially significant impacts that appear to be ignored in the City's study. Accordingly, the City's environmental review should be revised to address these aspects of the Project and the potentially significant impacts to adjacent property owners.

Please also note that the City has been planning this realignment for some time and declined our earlier offer to sell the property and provide us some certainty to our family's ability to move forward with relocating our home and business to an acceptable site. After the City's communication stating that it had no interest in negotiating purchasing the Property, and realizing that any proposed realignment of Harlan Road would likely displace us from our home at this location, we have begun the process of

3





Response:

Thank you for your comments. They have been included within the final environmental document.

Response to Comment 1A:

Visual impacts that would occur as a result of selecting Alternative 2 are evaluated in Section 2.1 of the environmental document. Minor tree trimming and vegetation clearing in select locations during construction of Alternative 2 would result in a temporary change in aesthetics, but those changes would be negligible and nearly unnoticeable from the realignment of Roth Road within an already highly urban area. Therefore, impacts that would occur as a result of Alternative 2 are considered less than significant under CEQA.

Noise impacts that would occur as a result of Alternative 2 are discussed in Section 2.13 of the environmental document. The Project would increase noise levels next to the residence by 3dBA, however through the use of rubberized asphalt noise levels would be decreased by at least 3 dBA.; therefore, reflecting the existing noise conditions within the Project vicinity. Therefore, impacts are expected to be less than significant with mitigation incorporated under CEQA.

Response to Comment 1B:

Figure 3 Features Map has been updated to reflect the proposed condition of the existing Harlan Road adjacent to the residence north Roth Road that would occur as a result of all three alternatives.

Final ownership of the roadway will be determined as part of the right of way negotiations during final design. Any reference to the roadway as being "private" has been removed from the Environmental Document as ownership will be determined during right of way negotiations.

The City does not intend for the roadway to be gated at this time.

Upon completion of the Project, the roadway will not provide access between Roth Road and the realigned Harlan Road in front of the property.

If the public road is converted to a private roadway, it will not require the formation of a property owner's association.

Responsibility for maintenance of the roadway will be determined during right of way negotiations.

Response to Comment 1C:

Should Alternative 2 be selected during final design, access to the property would be maintained at its existing location from the existing Harlan Road. Section 2.14, Table 16 of the Final IS/MND has been updated to reflect this information.



Response to Comment 1D:

Regarding your concern on value and damages to your parcel: The City and its consultants will follow the Right-of-Way Requirements of the Uniform Act (49 CFR Part 24) under Valuation, Acquisitions and Negotiation, and Relocation Assistance. The owner will also be notified and given the opportunity to meet the appraiser at the time of inspection of the property and at that time the owner may provide documents and explanation of how the property is being utilized and marketed.



-	
2	Commenter: Nicholas White/Central Valley Regional Water Quality Control Board, Received December 28, 2020
	Gives Nectoor
	Water Boards
	Central Valley Regional Water Quality Control Board
	28 December 2020
	Michael King City of Lathrop 390 Towne Center Drive Lathrop, CA 95330
	COMMENTS TO REQUEST FOR REVIEW FOR THE MITIGATED NEGATIVE DECLARATION, HARLAN ROAD REALIGNMENT AT ROTH ROAD PROJECT, SCH#2020110445, SAN JOAQUIN COUNTY
	Pursuant to the State Clearinghouse's 25 November 2020 request, the Central Valley Regional Water Quality Control Board (Central Valley Water Board) has reviewed the <i>Request for Review for the Mitigated Negative Declaration</i> for the Harlan Road Realignment at Roth Road Project, located in San Joaquin County.
	Our agency is delegated with the responsibility of protecting the quality of surface and groundwaters of the state; therefore our comments will address concerns surrounding those issues.
A	I. Regulatory Setting
	Basin Plan The Central Valley Water Board is required to formulate and adopt Basin Plans for all areas within the Central Valley region under Section 13240 of the Porter-Cologne Water Quality Control Act. Each Basin Plan must contain water quality objectives to ensure the reasonable protection of beneficial uses, as well as a program of implementation for achieving water quality objectives with the Basin Plans. Federal regulations require each state to adopt water quality standards to protect the public health or welfare, enhance the quality of water and serve the purposes of the Clean Water Act. In California, the beneficial uses, water quality objectives, and the Antidegradation Policy are the State's water quality standards. Water quality standards are also contained in the National Toxics Rule, 40 CFR Section 131.36, and the California Toxics Rule, 40 CFR Section 131.38.
	The Basin Plan is subject to modification as necessary, considering applicable laws, policies, technologies, water quality conditions and priorities. The original Basin Plans were adopted in 1975, and have been updated and revised periodically as required, using Basin Plan amendments. Once the Central Valley Water Board has adopted a Basin Plan amendment in noticed public hearings, it must be approved by the State Water Resources Control Board (State Water Board), Office of Administrative Law (OAL) and in some cases, the United States Environmental KARE E. LOBERTY SCD, P.E., CHARE PROPERTIES.
	11020 Şun Çenter Drive 4200, Bancho Çundova, ÇA 95870 www.wetertxoards.co.gov/centralvelley



at	larlan Road Realignment t Roth Road Project an Joaquin County	-2-	28 December 2020
	Protection Agency (USEPA). Basin they have been approved by the OAI (3) years, a review of the Basin Plan of existing standards and evaluates a information on the <i>Water Quality Con</i> <i>River Basins</i> , please visit our website <u>http://www.waterboards.ca.gov/centr</u>	L and in some cases, the U is completed that assesses and prioritizes Basin Planni atrol Plan for the Sacrament e:	SEPA. Every three the appropriateness ng issues. For more to and San Joaquin
	Antidegradation Considerations All wastewater discharges must com Board Resolution 68-16) and the Ant the Basin Plan. The Antidegradation at: https://www.waterboards.ca.gov/cen 05.pdf	idegradation Implementatio Implementation Policy is a	on Policy contained in vailable on page 74
	In part it states:		
	Any discharge of waste to high quali or control not only to prevent a condi also to maintain the highest water qu benefit to the people of the State.	tion of pollution or nuisance	e from occurring, but
	This information must be presented a impacts of the discharge on water qu concentrations and applicable water	ality, as measured by back	
	The antidegradation analysis is a ma Discharge Elimination System and la (WDRs) permitting processes. The e potential impacts to both surface and	nd discharge Waste Discha environmental review docum	arge Requirements
П.	. Permitting Requirements		
	Construction Storm Water General Dischargers whose project disturb or disturb less than one acre but are pa in total disturbs one or more acres, a General Permit for Storm Water Disc Disturbance Activities (Construction Order No. 2009-0009-DWQ. Constru- clearing, grading, grubbing, disturban excavation, but does not include regis the original line, grade, or capacity of requires the development and impler Plan (SWPPP). For more information State Water Resources Control Boar http://www.waterboards.ca.gov/water ml	te or more acres of soil or v rt of a larger common plan re required to obtain covera harges Associated with Co General Permit), Constructi uction activity subject to this nees to the ground, such as ular maintenance activities if the facility. The Construct nentation of a Storm Water n on the Construction Gene d website at:	of development that age under the nstruction and Land on General Permit s permit includes s stockpiling, or performed to restore ion General Permit Pollution Prevention eral Permit, visit the



Harlan Road Realignment 28 December 2020 - 3 at Roth Road Project San Joaquin County Clean Water Act Section 404 Permit If the project will involve the discharge of dredged or fill material in navigable waters or wetlands, a permit pursuant to Section 404 of the Clean Water Act may be needed from the United States Army Corps of Engineers (USACE). If a Section 404 permit is required by the USACE, the Central Valley Water Board will review the permit application to ensure that discharge will not violate water guality standards. If the project requires surface water drainage realignment, the applicant is advised to contact the Department of Fish and Game for information on Streambed Alteration Permit requirements. If you have any questions regarding the Clean Water Act Section 404 permits, please contact the Regulatory Division of the Sacramento District of USACE at (916) 557-5250. Clean Water Act Section 401 Permit – Water Quality Certification If an USACE permit (e.g., Non-Reporting Nationwide Permit, Nationwide Permit, Letter of Permission, Individual Permit, Regional General Permit, Programmatic General Permit), or any other federal permit (e.g., Section 10 of the Rivers and Harbors Act or Section 9 from the United States Coast Guard), is required for this project due to the disturbance of waters of the United States (such as streams and wetlands), then a Water Quality Certification must be obtained from the Central Valley Water Board prior to initiation of project activities. There are no waivers for 401 Water Quality Certifications. For more information on the Water Quality Certification, visit the Central Valley Water Board website at: https://www.waterboards.ca.gov/centralvalley/water issues/water guality certificatio n/ Waste Discharge Requirements – Discharges to Waters of the State If USACE determines that only non-jurisdictional waters of the State (i.e., "nonfederal" waters of the State) are present in the proposed project area, the proposed project may require a Waste Discharge Requirement (WDR) permit to be issued by Central Valley Water Board. Under the California Porter-Cologne Water Quality Control Act, discharges to all waters of the State, including all wetlands and other waters of the State including, but not limited to, isolated wetlands, are subject to State regulation. For more information on the Waste Discharges to Surface Water NPDES Program and WDR processes, visit the Central Valley Water Board website at:https://www.waterboards.ca.gov/centralvalley/water issues/waste to surface wat er/ Projects involving excavation or fill activities impacting less than 0.2 acre or 400 linear feet of non-jurisdictional waters of the state and projects involving dredging activities impacting less than 50 cubic yards of non-jurisdictional waters of the state may be eligible for coverage under the State Water Resources Control Board Water Quality Order No. 2004-0004-DWQ (General Order 2004-0004). For more information on the General Order 2004-0004, visit the State Water Resources Control Board website at: https://www.waterboards.ca.gov/board_decisions/adopted_orders/water_guality/200 4/wgo/wgo2004-0004.pdf



at Roth Road Project San Joaquin County Dewatering Permit If the proposed project includes construction or groundwater dewatering to be discharged to land, the proponent may apply for coverage under State Water Board General Water Quality Order (Low Threat General Order) 2003-0003 or the Central Valley Water Board's Waiver of Report of Waste Discharge and Waste Discharge Requirements (Low Threat Waiver) R5-2018-0085. Small temporary construction dewatering projects are projects that discharge groundwater to land from excavator activities or dewatering of underground utility vaults. Dischargers seeking coverage under the General Order or Waiver must file a Notice of Intent with the Central Valley Water Board prior to beginning discharge. For more information regarding the Low Threat General Order and the application process, visit the Central Valley Water Board website at: http://www.waterboards.ca.gov/board decisions/adopted_orders/water_quality/2003 wqo/wqo2003-0003.pdf For more information regarding the Low Threat Waiver and the application process, visit the Central Valley Water Board website at: https://www.waterboards.ca.gov/centralvalley/board_decisions/adopted_orders/waivers/f5-2018-0085.pdf Limited Threat General NPDES Permit If the proposed project includes construction dewatering and it is necessary to discharge the groundwater to waters of the United States, the proposed project will require coverage under a National Pollutant Discharge Elimination System (NPDES permit. Dewatering discharges are typically considered a low or limited Threat Discharges to Surface Water (Limited Threat General Order). A complete Notice of Intent must be submitted to the Central Valley/board_decisions/adopted_orders/oem rai_orders/f5-2016-0076-01.pdf If you have questions regarding these comments, please contact me at (916) 464-4856 or Nicholas White Water Resource Control Engineer cc: State Clearinghouse unit, Governor's Office of Planning and Research,	at Roth Road Project San Joaquin County <u>Dewatering Permit</u> If the proposed project includes discharged to land, the propon General Water Quality Order (I Valley Water Board's Waiver o Requirements (Low Threat Wa dewatering projects are project activities or dewatering of unde under the General Order or Wa Valley Water Board prior to be For more information regarding	s construction or grour ent may apply for cove Low Threat General O f Report of Waste Disc iver) R5-2018-0085. Is that discharge grour erground utility vaults. aiver must file a Notice	erage under State Water Board rder) 2003-0003 or the Central charge and Waste Discharge Small temporary construction ndwater to land from excavation
If the proposed project includes construction or groundwater dewatering to be discharged to land, the proponent may apply for coverage under State Water Board General Water Quality Order (Low Threat General Order) 2003-0003 or the Central Valley Water Board's Waiver of Report of Waste Discharge and Waste Discharge Requirements (Low Threat Waiver) R5-2018-0085. Small temporary construction dewatering projects are projects that discharge groundwater to land from excavatior activities or dewatering of underground utility vaults. Dischargers seeking coverage under the General Order or Waiver must file a Notice of Intent with the Central Valley Water Board prior to beginning discharge. For more information regarding the Low Threat General Order and the application process, visit the Central Valley Water Board website at: http://www.waterboards.ca.gov/board decisions/adopted orders/water quality/2003 wqo/wqo2003-0003.pdf For more information regarding the Low Threat Waiver and the application process, visit the Central Valley Water Board website at: https://www.waterboards.ca.gov/centralvalley/board_decisions/adopted_orders/waivers/f5-2018-0085.pdf Limited Threat General NPDES Permit If the proposed project includes construction dewatering and it is necessary to discharge the groundwater to waters of the United States, the proposed project will require coverage under a National Pollutant Discharge Elimination System (NPDES) permit. Dewatering discharges are typically considered a low or limited threat to water General Order for Limited Threat General Order. For more information regarding the Low Threat Walter Board uebsite at:			



	Response to Comment 2A:
	Thank you for your comments. They have been included within the final environmental document. The District will comply with all applicable permitting requirements prior to construction.
3	Commenter: Nicholas Fung for Tom Dumas/California Department of Transportation, Received January 19, 2021 and January 20, 2021



STATE OF CALIFORNIA-BUSINESS, TRANSPORTATION AND HOUSING AGENCY Gavin Newsom, Gov DEPARTMENT OF TRANSPORTATION P.O. BOX 2048 STOCKTON, CA 95201 (1976 E. CHARTER WAY/1976 E. DR. MARTIN LUTHER KING JR. BLVD. 95205) TTY: California Relay Service (800) 735-2929 Making Conservation a California Way of Life. PHONE (209) 941-1921 FAX (209) 948-7194 January 19, 2021 10-SJ-5-PM R 019.622 SCH#2020110445 Harlan Road Realignment At Roth Road, Lathrop Michael King City of Lathrop 390 Towne Center Drive Lathrop, CA 95330 Dear Mr. King: The California Department of Transportation appreciates the opportunity to review the draft Initial Study and Mitigated Negative Declaration for the proposed Harlan Road Realignment at Roth Road as well as the as well as the July 24, 2020 Traffic Evaluation performed by Kimley Horn. The project proposes to shift the Harlan Road/Roth Road intersection approximately 600 feet east. This will increase spacing between the intersection and the I-5/Roth ramps and allow for future improvements. Three separate alternatives are being considered. The Department has the following recommendations: 1. Table 3 should read Cumulative (2040) No Project to avoid confusion. The Traffic Evaluation lacks a table similar to Table 3 for the northbound and southbound ramps Α intersection. 2. The Synchro/Simtraffic files provided show the existing intersection #4 (Roth Rd/Harlan Rd intersection) NB/SB as closed under the Cumulative 2040 plus project. However, the report does not show a figure of this scenario. Each scenario should have tables and figures. For example, Figure 5 shows both existing and proposed intersection 4 (Cumulative 2040 traffic volume is shown) however, the proposed intersection 4 volume is missing from the report. For clarification, please include a Figure to reflect the results of the Synchro files Cumulative 2040 Plus Project intersections lane configurations and volume. All figures should show the lane configurations and volume under each scenario to be consistent and to avoid confusion. Since intersection 4 is phased, it would be helpful to show it at its ultimate location, and show the lane configurations and volume in exhibits for each scenario. 4. In order to clarify Exhibit 5 please change to "No Project Cumulative (2040) Peak-Hour Traffic Volume". Correct intersection lane configurations and traffic volumes should be reflected in each scenario in each exhibit. "Caltrans improves mobility across California"



Mr. King January 19, 2021 Page 2 5. For Exhibit 5, please remove the movement arrows and show lane configuration arrow with volume for each scenario in the exhibit to clarify the confusion. 6. Table 2 shows the existing intersection 4 is improved from AWSC to Signalization through Cumulative 2040 plus project. However, Synchro Analysis shows this existing intersection's NB/SB lanes are closed and is changed to EB/WB free flow. If you have any questions or would like to discuss our comments in more detail, please contact Nicholas Fung at (209) 948-7190 or myself at (209) 941-1921. Caltrans looks forward to working on this important project with the City in a collaborative manner. Sincerely, Nichola FD FOR TOM DUMAS, CHIEF OFFICE OF METROPOLITAN PLANNING "Caltrans improves mobility across California"



	From: Fung, Nicholas@DOT < <u>nicholas.fung@dot.ca.gov</u> >
	Sent: Wednesday, January 20, 2021 9:19 AM
	To: Michael King < <u>mking@ci.lathrop.ca.us</u> >
	Cc: Jacqueline Lockhart < <u>ilockhart@dokkenengineering.com</u> >; Dumas, Thomas A@DOT
	<tom.dumas@dot.ca.gov></tom.dumas@dot.ca.gov>
	Subject: Follow-up: Caltrans comments on Harlan Road Realignment
	Hello all. This is an addendum to the letter we sent you yesterday. An Encroachment Permit
В	will be required for any work done within the Department's right of way. This work is
	subject to the California Environmental Quality Act. Therefore, environmental studies may
	be required as part of the encroachment permits application. A qualified professional must
	conduct any such studies undertaken to satisfy the Department's environmental review
	responsibilities. Ground disturbing activities to the site prior to completion and/or approval
	of required environmental documents may affect the Department's ability to issue a permit
	for the project. Furthermore, if engineering plans or drawings will be part of your permit
	application, they should be prepared in standard units.
	Please let me know if you have any questions.
	Nicholas Fung
	Caltrans District 10
	Metropolitan Planning
	Response to Comment 3A:
	Thank you for your comment. The City has revised the Traffic Study for the Project per
	Caltrans comments. A copy of the updated study will be submitted to Caltrans for further
	review.
	Response to Comment 3B:
	•
	An Encroachment Permit will be obtained prior to construction. All applicable
	environmental studies will be provided at that time.
	' '