



PLANNING COMMISSION
STAFF REPORT

DATE: July 19, 2023

APPLICATION NO: River Islands West Village Architectural Design Guidelines and Development Standards for Non-Active Adult Neighborhoods (DG/DS) Neighborhood Design Plan No. NDP-23-73

LOCATION: West Village District (Phase 2 of River Islands at Lathrop)

REQUEST: Planning Commission to Consider Adoption of a Resolution Approving an Amendment to the West Village Architectural Design Guidelines and Development Standards for Non-Active Adult Neighborhoods for River Islands at Lathrop (Phase 2)

APPLICANT: River Islands Stage 2B, LLC
73 W. Stewart Road
Lathrop, CA 95330

PROPERTY OWNER: River Islands Development Area 1, LLC
73 W. Stewart Road
Lathrop, CA 95330

CEQA STATUS: The Proposed Project Falls within the Scope of the Previously Certified Subsequent Environmental Impact Report (SEIR) (SCH No. 1993112027) for the River Islands at Lathrop Phase 2 Project.

SUMMARY:

The applicant is requesting approval of the Architectural Design Guidelines and Development Standards (DG/DS) for the Non-Active Adult Neighborhoods of the West Village District of River Islands Phase 2. In compliance with the West Lathrop Specific Plan (WLSP) for Phase 2, River Island Development, LLC (RID) has prepared the DG/DS for Planning Commission review and approval.

Staff recommends the Planning Commission adopt Resolution No. 23-8 approving the DG/DS for Non-Active Adult Neighborhoods of the West Village District of River Islands at Lathrop.

SITE DESCRIPTION

The West Village District is located within Phase 2 of the River Islands development, specifically within the boundaries of Vesting Tentative Map (VTM) 6716. The District consists of nine (9) villages, three (3) different lot sizes for active adult, and villages for low density residential, clustered single-family residential, condominiums, and apartments. The District also includes a community park, high school and open space. The location and boundary of West Village District is illustrated in Attachment 2.

BACKGROUND

In 2021, the River Islands project received approval for various major entitlements for Phase 2, including approval of a Subsequent Environmental Impact Report, Phase 2 WLSP, Phase 2 Urban Design Concept, Phase 2 Vesting Tentative Map Tract 6716, which provides for the development of 10,726 residential units (single and multifamily), commercial development, mixed use development, transit oriented development, and associated public amenities including parks, schools, roadways, open space, and public rights-of-way, and Phase 2 Preliminary Development Plan.

The West Lathrop Specific Plan for Phase 2 requires the preparation of a Neighborhood Development Plan (NDP) and Architectural Design Guidelines and Development Standards (DG/DS) for areas of new development within River Islands. The NDP provides requirements for the use, development, improvement and maintenance of master developer-constructed portions of the River Islands project. Alternatively, the purpose of the DG/DS is to establish design guidelines and standards for residential development and associated site improvements to be constructed by the residential builders. This includes overall residential design principles, guidelines for orientation, siting and architecture of new residences, and more specific guidelines for building form, roof style, wall and window details, outdoor spaces and colors.

The NDP for the West Village District and the DG/DS for the Active Adult Neighborhoods were both approved by Planning Commission on October 19, 2022 via PC Resolution No. 22-11. The West Village District NDP also encompasses the proposed DG/DS for the Non-Active Adult Neighborhoods. These documents together provide the necessary standards and guidelines for development within both the Active & Non-Active Adult Neighborhoods as well as master developer-constructed improvements, including but not limited to roadways, parkway landscaping, the Community Park, and signage.

The DG/DS for the Non-Active Adult Neighborhoods for the West Village District was presented to the Stewart Tract Design Review Committee (STDRC) on July 5, 2023. The STDRC voted unanimously to recommend the NDP and DG/DS for Planning Commission approval, attached to this Staff Report as Attachment 3.

ANALYSIS

The proposed DG/DS for Non-Active Adult Neighborhoods establishes design guidelines and development standards for residential development and associated improvements to be constructed by residential builders within the Low Density, Medium Density, High Density, and Single-Family Clustered Residential areas. This includes overall design principles, guidelines for orientation, siting, and architecture of new residences, and more specific design guidelines for building form, roof style, wall and window details, outdoor spaces, and colors for nine (9) architectural styles. These styles include:

- American Traditional
- European Cottage
- Savannah
- California Ranch
- Craftsman
- California Modern
- Modern Farmhouse
- Spanish Eclectic
- Modern Prairie

Similar to the previous districts, the West Village District DG/DS for Non-Active Adult Neighborhoods describes specific development standards (i.e. lot size, yard requirements, building height, parking requirements) for each of the residential lot sizes. The DG/DS also specifies residential facades and side yards that will require “enhanced architectural elevations.” In addition, the DG/DS provides landscaping guidelines and standards for streetscapes, front yard areas, and rear yards on lake slopes of waterfront lots and walls and fences to be developed by the residential builders.

Additionally, the West Village DG/DS for Non-Active Adult Neighborhoods includes specific design criteria for the development of Condominiums and Apartments, including but not limited to siting, amenities, off-street parking, landscaping, etc.

The DG/DS will serve as a resource document for the STDRC, Planning Commission, City Council (as applicable) and City staff in their review of subsequent approvals. The Planning Commission is the final approval authority for the DG/DS. The West Village DG/DS for the Non-Active Adult Neighborhoods is attached to this Staff Report as Attachment 4.

CEQA REVIEW

Environmental review for the River Islands project as a whole was completed in the certified Subsequent Environmental Impact Report (SEIR) for the River Islands at Lathrop Phase 2 Project (State Clearinghouse No. 1993112027). The SEIR considered the full range of potential environmental effects of urban development of the entire River Islands Project, including planned urban development of the Project Site.

The project would not produce any new significant environmental impacts, and no new mitigation measures are required. The SEIR specified the mitigation measures needed to reduce potentially significant environmental effects of the River Islands project to a less than significant level. The project is required to conform to these mitigation measures.

RECOMMENDATION:

Staff recommends that the Planning Commission adopt Resolution No. 23-8, approving the West Village District Architectural Design Guidelines and Development Standards (DG/DS) for the Non-Active Adult Neighborhoods for River Islands at Lathrop (Phase 2).

Approvals:


Trent DaDalt, Assistant Planner

7/11/2023
Date


James Michaels, Senior Planner

7/11/2023
Date


Rick Caguiat, Community Development Director

7/11/2023
Date


Salvador Navarrete, City Attorney

7-12-2023
Date

Attachments:

1. PC Resolution No. 23-8 for West Village District DG/DS for Non-Active Adult Neighborhoods
2. Vicinity Map
3. STDRC DG/DS Recommendation Letter dated July 5, 2023
4. West Village District DG/DS for Non-Active Adult Neighborhoods

**CITY OF LATHROP
PLANNING COMMISSION RESOLUTION NO. 23-8**

**A RESOLUTION OF THE PLANNING COMMISSION OF THE CITY OF LATHROP
APPROVING THE WEST VILLAGE DISTRICT ARCHITECTURAL DESIGN
GUIDELINES AND DEVELOPMENT STANDARDS (DG/DS) FOR NON-ACTIVE
ADULT NEIGHBORHOODS (NDP-23-73)**

WHEREAS, the City of Lathrop Planning Commission held a duly noticed public meeting to consider the proposed project pursuant to the Lathrop Municipal Code; and

WHEREAS, the request is to approve the Architectural Design Guidelines and Development Standards (DG/DS) for Non-Active Adult Neighborhoods for the West Village District of River Islands at Lathrop (Phase 2); and

WHEREAS, The Neighborhood Design Plan (NDP) for the West Village District and the Architectural Design Guidelines and Development Standards (DG/DS) for the Active Adult Neighborhoods were both approved by Planning Commission on October 19, 2022 via PC Resolution No. 22-11; and

WHEREAS, The West Village District Neighborhood Design Plan (NDP) also encompasses the proposed Architectural Design Guidelines and Development Standards (DG/DS) for the Non-Active Adult Neighborhoods; and

WHEREAS, the City of Lathrop has adopted the West Lathrop Specific Plan (WLSP) for Phase 2, which governs land use and development for the West Village District; and

WHEREAS, the River Islands Urban Design Concept (UDC) for Phase 2 has been prepared and approved by the City Council in accordance with the requirements of the WLSP Phase 2; and

WHEREAS, the Phase 2 WLSP requires that Architectural Design Guidelines be prepared, reviewed by the Stewart Tract Design Review Committee (STDRC), and approved by the Planning Commission for each community within the River Islands project; and

WHEREAS, on July 5, 2023, the STDRC voted unanimously to recommend the NDP and DG/DS for Planning Commission approval; and

WHEREAS, the environmental review for the River Islands project as a whole was completed in the certified Subsequent Environmental Impact Report (SEIR) for the River Islands at Lathrop Phase 2 Project (State Clearinghouse No. 1993112027). The SEIR considered the full range of potential environmental effects of urban development of the entire River Islands Project, including planned urban development of the Project Site. The project would not produce any new significant environmental impacts, and no new mitigation measures are required. The SEIR specified the mitigation measures needed to reduce potentially significant environmental effects of the River Islands project to a less than significant level. The project is required to conform to these mitigation measures; and

WHEREAS, proper notice of this public meeting was given in all respects as required by law; and

WHEREAS, the Planning Commission has reviewed all written evidence and oral testimony presented to date.

WHEREAS, that the Planning Commission of the City of Lathrop does hereby make the following finding that the proposed project will comply with the requirements of the Zoning Ordinance and design standards of the Lathrop Municipal Code upon development, as conditioned and is consistent with the following land use goals and policies of the City of Lathrop General Plan:

- **LU-1.4:** *“Continue to support the development of a variety of housing types and densities that meet the needs of individuals and families, and offers residents of all income levels, age groups and special needs sufficient housing opportunities and choices. (Additional policies specifically related to Housing are included in the General Plan’s Housing Element)”*
- **LU-1.7:** *“Ensure consistency between the Land Use Map and implementing plans, ordinances, and regulations.”*
- **LU-1.9:** *“Promote equitable land use patterns to ensure that all residents in neighborhoods have access to community amenities and transportation choices, and have safe places to walk and bike.”*

THEREFORE, BE RESOLVED that the Planning Commission of the City of Lathrop based on substantial evidence in the administrative record of proceedings and pursuant to its independent review and consideration, does hereby approve the Architectural Design Guidelines and Development Standards for Non-Active Adult Neighborhoods for the West Village District of River Islands at Lathrop (Phase 2).

PASSED AND ADOPTED by the Planning Commission of the City of Lathrop at a Regular Meeting on the 19th day of July 2023, by the following vote:

AYES:

NOES:

ABSTAIN:

ABSENT:

Tosh Ishihara, Chair


ATTEST:

APPROVED AS TO FORM:

Rick Caguiat, Secretary




Salvador Navarrete, City Attorney



**PLANNING DIVISION
Vicinity Map**



**NDP-23-73
Neighborhood Design Plan (NDP) &
Architectural Design Guidelines and
Development Standards (DG/DS) for
Non-Active Adult Neighborhoods
West Village District
River Islands (Phase 2)**





July 5, 2023

Rick Caguiat
City of Lathrop
390 Towne Centre Drive
Lathrop, CA 95330
Email: rcaguiat@ci.lathrop.ca.us

Subject: Recommendation for Approval of River Islands West Village Non-Active Adult
AG/DS Document

Dear Rick:

At its meeting of July 5, 2023, the Stewart Tract Design Review Committee voted unanimously to recommend approval of the West Village District Non-Active Adult Architectural Guidelines and Design Standards (AG/DS) to the Lathrop Planning Commission

An electronic copy of the document will be transmitted to you. Please let us know if you require hard copies.

If you have any questions regarding this letter, please feel free to contact me at (209) 879-7900 or at sdelloso@riverislands.com.

Sincerely,

Susan Dell'Osso, President
River Islands Development Area 1, LLC

cc: Brad Taylor, City Engineer
Ed Short, City of Lathrop Chief Building Official
James Michaels, Senior Planner
Trent Dedalt, City of Lathrop Assistant Planner
Ken Reed, Senior Construction Manager



RIVER
ISLANDS

WEST VILLAGE DISTRICT
NON-ACTIVE ADULT NEIGHBORHOODS

JULY 12, 2023
PLANNING COMMISSION DRAFT

ARCHITECTURAL
DESIGN GUIDELINES

&

DEVELOPMENT
STANDARDS




Imagery depicted on this document is used only for purposes of conveying architectural and/or planning concepts and may or may not represent the work of Dahlin Group Architecture Planning.

RIVER ISLANDS



TABLE OF CONTENTS





Chapter 1 Community Overview 1

1.1 Introduction..... 3

1.1.1 Purpose & Intent 4

1.1.2 Relationship to West Lathrop Specific Plan 4

1.1.3 Language and Organization of Document 4

1.2 Architecture Design Principles 6

1.2.1 Regional Precedents 6

1.2.2 Three Architectural Districts 7

1.2.3 Energy Efficiency 8

Chapter 2 Architecture 10

2.1 Design Guidelines 11

2.1.1 Architectural Character 11

2.1.2 Streetscape..... 11

2.1.3 Building Elements 12

2.1.4 Building Materials and Colors 14

2.1.5 Architectural Styles..... 15

American Traditional..... 16

European Cottage 20

Savannah 24

California Ranch 28

Craftsman 32

California Modern 36

Modern Farmhouse 40

Spanish Eclectic 44

Modern Prairie..... 47

2.2 Development Standards 50

2.2.1 Low Density Res. (LDR) Dev. Standards..... 53

2.2.2 Medium Density Res. (MDR) Dev. Standards.. 54

2.2.3 High Density Res. Dev. Standards 55

2.3 Technical Specifications:..... 63

2.3.1 Structural Wiring (LDR & MDR Only)..... 63

Chapter 3 Landscape 67

3.1 Introduction..... 68

3.2 Residential Landscape..... 69

3.2.1 Planting Design..... 72

3.2.2 Front and Side Yards 72

3.2.3 Rear Yards 72

3.3 Site Furnishings/ Materials 74

3.3.1 Fences 74

3.3.2 Signage..... 78

3.3.3 Landscape Lighting..... 78

3.3.4 Paving and Hardscape 78

3.4 Landscape Construction Practices 79

3.4.1 Irrigation and Water Conservations 79

3.4.2 Soil Preparation and Mulching 80

Chapter 4 Project Implementation 81

4.1 Project Implementation 83

4.1.1 Stewart Tract Design Review and Committee
(STDRC) 83

4.1.2 Consistency Requirements..... 83

4.1.3 Design Review Submittal Requirements 83

APPENDIX 85

Accessory Structures 86

Builder Identification Signs 87

Plant List 90




Figure 1.0 River Islands Overall Illustrative Map

This page intentionally left blank

1.1 Introduction

River Islands has been designed as the premier master planned community in Northern California. Its island location, on the San Joaquin River in Lathrop, provides a backdrop of nearly 5,000 acres for a mixed use community of 15,010 homes, nearly 4 million square feet of commercial space and ten schools. Such community recreational amenities as lakes, walking trails, parks and a boathouse are all part of the vision for our first neighborhoods. This document will cover

the non-active adult residential housing units within the West Village District to provide a descriptive vision of this unique part of the River Islands master plan. Non-active adult units may be single-family or multi-family units.

Figure 1.1 shows the location of River Islands, and its relationship to the major highways and surrounding cities.



Figure 1.1 Location Map

1.1.1 Purpose & Intent

The Architectural Guidelines and Development Standards of River Islands (AG/DS) complement the River Islands Urban Design Concept (UDC) and Neighborhood Development Plan (NDP). Since the West Village District is located within Phase 2, the Phase 2 UDC adopted by the Lathrop City Council on June 14, 2021 has the direction needed for this AG/DS document. The City Council also adopted an update to the West Lathrop Specific Plan (WLSP) that updates the land uses, zoning, general development framework and other design policies for both the NDP and the AG/DS. The documents provide the specific standards and guidelines for the Stewart Tract Design Review Committee (STDRC) and Lathrop Community Development Development to review and evaluate new development proposals involving non-Active-Adult residential developments within the West Village District in particular.

1.1.2 Relationship to West Lathrop Specific Plan (WLSP)

The West Lathrop Specific Plan (WLSP) provides the authority to which the River Islands AG/DS has been prepared. As described in the WLSP, each sub-area of each District must have a set of written guidelines and standards for new development. This document applies only to the Non-Active Adult neighborhoods of the West Village District. The reason for separating this document from other areas of West Village is because of the unique nature of the Active Adult product, which is specifically marketed to buyers over 55 years old. A separate AG/DS document has already been approved for the Active Adult product in West Village District.

1.1.3 Language and Organization of Document

These AG/DS are divided into three major sections: Architecture; Landscape and Project Implementation. Architecture and Landscape are each further divided into Design Guidelines and Development Standards. Together, these will assure that neighborhood home builders and individual homeowners have the guidance to carry out the vision for West Village.

The Design Guidelines describe the overall design quality that River Islands envisions. Complementary sketches, imagery, diagrams, and other graphic materials further illustrate the AG/DS design intent. The words “should”; “may” and “can” indicates that the guideline is highly recommended and suggests possible design solutions that are acceptable and encouraged, but not required.

The Development Standards section addresses the particular design criteria, conditions and standards that shall be met when designing homes and landscape. The River Islands AG/DS uses careful language to assist the STDRC in reviewing design proposals. The words, “shall”, “will”, and “must” are to be implemented requirements. All development standards intended to supplement the WLSP’s and City of Lathrop’s zoning requirements use this language.

The Project Implementation Section will guide home builders and home owners through the approval and permit process.



Figure 1.2 River Islands District Diagram (Currently Approved and Pending)

1.2 Architecture Design Principles

The character and quality of River Islands' architecture is an important factor in creating the overall identity of the community. Although it is likely that there will ultimately be a variety of architectural styles in the community, the following design principles are intended to provide the guidance that will assure unity and consistency in architectural design.

1.2.1 Regional Precedents

The region of San Joaquin and Sacramento River Deltas is rich in precedents that can serve as the basis for the architecture of River Islands. These include not only the historical architectural tradition, but the climate, natural environment, and cultural history. There are 4 distinct influences identified for this area, that provide us with the architectural styles that will be considered for the River Islands community.

River Edge

The use of the river system for commerce has been largely replaced by recreational use. Still, remnants of the river's use as the primary conduit for goods and materials, as well as the agricultural products of the region, remain. The simple, economical forms and materials of river edge industrial buildings, and their docks and quays provide a meaningful source for the architecture of the Town Center.

Similarly, the tradition of placing large homes on high ground near the river edge, with their small docks and boat houses provides inspiration for the design of residential buildings along the river.

River Delta

Because of the abundant water, flat slopes and easily worked soils, river deltas have always been desirable for agriculture. The tradition of farmsteads in the Delta, with their simple farmhouses and outbuildings, can be a particularly rich source for residential building design.



Mediterranean Climate

The climate of the delta is Mediterranean: cool, moist winters are followed by warm, dry summers. The prevailing westerly winds bring in cool air from the Pacific, making evenings pleasant, even in the summer. Often homes in this area were built with large roof overhangs and porches to limit the heat gain in the house, or with carefully placed large trees and shade structures.

Delta History & Culture

Originally part of the Rancho Pescadero, River Islands has a direct historical connection to the Spanish and Mexican Land Grant system that characterized California in the eighteenth and early nineteenth century. The discovery of gold north and east of River Islands, and the subsequent boom are also part of the region's architectural influences. The simple, slapdash architecture of boom towns, and the subsequent opulence of the Victorian Era are a part of the architectural history of the region. The traditions of agriculture and river-based industry are the most prevalent historical influences, however, and provide perhaps the most fitting stimulus for architectural design at River Islands.

1.2.2 Three Architectural Districts

As described in the UDC, River Islands is divided into three architectural districts based primarily on the dominant use within the district: Residential, Town Center and Employment Center. The requirements for the architecture of each district vary, as described in the following paragraphs.

Residential District

The architecture of the residential districts of the River Islands community will contain a wide variety of architectural styles and influences. The styles will be based on historical precedents from the region, such as those found in farmsteads, the river edge, or in the older residential neighborhoods of valley and delta cities. Modern adaptations of these styles will also be proposed, though the intent is to create an appearance and feeling of old tradition architecture. The mixing of styles within individual neighborhoods will be limited so that visual unity can be achieved, and strange juxtapositions avoided. See the specific description of how this set of AG/DS addresses the West Village and Non-Active Adult developments.

Village Center

The architecture of the Paradise Cut Village Center will vary according to land use and location. Retail and commercial architecture could be inspired by historical commercial and industrial building types that might be found in other riverfront towns. Ideally, this area should appear as if it developed over time, with the participation of numerous designers. Unity will be achieved primarily by uniformity of use and development standards, such as building mass and setbacks. A NDP and AG/DS, or equivalent Paradise Cut Village Center Plan will detail the specifics of these standards and the architecture to be utilized.

Employment Center/Transit Oriented Development

Employment Center/Transit Oriented Development will be a mixed-use area likely to be implemented with more contemporary styles of architecture for its higher density residential housing. For office, retail and commercial uses, the architectural styles will be the most modern of any of the three

districts. Larger floorplate office and commercial buildings will generally be simple, modern, rectilinear forms with flat roofs. Masonry, concrete tilt-up and other economical building types will be predominant. Buildings with historical references will likely be limited to retail centers or restaurants. A NDP and AG/DS, or equivalent Employment Center/Transit Oriented Development Plan will detail the specifics of these standards and the architecture to be utilized.

Residential District (West Village)

The architecture of the West Village District will include both historical architectural styles of California, along with more modern themes that predominate today's housing market. Unity will be achieved primarily by uniformity of use and development standards, such as building mass and setbacks.

This set of guidelines was developed for the portions of the West Village District that are separate and distinct from the Active Adult neighborhoods. The reason is that the traditional market rate residential neighborhoods that make up the balance of the West Village District will be more akin to those already constructed in Phase 1 of River Islands which will include detached single-family homes of both single story and two-story construction, attached single-family product (such as clustered housing and bungalows), as well as medium density multi-family dwelling units. High-density residential units may also employ the same architectural themes as outlined in this AG/DS, however additional themes may be added in the future for high density developments as well.

1.2.3 Energy Efficiency

All buildings within River Islands should be designed to conserve energy as required by the State of California's CALGreen Code. Among the methods that should be considered are:

- ^ Passive solar design: thermal masses to absorb winter sun energy, roof overhangs, and carefully placed deciduous trees to provide summer shade;
- ^ Active solar design: solar collectors to heat water, or photo voltaic cells to generate electricity;
- ^ Energy efficient mechanical equipment for heating and cooling, such as heat pumps;
- ^ Extra thermal insulation in roofs and walls to control heat gain and loss;
- ^ Operable windows in commercial buildings; to reduce dependence on mechanical ventilation;
- ^ Home integrated systems: wireless PC based systems that allow homeowners to program appliances to restrict usage during peak energy periods;
- ^ Load shifting technologies: thermal energy storage for residential and commercial use that moves the operation of air conditioning compressors from on-peak operation to off-peak hours;
- ^ Thermal rated glazing, including reflective coatings to reduce heat load in the summer;
- ^ Utilization of Energy Star rated appliances.

This page left intentionally blank



RIVER ISLANDS



CHAPTER 2


ARCHITECTURE

2.1 Design Guidelines

2.1.1 Architectural Character

Future residential village neighborhoods in River Islands will present diverse and varied streetscapes with interesting mix of architectural styles and motifs. Individual Village Districts should be designed and developed into themed residential neighborhoods with a coordinated mix of plans and elevation styles within any specific housing product line. The primary theme of each residential neighborhood will aim to create authentic Central Valley-inspired community with well crafted architectural mix and site-specific landscape features.

The key to a visually cohesive residential neighborhood can be achieved by modern interpretation of heritage architectural styles surveyed and collected throughout the region with keen attention to details and craftsmanship.



Encouraged garage layouts

2.1.2 Streetscape

Minimizing the visual impact of garage doors on the front elevations is strongly encouraged. Merchant builders are encouraged to mix their product to provide a variety of garage placements relative to floor plan and site plan. By providing a mix of side facing or angled garage doors, garage doors set back further than living areas and garage doors that tie into courtyard entry portals, as well as by setting street facing garage doors back a minimum 18" into structures, this impact can be minimized. To encourage streetscape variety, side-facing garages may in some cases reduce front yard setbacks so as not to prohibit buildable square footage. Tandem (two deep) garages are encouraged so as to cut down on the number and width of garage doors facing the street. Front facing garage doors are encouraged to be single width and builders must strive to reduce driveway paving, including the use of 18' long driveways when allowed by the standards for certain lot sizes.

Garages that are not tandem or split, shall be a minimum size of 20'x20' (at least 20' deep) and are encouraged to be deeper to accommodate longer vehicles. All garages shall allow for the parking of at least two cars.

Mailboxes shall be ganged together and not on individual lots. Cluster box units similar to Florence "vogue" series should be used, location to be determined.

2.1.3 Building Elements

Building Form

The massing, articulation and proportion of homes within River Islands should be designed to reflect the interior uses and the specific architectural style. Attention to massing, articulation and proportion are not limited to the primary street elevation. Equal care should be given to any elevation that sides or backs onto an alley or street when that elevation is visible from the street or in public view. Particular attention should be given to ensuring that appropriate window openings are incorporated in these instances.

The design should focus on breaking the main façade of the home into three to four distinct elements: entry, main building mass, a single story element and the roof. The following guidelines will encourage greater massing variety:

Massing:

- ^ The upper level of a two or three-story home should step back min. 24" to reduce the scale of the front building façade facing the street, unless appropriate to a historical style. This can be achieved with a roofed porch provided all other criteria are met.
- ^ Two-story houses should have a single story element, e.g. porch, bay window or building projection closest to the front of the house and/or next to the street.
- ^ Varying front setbacks, addition of a defined entry courtyard and a covered porch will be encouraged to create architectural interest and diversity along residential street front.
- ^ Alleys are encouraged to promote pedestrian friendly streetscapes.



Roof Form and Slope

Roof form and slope are important design elements in creating a well-conceived streetscape.

- Roof treatments should be consistent with the architectural style of residential unit.
- A mix of single story, two story elements, and undulating planes, wall and garage plans. No two story flat walls more than two houses in a row.
- Variety of roof design and treatment is encouraged to provide visual diversity through the village neighborhoods by extensive use of gable, cross-gable, hip or a combination of these roof forms.
- When visible from a public space or street, repetitious gable ends framed side to side on rear elevations are not permitted along perimeter edges of residential neighborhoods.
- Vertical and horizontal roof articulations are strongly encouraged.

Roof Materials

Developments of residential neighborhoods within River Islands should have varying roof materials, such as concrete shake, Spanish tile or “architectural” grade composition shingles. Metal roofings are encouraged when appropriate to an architectural style.



2.1.4 Building Materials and Colors

Building materials and color are important elements to maintain the visual quality of homes within the neighborhoods of River Island at Lathrop. The use of traditional materials and colors should dominate throughout the residential neighborhoods.

- ^ Selection and application of architectural materials and details should relate well and be expressive of the architectural style of the residence.
- ^ Exterior materials and architectural details should be designed to appear as an integral part of the design.
- ^ Acceptable primary exterior building materials including brick, masonry, stucco, stone and wood, (or a high quality wood composite material, such as Hardie siding or similar.)
- ^ Secondary or accent materials should include real or cultured masonry materials (such as stone, brick and decorative block or tile), horizontal siding, and composite wood shingles, or composite shingles.
- ^ Material changes at the outside corners of structures provide the visual impression of thinness and artificiality. Materials should fully wrap around outside building corners to the next substantial change in wall planes or direction, i.e. at an inside corner, or fence line.
- ^ The color palette should be selected with the design intent of avoiding monotony while providing balanced variety of color schemes that further enhancing visual diversity. A minimum of 2 (3 preferred) color schemes per elevation style is required.
- ^ Homes shall have a minimum of 3 colors per elevation, for field (body), accent and trim locations. If 2 different siding materials are used, 2 different but complementary colors are highly encouraged. (Stone or masonry not included).
- ^ The same color schemes shall not be plotted next to each other.



2.1.5 Architectural Styles

For concept and inspiration, architectural tradition across many notable and well established residential neighborhoods in proximity to the City of Lathrop were surveyed and compiled to generate 5 representative heritage architectural styles recommended for the River Islands neighborhoods. These heritage architectural styles have proven to possess market appeal, and community acceptance when they are successfully executed and delivered by contemporary merchant home builders. Additionally, modern influenced styles have been added based on current buyers tastes. The architectural styles are categorized into three architectural groups. Each group represents a major residential stylistic development trend introduced in the Central Valley over the past decades. Builders may propose additional styles which can be added by administrative action.

Continental Influence

- American Traditional
- European Cottage
- Savannah



Western Regional Influence

- California Ranch
- Craftsman



Modern Influence

- California Modern
- Modern Farmhouse
- Spanish Eclectic
- Modern Prairie



More detailed descriptions of the nine representative building styles are presented on the following pages and are intended to guide the builders and developers in creating a quality and finesse to the housing units in the West Village District.



- 1) Window shutters
- 2) Centered front gable (pediment)
- 3) Entry porch
- 4) Elliptical fanlight over paneled door
- 5) Multi-paned windows with double hung sashes



American Traditional

The American Traditional, also known as Colonial Revival, is a nationalistic style. When “manifest destiny” was at its peak in the early 1890s, Americans began to value their own heritage and architecture. Colonial Revival sought to follow the style of the period around the Revolutionary War. Distinctive in this style are multiple columned porches and doors with fanlights and sidelights. The trend arrived in California soon after the turn of century in reaction to the excessive usage of the Queen Anne style at the time.

Exterior Features

American Traditional style features porticos, slender columns, restrained capitals and classical Greek moldings, and narrow clapboard siding is used to cover the exterior and trimmed with strong accent colored shutters.

American Traditional - (Detached Homes)

American Traditional design details

| Elements | Minimum | Enhanced |
|---------------|---|---|
| Form | -Symmetrical one- and two-story stacked massing -Simple plan form massing and simple roof design | |
| Roof | -Front to back dominant gable roof with one intersecting gable roof -Moderate pitched roof slope (5:12-9:12 slope) -Wide projecting eaves with exposed rafter tails, and decorative beams or braces added under the gables -Flat tile -Composition shingles of high quality | -Gambrel roof form |
| Walls | -Blend of stucco and siding at exterior finish -Used brick -Stucco sand, light lace, or medium dash finish | -Narrow clapboard, board/batten, wood shingles or siding as primary building material -Brick veneer wainscot -Decorative shingles -Stone or brick accent materials |
| Windows | -Symmetrical placement of windows on front elevation -Vertical, wood cased, multi-paned -Standardized, single hung windows | -Bay window as principal window on front elevation |
| Details | -Colonial detailing -Porticos with colonial detailing -Decorative attic vents -Door trim surround is simple and elegant | -Cornice gable-end trim -Doors with fan lights and side lights -Louver, plank, or panel shutters -Restrained moldings |
| Colors | -Off-white to light colors with contrasting trim and accent colors | |
| Outdoor Space | -Porch, 4'-6' minimum depth -Substantial portion of front elevation | |

Decorative gable vent & gable enhancement



Lap siding

Square columns

Entry porch

Shutters
Multi grid single housing windows



Lap siding

Shingle siding




Entry Porch Square columns Pickets

American Traditional/Design Element Kit of Parts


Roof types



Side



Cross



Gambrel

Posts, columns, and piers



Wood post with bracket



Wood post with corbel



Double wood posts



Round columns



Square column

Chimneys



Stucco



Stucco



Brick



Lap siding

Door shapes



Rectilinear



Flat arch

Door styles



Panel door



Panel door with glass



Single with divided lite

Window shapes



Rectangular



Round



Square

Window style



Single hung with mullions



Slider with mullions



Picture



Bay window

American Traditional/Design Element Kit of Parts

Window sills



Trim surround



Header and sill



Sill with corbels

Shutter designs



Louver



Panel



Plank

Eaves and fascia



Square rafter tails



Chamfered rafter tails



Corbel to fascia



Bracket to fascia



Cornice



Return at rake

Garage door styles



Framed panel



Framed panel w/ door lights




Carriage Door

Railing



Decorative



Straight picket



Turned picket

Detail elements



Ornamental light fixture



Louvered vent



Decorative gable detailing



Gamble dormer



Classical entry features



- 1) Dominant front facade with multiple, steeply pitched front gables
- 2) Massive chimneys crowned by decorative chimney pots
- 3) Multi-paned ribbon window
- 4) Recessed entry alcove



European Cottage

The European Cottage is a style that evolved out of Medieval Tudor and Norman architecture. The combination of these two architectural influences eventually translated into the popular English and French “Cottage” style homes that received further acceptance with the addition of stone and brick veneer details developed in the 1920s.

Exterior Features

This evolving architectural style is characterized by its steep roofs, that are usually side-gabled, and facades that are dominated by cross gables. The primary material is stucco with heavy use of stone and brick at bases, as are rounded doorways, multi-paned casement windows, large and elaborate chimney feature. Some of the most recognizable features for this style are the accent details in gable ends, sculptured swooping walls at the front elevation and tower or alcove element at the entry.

European Cottage - (Detached Homes)

| Elements | Minimum | Enhanced |
|---------------|--|--|
| Form | -Asymmetrical one- and two-stories -Rectangular plan form mass | -Varied plan shapes -Tower at entry |
| Roof | -Side-gabled, rarely hipped or front-gabled -Façade dominated by one or more cross gables -Steeply pitched roof -Gable roof overhang, 9"-24" eave -Architectural quality wood/ asphalt shingles, or smooth flat concrete tiles | -Sculptured swooping roofs -Steeply pitched roof: 8:12 to 12:12 and steeper |
| Walls | -Primary Walls: Stucco – sand, light lace, or medium dash finish | -Stucco – smooth finish -Use of stone & brick -Horizontal siding accents -Wood claddings on principal gables or upper stories |
| Windows | -Tall, narrow windows, usually in multiple groups and with multi-pane glazing -Typically casements of wood or metal or double hung sash windows | -Bay window as principal window on front elevation -Stone mullions to divide casements and transoms -Grouped in strings of three or more -Stone mullions to divide casements and transoms |
| Details | -Louver and panel shutters -Simple round-arched doorways with board-and batten doors -Small boxed eaves -Accent details at gable ends | -Elaborate chimney feature -Entry accents with real or faux stone -Decorative details -Partial porches with wood columns and railings |
| Colors | -Off-white and light tones with contrasting color accents/trim | |
| Outdoor Space | -Porches or enclosed front yards -5' minimum depth | |

European Cottage design details



Louvered vent

Entry accents with real or faux stone

Panel shutter design

Off-white and light tones with contrasting color accents/trim

Decorative gable-end detailing

Decorative wooden balcony



European Cottage/Design Element Kit of Parts


Roof types



Front



Side



Cross

Posts, columns, and piers



Wood post with bracket

Chimneys



Stucco



Brick



Stone

Door shapes



Rectilinear



Full arch



Flattened Arch

Door styles



Panel door



Panel door with glass



Single with divided light



Plank door



Plank door with glass

Window shapes



Rectangular



Square



Rectangular horizontally proportioned

Window styles



Single hung with mullions



Slider with mullions



Picture



Bay window



Multi-sash

European Cottage/Design Element Kit of Parts

Window sills



Trim surround



Sculptured stucco



Potsheff with corbels

Shutter designs



Louver



Panel



Plank

Eaves and fascia



Square eaves



Cornice

Garage door styles



Framed panel



Framed panel w/ door lights



Plank w/ door lights

Railing



Decorative



Straight pick& t



Turned pick& t

Detail elements



Ornamental light fixture



Brick surrounds



Louvered vent



Wood pot shelf



Decorative gable-end detailing



Entry tower



Decorative wooden balcony



- 1) Dominant decorated brick chimney
- 2) Wide hipped roof extends over porch
- 3) Wide wrap-around porch (galleries)
- 4) Wooden square column



Savannah

The Savannah, also known as Rural French Colonial, Tidewater or Plantation, typically refers to the two-story square-shaped home plan, which originated near Southern waterways. It is designed with a central entrance that leads to the traditional hall-and-parlor floor plan. Tidewater house plans, with their distinctive abundant windows and doors and large shade porches (galleries), were built for the Southern marshy climates.

Exterior Features

The Savannah style features symmetrical massing with dual-pitched hipped roofs and always lack interior hallways. Openings are placed solely for the convenience of the interior often with the rear range of rooms consisting of an open loggia with a small room at each end known as a cabinet.

Savannah - (Detached Homes)

| Elements | Minimum | Enhanced |
|---------------|--|--|
| Form | -Asymmetrical one- and two-story massing -Strong horizontal emphasis | |
| Roof | -Side-gabled or hip roofs -Modest to high pitched roof -Shallow or moderate eave overhangs (3" - 18") | -Dual-pitched hipped roof -Concrete shake roof tiles -Metal roofs -Flat composite roofs |
| Walls | -Clapboard, wood shingles or siding | Accent material -Brick |
| Windows | -Multi-paned windows -Double-hung casement, sliding and picture windows | -Bands of vertically-proportioned windows tied together with continuous head and or sill trim |
| Details | -Front porch supported by square hood columns -Full porches and second story balconies -Shallow-molded, unadorned cornice on front facade -Single posts should be a minimum 6x6 dimension | -Dormers -Featured cornice with decorative moldings -Paired columns -Triple grouped columns at corners of porches |
| Colors | Light to medium earth tone colors with contrasting trim and accent colors | |
| Outdoor Space | -Wide porch/balcony, 5' minimum depth | |

Savannah design details



Brick chimney

Square windows

Square Column



Single hung windows with mullions

Straight picket railing

Rectilinear panel door



Wood shingles


Square Column

Savannah/Design Element Kit of Parts

Roof types



Side



Hip

Posts, columns, and piers



Double wide wood posts



Double wood posts



Square Column

Chimneys



Stucco



Brick



Lap siding

Door shapes



Rectilinear

Door styles



Panel door



Panel door with glass



Single with divided light

Window shapes



Rectangular



Round



Square

Window styles



Single hung with mullions



Slider with mullions



Picture



Multi-sash

Savannah/Design Element Kit of Parts

Window sills



Trim surround



Header and sill

Shutter designs



Louver



Panel

Eaves and fascia



Square rafter tails



Chamfered rafter tails



Cornice



Cornice

Garage door styles



Framed panel



Framed panel w/ door lights




Carriage Door

Railing



Cut out panels



Straight picket



Turned picket

Detail elements



Ornamental light fixture



Louvered vent



- 1) Low pitched cross-gabled roof with wide eave overhang
- 2) Partial width porch
- 3) Enclosed entry courtyard



California Ranch

The Ranch style was originated in the mid-1930s by several creative California architects. It gained in popularity during the 1940s to become the dominant style throughout the country. The style is loosely based on early Spanish Colonial precedents of the American southwest, modified by influences borrowed from Craftsman and Prairie modernism of the early 20th Century.

Exterior Features

Asymmetrical one-story shapes with low-pitched roofs dominate. Moderate or wide eave overhangs with exposed rafters, along with built-in garage, wood or brick exterior walls, sliding and picture windows, and sliding doors leading to patios are the characteristics for the California Ranch style.

California Ranch - (Detached Homes)

California Ranch design details

| Elements | Minimum | Enhanced |
|---------------|---|---|
| Form | -Asymmetrical one- and two-story massing -Strong horizontal emphasis | -Single story massing |
| Roof | -Front to back gable or hip with intersecting hip or gable roofs -Low to moderate pitched roof (3:12 - 5:12) -Moderate or wide eave overhangs with exposed rafters 12" - 30" -Flat concrete tile to simulate shake or split shake high quality composition shingle | -Lower pitched main roof or porch: 3:12 – 4:12 -Wide eave overhangs (18"~24") with exposed rafters -Concrete shake roof tiles |
| Walls | -Stucco with Clapboard, Wood Shingles or Siding -Stucco sand, light lace, or medium dash finish | -Clapboard, wood shingles, or siding as primary material -Use of stone and brick -Stone or brick accent materials |
| Windows | -Vertical multi-paned double hung casement windows -Multi-paned windows -Sliding and picture windows | -Bay window as principal window on front elevation -Round top accent or bay windows |
| Details | -The entry should be covered by porch -Front porch supported by square wood columns with trim -Full porches and balconies -Wood porches with classic square railings -Simplified cornice trim at gable ends | -Wide porch with decorative columns and trim -Entry doors will have side-lights, basic geometric patterns, and or multi paned windows with wood trim surround -Enhanced sills and louvered shutters |
| Colors | -Light to medium earth tone colors with contrasting trim and accent colors | |
| Outdoor Space | -Wide porch, 5' minimum depth | |



Stone surround
Panel door with glass
Straight picket railing



Single hung windows with mullions
Wood post with bracket
Brick accent material



Low pitched roof

Bay window

California Ranch/Design Element Kit of Parts


Roof types



Front



Side



Hip



Cross

Posts, columns, and piers



Wood post with bracket



Double wood posts



Wood post with corbel

Chimneys



Stucco



Stucco



Brick



Lap siding

Door shapes



Rectilinear

Door styles



Panel door



Panel door with glass



Single with divided light

Window shapes



Rectangular



Square



Rectangular horizontally proportioned

California Ranch/Design Element Kit of Parts

Window styles



Single hung with mullions



Slider with mullions



Picture



Bay window



Multi-sash

Window sills



Trim surround



Header and sill



Sill with corbels

Shutter designs



Louver



Panel



Plank

Eaves and fascia



Square rafter tails



Chamfered rafter tails



Quarter round rafter tails



Shaped rafter tails



Bracket to fascia

Garage door styles



Framed panel



Framed panel w/ door lights



Carriage Door

Railing



Cut out panels



Straight picket



Turned picket

Detail elements



Ornamental light fixture



Louvered vent



- 1) Low-pitched gabled roof with wide, unenclosed eave overhang
- 2) Full width entry porch with square tapered column support
- 3) Decorative (false) triangular knee brace under gable
- 4) Exposed roof rafter tails
- 5) Battered or tapered columns



Craftsman

The Craftsman style was inspired by the English Arts and Crafts movement of the late 19th Century, and is considered native to the California architectural tradition with notable early contribution by architects such as Greene and Greene and Bernard Maybeck.

Exterior Features

The physical character is dominated by its low-pitched, gabled roof with wide, unenclosed eave overhang. In addition, the style features exposed roof rafters and decorative beams or braces commonly added under gables. Large porches with distinctive supporting columns that extend across the entire front of the house along with extensive use of natural materials (wood and stones) are all defining features of the Craftsman style.

Craftsman - (Detached Homes)

| Elements | Minimum | Enhanced |
|---------------|---|--|
| Form | -Asymmetrical one- and two-story boxy forms -Low lines with simple wide projecting roofs | -Horizontal forms through boxed massing with vertical and horizontal offsets |
| Roof | -Low-pitched gable roofs, rarely hipped PITCH -Low pitched roof slopes (3:12 - 5:12) -Wide projecting eaves with exposed rafter tails, and decorative beams or braces added under the gables (12"-30") -Flat concrete tile -Composition shingles of high quality | -Varied porch roofs: shed or gabled -Minimum Overhang: 18" -Concrete shakes |
| Walls | -Blend of stucco and siding at exterior finish -Stucco sand, light lace, or medium dash finish | -Clapboard, board/batten, wood shingles or siding as primary building material -River rock stone or brick accent materials |
| Windows | -Simple double-hung casement windows -Large front windows, often in 3 parts -Typically, multi-paned upper sash with single pane below | -Bands of vertically-proportioned windows tied together with continuous head and or sill trim |
| Details | -Exposed structural elements -Prominent front porch with columns and gabled roof element -Wide projecting eaves, decorative beams, or added braces under gables -Strong header and sill with beams or braces under sill -Exposed eaves and rafter tails | -Heavy square or tapered columns resting on stone or brick piers -Arts and Crafts style lighting fixtures -"Dormers" with shed or gable roof |
| Colors | -Light to medium earth tone colors with contrasting trim and accent colors | |
| Outdoor Space | -Wide porch, 5' minimum depth | |

Craftsman design details

Stucco chimney

Sill with corbels

Decorative gable
-end portal



Decorative gable
-end detailing

Single hung with
mullions



Knee brace



Panel door

Craftsman/Design Element Kit of Parts


Roof types



Front



Side



Hip



Cross

Posts, columns, and piers



Wood post with bracket



Double wood posts



Battered columns



Corbel



Knee brace

Chimneys



Stucco



Stucco



Stone



Brick



Lap siding

Door shapes



Rectilinear

Door styles



Panel door



Panel door with glass



Single with divided light



Plank door



Plank door with glass

Window shapes



Square

Craftsman/Design Element Kit of Parts

Window styles



Single hung with mullions



Slider with mullions



Picture



Shaped Tails



Multi-sash



Awning

Garage door styles



Framed panel



Framed panel w/ door lights



Carriage Door

Window sills



Trim surround



Header and sill



Sill with corbels

Railing



Decorative



Straight picket

Shutter designs



Louver



Panel



Plank

Detail elements



Ornamental light fixture



Decorative gable-end detailing



Decorative gable-end portal

Eaves and fascia



Square rafter tails



Chamfered rafter tails



Quarter round rafter tails



- 1) Mix of shed, hipped or gable roofs
- 2) Mix of stucco, wood and stone siding
- 3) Horizontal lines
- 4) Clean detailing



California Modern

As the economy continues to bounce back, Contemporary styled homes continue to grow in popularity. California Modern homes take traditional styles and contemporize the shapes, massing and details, which often appeals to a younger demographic of homeowner. Simple detailing and careful selection of low maintenance materials characterize this style.

Exterior Features

Sculptural forms can include smooth surfaces, shifted volumes, and projecting cantilevers. Floor-to-ceiling windows and an array of square openings placed throughout the façade present straightforward geometry. Retractable shutter panels provide ways to both shade interiors from daylight while maintaining a cutting-edge look. A mix of roof styles can include hip, gable, and sloping shed. A mix of stucco and wood, horizontal lines with contrasting vertical towers or elements and distinct design elements such as sunshades add to the new geometry of the California Modern home.

California Modern - (Detached Homes)

| Elements | Minimum | Enhanced |
|---------------|--|---|
| Form | -Asymmetrical one- and two-story boxy forms -Low lines with simple wide projecting roofs | -Horizontal character through the use of boxed massing with vertical and horizontal offsets |
| Roof | -Low-pitched hipped roofs, low & steep pitched gables, shed form -A mix of low and steep-pitched roof slopes (3:12 - 5:12) & (8:12 - 10:12) -Wide eaves with enclosed rafter tails, decorative beams/braces under gables (12"-30") -Flat concrete tile -Composition shingles of high quality | -Varied porch roofs: shed or gabled -Minimum Overhang: 18" -Concrete shakes -Composition shingle with shadow relief |
| Walls | -Stucco and siding at exterior finish -Stucco sand, light lace, or medium dash finish -Horizontal siding and panel systems | -Stucco, clapboard, board/batten, wood shingles or siding -Horizontal stone |
| Windows | -Double-hung casement windows -Large front windows, often divided -Square windows, minimal breakups | -Vertically-proportioned windows tied together with continuous head or sill trim -Storefront windows -Stacking window walls |
| Details | -Prominent front porch with columns and gabled roof element -Wide projecting eaves, decorative beams, or added braces under gables -Strong header and sill with beams or braces under sill -Enclosed eaves and rafter tails -Use of Horizontal stone columns - sometimes spanning 1 - 1/2 stories. | -Heavy square or tapered columns resting on horizontal stone -Contemporary lighting fixtures |
| Colors | -Light to medium earth tone colors with contrasting trim and accent colors, bold base colors, multi colored | |
| Outdoor Space | -Wide porch, 5' minimum depth | |

California Modern design details



California Modern / Design Element Kit of Parts

Roof types




Shed



Shed



Side



Hip



Cross

Posts, columns, and piers



Round columns



Square Columns

Door styles



Panel door



Single with glass



Panel door with side lights



Panel door with glass and side lights

Eaves and fascia



Enclosed Eaves



Enclosed Eaves

California Modern / Design Element Kit of Parts

Window styles



Multi sash (Fixed or arching)



Multi paned



Picture



Plate glass



Square



Window wall with stacking doors

Exterior Lighting



Ornamental light fixture



Ornamental light fixture



Ornamental light fixture

Garage door styles



Framed panel with door lights



Framed panel w/ door lights



Framed panel w/ door lights

Railing



Tube Steel



Straight picket



Cable railing



Vertical Picket



- 1) Mix of shed, hipped or gable roofs
- 2) Mix of stucco, wood and stone siding
- 3) Vertical lines
- 4) Clean detailing



Modern Farmhouse

The Modern Farmhouse style is a contemporary interpretation of the traditional farmhouse that incorporates classic farmhouse elements such as gable end roofs, strong vertical lines, and a sense of overall symmetry and puts a contemporary spin on them for a more streamlined modern feel. Modern Farmhouse homes are simply framed and rectangular in shape, with the most recognizable characteristic being the gable roof, typically with a 12:12 pitch. The steep pitch emphasizes the height of the house, and sets the tone for strong vertical lines.

Exterior Features

Most Modern Farmhouse-styled homes are two-story buildings with symmetrical arrangement of parts, with entrance at the center and typically a strong vertical element capped with a gable roof. A short set of wide steps leads from the sidewalk to the porch at the front entrance. The two main exterior siding materials commonly found on Modern Farmhouse styles are lap, and board and batten. Shutters commonly found on the traditional farmhouse are typically replaced with horizontal working barn door style shutters.

Modern Farmhouse - (Detached Homes)

| Elements | Minimum | Enhanced |
|---------------|---|---|
| Form | -Simple plan form massing and roof shape | |
| Roof | -6:12 to 12:12 roof pitch -Front-to-back main gable roof -12" minimum overhangs -Smooth, flat concrete tiles or high-quality composition singles -Standing seam material | -Main gable roof with one or two intersecting gable roofs -16" minimum overhangs |
| Walls | -Blend of siding, stone and stucco -Stucco sand, light lace, or medium dash finish | -Full-wrapped horizontal siding, board-and batten or fine-sand finish stucco |
| Windows | -Vertical, multi-lined windows at front elevations | -Built-up header trims at front windows |
| Details | -Porches with simple wood columns and wood railings. -Stucco finished or horizontal siding-wrapped chimney, if applicable -Complementary garage door patterns -Barn door style shutters -Wood columns shall be doubled (or tripled at corners) or 6" min. dimension | -Shaped-wood columns with brackets and knee braces -Wood pot shelves -Gable or hip dormers at front elevation -Doors with fan-lights and side lite windows |
| Colors | -Light to medium colors with contrasting trim and accent colors | |
| Outdoor Space | - Wide porch: Minimum 6' in depth | |

Modern Farmhouse design details

Enclosed eaves

Square columns

Panel door with glass



Ornamental light fixture

Panel shutter



Single hung window

Light to medium colors with contrasting trim and accent



Modern Farmhouse / Design Element Kit of Parts

Roof types



Front



Shed



Side



Cross

Posts, columns, and piers



Round columns



Square Columns

Door styles



Panel door



Barn door



Single with glass



Panel door with side lights



Panel door with glass and side lights

Eaves and fascia



Enclosed Eaves



Enclosed Eaves

Modern Farmhouse / Design Element Kit of Parts

Window styles



Multi sash (Fixed or arching)



Multi paned



Picture



Plate glass



Square



Window wall with stacking doors

Exterior Lighting



Ornamental light fixture



Ornamental light fixture



Ornamental light fixture

Garage door styles



Framed panel with door lights



Framed panel w/ door lights



Framed panel w/ door lights



Carriage Door

Railing



Tube Steel



Straight picket



Cable railing



Vertical Picket



- 1) Arched entrance
2. Tiled roof material
- 3) Use of window shutters
- 4) Spanish vent element



Spanish Eclectic

The Spanish Eclectic style is a modern interpretation of the traditional Spanish style that incorporates classic Spanish elements such as arched walls, tile roofs, along with a mix of contemporary elements from other styles to create a more modern feel. Spanish Eclectic homes have clean lines, can be one or two story, utilizing muted earth tone color schemes.



Exterior Features

Most Spanish Eclectic-styled homes are two-story buildings with asymmetrical arrangement of parts, often with the entrance to one side of the front elevation or with the front door angled away from the rest of the front elevation wall. A mix of exterior materials can be used, including stucco, stone veneer, lap or horizontal siding, and/or board and batten. Shutters usually not found on other Spanish styles are commonly found with the Spanish Eclectic-styled homes.

Spanish Eclectic - Detached homes

| Elements | Minimum | Enhanced |
|---------------|--|------------------------------------|
| Form | Asymmetrical form with rustic details and flared wall accents | |
| Roof | -Front to back gable or hip with intersecting hip or gable roofs -Low to moderate pitched roof (3:12 - 5:12) - Moderate or zero overhang -S or villa style roof tiles | Medium 12" overhang, exposed eaves |
| Walls | Stucco with with foam trim, arched openings, and flared accents at gable or massing | |
| Windows | Slider, fixed or single hung windows | Window grids and recessed massing |
| Details | Enhanced window trim at projecting building massing. Flared foam trim at gable ends and at covered porches | |
| Colors | -Light to medium earth tone colors with contrasting trim and accent colors | |
| Outdoor Space | 15' minimum open space | |

Spanish Eclectic Design Images



Spanish Eclectic - Design Element/Kit of parts


Roof types



Front



Side



Hip



Cross

Posts, columns, and piers



Wood post with bracket



Double wood posts



Wood post with corbel



Stucco columns



Brick



Lap siding

Chimneys

Door shapes and styles



Rectilinear



Panel door



Glazed panel door


Window shapes



Rectangular



Square



Arched

Garage door styles



Louvered shutter



Light fixture



Flared eave



Tile Vents



- 1) Low pitched hip roof structure
- 2) Strong stone accent material
- 3) Deep overhang at entry
- 4) Strong contrasting accent color to house body



Modern Prairie

Modern Prairie is a mid-American architectural style that features low-pitched hipped roofs with deep overhangs, low but strong horizontal lines, and bands of windows. Natural materials are emphasized in the exterior elevation.

Exterior Elements

The Modern Prairie style features nearly symmetrical massing with low-pitched hipped roofs. While stucco is the primary exterior material, strong accents with stone, masonry and wood styled siding are utilized and sometimes mixed. Glazing is typically single hung windows, but picture/fixes and sliding windows can also be utilized. Neutral tones are preferred for exterior color with use of bolder accent color for contrast.

Modern Prairie - (Detached Homes)


| Elements | Minimum | Enhanced |
|---------------|--|---|
| Form | - Single story form with emphasis on horizontal linear massing and slender vertical columns in accent stone or brick | |
| Roof | - Low slope hip roof ranging from 3:12 to 4:12 with deep overhangs | - 12"-16" overhangs |
| Walls | - Stucco with stone wainscoting and accent material on columns | - Use of stone and siding as accent materials |
| Windows | -Slider, fixed or single hung windows | - Grids in selected locations |
| Details | - Prominent use of stone or brick columns and horizontal trim lines - Modern paneled entry doors | |
| Colors | - Neutral tones with bold contrasting colors | |
| Outdoor Space | - Porch, minimum 5' in depth | |

Modern Prairie Design Element Kit of Parts

Roof types



Hip



Shed



Side

Door styles



Panel door

Posts, columns, and piers



Masonry columns

Detail elements



Ornamental light fixture

Garage door style



Modern panels with side lights

Window styles



Trim surround

2.2 Development Standards


The non-active adult units of the West Village District include Villages 1 through 3 and adjacent areas. It does not include the active adult neighborhoods that are covered in a separate document previously approved by the City. It also includes Villages 30-32 that include multi-family housing.

The numerical and dimensional development standards necessary to regulate housing for the non-active adult housing and multi-family housing associated with West Village are summarized in Table 2.1 Summary of River Islands Architectural Standards.

The summary is supplemented with more detailed development standards for each Architectural land use designation in illustrative lot diagrams based on various lot sizes. Yard-street relationships, lot design, setbacks and building height are covered in detail. The City, based on recommendation of the STDRC shall have the authority to accept, review and grant any minor architectural variance on a case document so long as such variances are not in direct conflict with this document or the UDC.



Figure 2.1 The West Village Illustrative Plan



LEGEND

- ENHANCED ARCHITECTURAL ELEVATION LOCATIONS

Enhanced architectural elevations are side and/or rear elevations that are in more visible locations to the general area, including lakes, major streets, and near levees. Additional architectural elements, such as enhanced trim, window treatments, wainscoting, and similar items will likely be required by designers. Note that multi-family projects (e.g. condo, apartments and attached single family) make take special consideration due to unique nature of each project.

Since the design and construction of all public schools in California are governed by State agencies, the proposed high school will not be reviewed by the STDRC and is not subject to a City building permit.

Figure 2.2 The West Village District Enhanced Architectural Elevation Location Map (Non-Active Adult Product)

Lotting Summary








| AREA | VILLAGE | PRODUCT TYPE | Units |
|---|------------|----------------|-------|
|  | VILLAGE 1 | 50' x 100' | 68 |
|  | VILLAGE 2 | MEDIUM DENSITY | 192 |
|  | VILLAGE 3 | HIGH DENSITY | 312 |
|  | VILLAGE 24 | MEDIUM DENSITY | 273 |
|  | VILLAGE 30 | MEDIUM DENSITY | 44 |
|  | VILLAGE 31 | HIGH DENSITY | 185 |
|  | VILLAGE 32 | HIGH DENSITY | 201 |



Figure 2.3 Lot Sizes Diagram - West Village District (Non-Active Adult)

2.2.1 Low Density Architectural (LDR) Development Standards - West Village Non-Active Adult

The LDR land use designation is intended to provide a wide range of single family detached housing products, however, only 50'x100' product is proposed in the West Village District for non-active adult units. The permitted density range for this category is between 3~9 dwellings per acre (du/ac). Lot sizes for this District shall be 5,000 s.f.

| Land Use Designation: Low Density Residential Front Loaded Lots | |
|---|-----------------|
| Lot Size: | 50 x 100 Lots |
| Setbacks (Minimum) | |
| Front Yard @ street | |
| Living Space (First/Second Story) | (15'/20') |
| Porch (6' min. clear depth) | 12' |
| Garage Front Facing (Door) | 20' |
| Side-Entry Garage Wall ⁽³⁾ | Not Allowed |
| Front Courtyard walls | 10' |
| Side-Entry Garage Conversion | Not Allowed |
| Side Yard | |
| Living Space (Interior Property Line) ⁽⁴⁾ | 5' |
| Living Space (Corner Property Line) | 10' |
| Wrap Around Porch (Corner) | 7' |
| Detached Garages | 5' |
| Rear Yard | |
| Living Space (Min./Ave) ⁽¹⁾ | (15'/20') |
| Front Entry Attached/Detached | N/A |
| Garages ⁽²⁾ | N/A |
| Garages with Rear Access | N/A |
| Patio Covers/CA Rooms (1 Story Height) ⁶ | 10' min. |
| Height (Maximum to Ridge Line) | |
| Primary Dwelling | 35' (2 Stories) |
| Detached Garage | N/A |
| Detached Garage/Accessory Unit | N/A |
| Parking | |
| Resident (Garage) | 2 Cars min. |
| Guest (Apron) | 2 Min. |
| Building Coverage | 55% |

Notes:

1. Minimum rear setback may be for only 1/2 width of the allowed house width.
2. Front entry garages located in rear of lot limited to 22' in width
3. Single story only; facades shall have enhanced architectural elements.
4. Front, side, rear and street side yard setbacks may be reduced and lot coverage increased for single story units at STDRC recommendation to encourage single story units. To be considered for these exceptions, the product must demonstrate reduced massing from other units in the subdivision, create a diverse front yard streetscape by varying setbacks and encourage living space of the unit to be forward of the garage. Under no circumstance shall an exception be granted that allows encroachment into a public utility easement.
5. See Appendix for accessory structure standards.
6. Two story patio covers/California Rooms (a.k.a. "sleeper porches") may be placed within a 10' rear yard setback when the rear yard is adjacent to open space, a lake, or is otherwise not adjacent to another residential lot.

2.2.2 Medium Density Architectural (MDR) Development Standards

The MDR land use designation is intended to provide a denser attached single family or multi-family housing products. The permitted density range for this category is 6 to 14 units per acre.

| Lot Sizes: | Four Packs | Four Packs + ADUs | Six and Eight Packs - Alt. 1 | Six and Eight Packs - Alt. 2 | Bungalows |
|---------------------------------------|--------------------|--------------------|------------------------------|------------------------------|--------------------|
| Setbacks (Minimum) | | | | | |
| Front Yard @ Street | | | | | |
| Living Space (First/Second Story) | (10'/14') | (10'/10') | (10'/10') | (10'/10') | (10'/10') |
| Porch (5' min. clear depth) | 10' | 5' | 5' | 5' | 6' |
| Garage Front Facing (Door) | 18' | 18' | 18' | 18' | N/A |
| Side-Entry Garage Wall | N/A | N/A | N/A | N/A | N/A |
| Front Courtyard walls | N/A | N/A | N/A | N/A | N/A |
| Front walls (Private Street) | N/A | N/A | N/A | N/A | 3' |
| Front Yard @ Private Street | | | | | |
| Living Space (First/Second Story) | 7'/10' | 7'/10' | 7'/10' | 5'/5' | 5'/5' |
| Porch (5' min. clear depth) | 4' | 3' | 3' | 5' | 6' |
| Garage Front Facing (Door) | 18' | 18' | 18' | 5' | N/A |
| Side-Entry Garage Wall | N/A | N/A | N/A | N/A | 5' |
| Side Yard | | | | | |
| Living Space (Interior Property Line) | 4' | 4' | 4' | 4' | 4' |
| Living Space (Corner Property Line) | N/A | N/A | N/A | N/A | N/A |
| Detached Garages | N/A | N/A | N/A | N/A | N/A |
| Street Side Yard | 10' | 10' | 10' | 10' | N/A |
| Rear Yard | | | | | |
| Living Space (Min./Ave) | 10'/10' | 10'/10' | 10'/10' | 10'/10' | 10'/10' |
| Front Entry Attached/Detached Garages | N/A | N/A | N/A | N/A | 3' |
| Garages with Rear Access (Apron) | N/A | N/A | N/A | N/A | N/A |
| Patio Covers (1 Story Height) | N/A | N/A | N/A | N/A | N/A |
| Paseo Walk | | | | | |
| Living Space (to enter of Paseo) | N/A | N/A | N/A | N/A | N/A |
| Porch (to center of Paseo) | N/A | N/A | N/A | N/A | N/A |
| Alley / Private Drive | | | | | |
| Garage (door) | 18' | 18' | 18' | 5' | 3' |
| Garage (to center of Private Drive) | N/A | N/A | N/A | N/A | 14' |
| Porch | 5' | 4' | 4' | 5' | 5' |
| Height (Maximum to Ridge Line) | | | | | |
| Primary Dwelling | 35' (2 Stories) | 35' (2 Stories) | 35' (2 Stories) | 35' (2 Stories) | 35' (2 Stories) |
| Detached Garage/Accessory Unit | N/A | N/A | N/A | N/A | N/A |
| Parking | | | | | |
| Resident (Garage) | 2 Cars min. | 2 Cars min. | 2 Cars min. | 2 Cars min. | 2 Cars min. |
| Guest (Apron or Off-Site) | 0.25 cars per unit | 0.25 cars per unit | 0.25 cars per unit | 0.25 cars per unit | 0.25 cars per unit |
| Building Coverage | N/A | N/A | N/A | N/A | N/A |

Table 2.1 Summary of West Village Non-Active Adult Development Standards (Continued)

2.2.3 High Density Residential Development Standards

The HDR land use designation is intended to provide housing products for sale (condominiums) and for rent (apartments). Since each HDR site varies in size and shape, layouts for these units will vary, with units being 2 to 4 stories. The permitted density range for HDR is 15-40 dwellings per acre (du/ac). Architectural themes for high density product may range from any permitted style provided in this document. Since each building site is individualized, specific development standards will be provided with each proposed project. The guidelines below are general, to be applied each project on a case by case basis:

1. Design buildings to be respectful of adjacent buildings, and create transitions of appropriate height and scale.
2. Locate the taller portions of projects away from adjoining smaller properties in order to provide height transitions between taller and lower buildings, and to maximize light, air, and privacy for units.

Building Form

1. Design projects to avoid large box-like forms with continuous unrelieved surfaces.
2. Include articulation at a minimum along the public and private street frontage, and project side and rear yards, such that the bulk of the structure as seen from existing neighbors is reduced.
3. Minimize the bulk of the buildings by limiting building length, or designing buildings with two or more of the following special features to break up building bulk, including:
 - o Horizontal and vertical setbacks and stepbacks (instead of a long flat wall).
 - o Changes in roof form and height.
 - o Major full-height recesses (typically at least 10 feet deep) along the length of the building that successfully break the building into smaller discrete masses.

Building Orientation, Entrances, and Street Facing Facades

1. Design the street-facing façade of buildings to orient towards the public street, or private street if lot does not abut public street. Incorporate building articulation elements (such as cornices, brackets, overhangs, shutters, window boxes, etc.), and extensive landscaping to create an attractive street appearance that enhances the surrounding neighborhood.
2. Locate the primary front entrance of building units to face public, or private streets if lot does not abut public street.
3. In areas where the prevailing character is single-family detached development, design the public street facing facade to “read” like single dwelling units, including varying the design treatment for individual units to be complementary to the architecture of the neighborhood.

Table 2.2 Summary of High Density Residential Development Standards


| | |
|---|------|
| Setbacks (minimum) | |
| At Arterial/Collector Streets | 10' |
| At Local/Minor Streets | 5' |
| At Levee/Lake Slopes/Open Space | 20' |
| Building Height (maximum) | |
| Five Stories or more ¹ | 125' |
| At Four Stories | 60' |
| At Three Stories or less | 40' |
| Building Coverage (maximum) ² | 50% |

| | |
|--------------------------------|-----------------------------|
| Building Site (minimum) | 20,000 s.f. |
| Lot Width (minimum) | 100' |
| Lot Frontage (minimum) | 100' |
| Parking | 1.7 parking spaces per unit |

1. Structures above 60 feet in height are typically steel/concrete or steel framed. Such structures may require special review and approval from the Building Department and Fire District.
2. Exceptions to building coverage may be granted on a case by case basis upon recommendation of the STDRC and approval of the Planning Commission.

Table 2.3 Low Density Architectural (LDR) - 50 x 100 Lots


| Setbacks (minimum) | |
|--|-------------|
| Front Yard | |
| Living Space (First/Second Story) | (15'/20') |
| Porch (5' min. Clear Depth) | 12' |
| Garage Front Facing (Door) | 20' |
| Side-Entry Garage Wall ⁽³⁾ | Not Allowed |
| Side-Entry Garage Conversion ⁽³⁾ | 10' |
| Front Courtyard walls | 10' |
| Side Yard | |
| Living Space (Interior Property Line) | 5' |
| Living Space (Corner Property Line) | 10' |
| Wrap Around Porch (Corner) | 7' |
| Detached Garages/Accessory Unit | 5' |
| Rear Yard | |
| Living Space (Min./Ave.) ⁽¹⁾ | (15'/20') |
| Front Entry Attached/Detached Garages ⁽²⁾ | N/A |
| Garages with Rear Access | N/A |
| California Rooms/Patio Covers (1 Story Height) | 10' min |
| Building Coverage | 55% |



Dimensions shown are for example purpose only
See table above for setbacks

Table 2.4 Medium Density Architectural (MDR) - Courtyard - "Four Packs"

| Setbacks (Minimum) | | Setbacks (Minimum) | | Setbacks (Minimum) | |
|------------------------------------|-----------|---------------------------------------|---------|---------------------------------------|-----------------|
| Front Yard @ Street | | Side Yard | | Alley / Private Drive | |
| Living Space (First/Second Story) | (10'/14') | Living Space (Interior Property Line) | 4' | Garage (door) | 18' |
| Porch (5' min. clear depth) | 10' | Living Space (Corner Property Line) | N/A | Garage (to center of Private Drive) | N/A |
| Garage Front Facing (Door) | 18' | Wrap Around Porch (Corner) | N/A | Porch | 5' |
| Side-Entry Garage Wall | N/A | Detached Garages | N/A | Height (Maximum to Ridge Line) | |
| Front Courtyard walls | N/A | Street Side Yard | 10' | Primary Dwelling | 35' (2 Stories) |
| Front Yard @ Private Street | | Rear Yard | | Detached Garage | N/A |
| Living Space (First/Second Story) | (7'/10') | Living Space (Min./Ave) | 10'/10' | Parking | |
| Porch (5' min. clear depth) | 4' | Front Entry Attached/Detached Garages | N/A | Residence (Garage) | 2 cars min. |
| Garage Front Facing (Door) | 18' | Garages with Rear Access | N/A | Guest (Apron) | N/A |
| Side-Entry Garage Wall | N/A | Patio Covers (1 Story Height) | N/A | Building Coverage | |
| | | | | | N/A |



Not To Scale


Dimensions shown are for example purpose only
See table above for setbacks

Table 2.5 Medium Density Architectural (MDR) - Courtyard - "Four Pack ADU"

| Setbacks (Minimum) | |
|------------------------------------|-----------|
| Front Yard @ Street | |
| Living Space (First/Second Story) | (10'/10') |
| Porch (5' min. clear depth) | 5' |
| Garage Front Facing (Door) | 18' |
| Side-Entry Garage Wall | N/A |
| Front Courtyard walls | N/A |
| Front Yard @ Private Street | |
| Living Space (First/Second Story) | (7'/10') |
| Porch (5' min. clear depth) | 3' |
| Garage Front Facing (Door) | 18' |
| Side-Entry Garage Wall | N/A |

| Setbacks (Minimum) | |
|---------------------------------------|---------|
| Side Yard | |
| Living Space (Interior Property Line) | 4' |
| Living Space (Corner Property Line) | N/A |
| Wrap Around Porch (Corner) | N/A |
| Detached Garages | N/A |
| Street Side Yard | 10' |
| Rear Yard | |
| Living Space (Min./Ave) | 10'/10' |
| Front Entry Attached/Detached Garages | N/A |
| Garages with Rear Access | N/A |
| Patio Covers (1 Story Height) | N/A |


| Setbacks (Minimum) | |
|---------------------------------------|-----------------|
| Alley / Private Drive | |
| Garage (door) | 18' |
| Garage (to center of Private Drive) | N/A |
| Porch | 4' |
| Height (Maximum to Ridge Line) | |
| Primary Dwelling | 35' (2 Stories) |
| Detached Garage | N/A |
| Parking | |
| Residence (Garage) | 2 cars min. |
| Guest (Apron) | N/A |
| Building Coverage | |
| | N/A |



Dimensions shown are for example purpose only
See table above for setbacks

Table 2.6 Medium Density Architectural (MDR) - Courtyard - "Six and Eight Packs" - Alternative One

| Setbacks (Minimum) | | Setbacks (Minimum) | | Setbacks (Minimum) | |
|------------------------------------|-----------|---------------------------------------|---------|---------------------------------------|-----------------|
| Front Yard @ Street | | Side Yard | | Alley / Private Drive | |
| Living Space (First/Second Story) | (10'/10') | Living Space (Interior Property Line) | 4' | Garage (door) | 18' |
| Porch (5' min. clear depth) | 5' | Living Space (Corner Property Line) | N/A | Garage (to center of Private Drive) | N/A |
| Garage Front Facing (Door) | 18' | Wrap Around Porch (Corner) | N/A | Porch | 4' |
| Side-Entry Garage Wall | N/A | Detached Garages | N/A | Height (Maximum to Ridge Line) | |
| Front Courtyard walls | N/A | Street Side Yard | 10' | Primary Dwelling | 35' (2 Stories) |
| Front Yard @ Private Street | | Rear Yard | | Detached Garage | N/A |
| Living Space (First/Second Story) | (7'/10') | Living Space (Min./Ave) | 10'/10' | Parking | |
| Porch (5' min. clear depth) | 3' | Front Entry Attached/Detached Garages | N/A | Residence (Garage) | 2 cars min. |
| Garage Front Facing (Door) | 18' | Garages with Rear Access | N/A | Guest (Apron) | N/A |
| Side-Entry Garage Wall | N/A | Patio Covers (1 Story Height) | N/A | Building Coverage | |
| | | | | | N/A |



Dimensions shown are for example purpose only
See table above for setbacks



Table 2.7 Medium Density Architectural (MDR) - Courtyard - "Six and Eight Packs" - Alternative Two

| Setbacks (Minimum) | |
|------------------------------------|-----------|
| Front Yard @ Public Street | |
| Living Space (First/Second Story) | (10'/10') |
| Porch (5' min. clear depth) | 5' |
| Garage Front Facing (Door) | 18' |
| Side-Entry Garage Wall | N/A |
| Front Courtyard walls | N/A |
| Front Yard @ Private Street | |
| Living Space (First/Second Story) | (5'/5') |
| Porch (5' min. clear depth) | 5' |
| Garage Front Facing (Door) | 5' |
| Side-Entry Garage Wall | N/A |

| Setbacks (Minimum) | |
|---------------------------------------|---------|
| Side Yard | |
| Living Space (Interior Property Line) | N/A |
| Living Space (Corner Property Line) | N/A |
| Wrap Around Porch (Corner) | N/A |
| Detached Garages | N/A |
| Street Side Yard | 10' |
| Rear Yard | |
| Living Space (Min./Ave) | 10'/10' |
| Front Entry Attached/Detached Garages | N/A |
| Garages with Rear Access | N/A |
| Patio Covers (1 Story Height) | N/A |

| Setbacks (Minimum) | |
|---------------------------------------|-----------------|
| Alley / Private Drive | |
| Garage (door) | 5' |
| Garage (to center of Private Drive) | N/A |
| Porch | 5' |
| Height (Maximum to Ridge Line) | |
| Primary Dwelling | 35' (2 Stories) |
| Detached Garage | N/A |
| Parking | |
| Residence (Garage) | 2 cars min. |
| Guest (Apron) | N/A |
| Building Coverage | |
| | N/A |

2

Dimensions shown are for example purpose only See table above for setbacks




Table 2.8 Medium Density Architectural (MDR) - Bungalows


| Setbacks (Minimum) | | |
|---|-----------|-----------|
| Front Yard @ Street | | |
| Living Space (First/Second Story) | (10'/10') | (10'/10') |
| Porch (6' min. clear depth) | 6' | 6' |
| Garage Front Facing (Door) | N/A | N/A |
| Side-Entry Garage Wall | N/A | N/A |
| Front walls (Private Street) | 2' | 2' |
| Front Yard @ Non-Street Frontage | | |
| Living Space (First/Second Story) | (5'/5') | (5'/5') |
| Porch (6' min. clear depth) | 6' | 6' |
| Garage Front Facing (Door) | N/A | N/A |
| Side-Entry Ga all | 5' | 5' |
| Front walls (Private Street) | 2' | 2' |

| Setbacks (Minimum) | | |
|---------------------------------------|-------------|-------------|
| Rear Yard | | |
| Living Space (Min./Ave) - See Note 6 | 10' | 10' |
| Front Entry Attached/Detached Garages | 3' | N/A |
| Garages with Rear Access | Not Allowed | Not Allowed |
| Patio Covers (1 Story Height) | Not Allowed | Not Allowed |
| Alley / Private Drive | | |
| Garage (door) | 2' Apron | 2' Apron |
| Garage (to center of Private Drive) | 14' | 14' |
| Lot Coverage | | N/A |
| Structure Height (Maximum) | | 35' |

| Side Yard | | |
|---------------------------------------|-------------|-------------|
| Living Space (Interior Property Line) | 4' | 4' |
| Living Space (Corner Property Line) | N/A | N/A |
| Wrap Around Porch (Corner) | Not Allowed | Not Allowed |
| Detached Garages/Accessory Unit | Not Allowed | Not Allowed |

Special Development Standards:

1. No accessory structures shall be allowed.
2. No pools shall be allowed and spa and hot tubs permitted only within courtyards subject to City building code.
3. No building additions shall be allowed.
4. Balconies shall only be allowed on carriage units subject to the setback requirements shown on this page.
5. Guest parking shall be as per LMC 17.76.020 D.1.c. (0.25 spaces per unit).



Dimensions shown are for example purpose only
See table above for setbacks

2

This page left intentionally blank

2.3 Technical Specifications:

2.3.1 Structural Wiring (LDR & MDR Only)

Introduction

The Structured Wiring System shall be installed in a star topology (often called a homerun topology). The system shall consist of a central structured wiring panel (SWP) that terminates cable feeds from each telecommunications provider's network demarcation point. Cables emanate from the SWP and terminate in outlets conveniently located throughout the home.

When possible, all connecting hardware, cables, and SWP shall be purchased from a single manufacturer and installed to the manufacturer's specifications required to provide for a limited product warranty.

All components shall be installed in compliance with applicable local, state, and national building codes. If these specifications conflict with building codes, the building codes shall apply.

Components

Outlets and Terminations

Outlet Locations:

- ^ A minimum of three (3) Media Outlets shall be installed in each home. Media Outlets should be considered in the Kitchen, Home Office, Master Bedroom, and Family Room/Living Room locations. Builders are encouraged, but not required to add more media outlets than the required minimum.
- ^ A minimum of one (1) Quad Media Outlet shall be installed in each home. Typically, this outlet should be placed in the Family Room/Great Room or wherever the main audio/video entertainment equipment is placed within the home. Builders are encouraged, but not required to add more quad media outlets than the

required minimum.

- ^ A minimum of two (2) Data Outlets shall be installed in each home. Data Outlets should be considered in the Kitchen/Great Room area and in the Master Bedroom. A Media Outlet may be substituted. Builders are encouraged, but not required to add more data outlets than the required minimum.
- ^ All outlets shall be located within three feet (3') of an electrical outlet.
- ^ It is recommended that two (2) Media Outlets be installed on opposing walls in each Master Bedroom.

Terminations:

Cat 5e/6 cables shall be placed from the SWP to the following locations:

- ^ Near the HVAC Unit (within 16", blank plated)
- ^ Near any irrigation control (within 16", blank plated)
- ^ These cables are not terminated and shall be labeled by destination (example: "HVAC").

Cable and Connection Requirements

Data:

- ^ All Cat 5e/6 connections are made with an RJ-45 8-conductor modular plugs and jacks wired to the EIA 568A criteria.
- ^ All components shall be rated for Cat 5e/6 performance, including those designated for telephone terminations. Cable runs shall meet EIA 568A criteria for performance, minimum bend radius, and connections.
- ^ Cross-connects at the SWP shall use modular jacks and plugs. The incoming service feeds may use "punch-down" termination.

Video:

- ^ Only hex crimp or radial compression connectors may be used. Twist-on and reusable type connectors are not acceptable.
- ^ Media Outlets are the minimum requirement for any video location.
- ^ All unused coax network ports shall be terminated into a 75-ohm termination device or utilize self-terminating connectors.
- ^ The video distribution system shall include a 4 port passive "splitter" for the distribution of RF signals. If more than 4 video outlets are active, then a bi-directional amplifier shall be installed.

General:

- ^ Unshielded twisted pair (UTP) cable compliant with the Cat 5e/6 or greater EIA 568A specification shall be used to distribute voice and data signals.
- ^ RG-6 coaxial cable is used to distribute video and data signals.
- ^ All cabling shall be installed in a homerun from the SWP to each outlet with maximum individual cable lengths of no greater than 295' (90m) in compliance with TIA/ EIA 568A specifications.
- ^ Cables shall be installed according to manufacturers' instructions adhering to minimum bending radius and cable tension specifications.
- ^ At least eighteen inches (18") of cable slack shall be left at all outlets.
- ^ Where possible, the horizontal routing of the cables shall be done between floors (ceilings) and basements or crawlspace (if applicable/available) rather than through studs.
- ^ All cables installed into the SWP shall include a minimum of 24" of slack.

- ^ All installed cable runs shall be tested individually, end-to-end for parity and continuity after final termination. It is recommended that all Cat 5e/6 cabling be mapped and certified to then current, industry accepted standards for the cabling grade.
- ^ The cables can be deployed individually or bundled in a common sheath.
- ^ Hard fasteners may compromise cable performance and shall not be used.
- ^ All cables shall be at least twelve inches (12") from parallel 110 VAC cable runs, and shall never pass through the same holes. If the cable must cross the 110 VAC cable, it shall do so at a 90-degree angle.
- ^ Electrical boxes may cause damage by exceeding allowable bend radius to cables and will not allow for the required 18" of wire or wires to be left for future re-configuring. Cables and outlet cover plates shall be clearly labeled. All cables entering or exiting the SWP shall be labeled. A legend shall be left in the SWP.
- ^ Where it is necessary to penetrate a fire-rated wall, the hole shall be sleeved with EMT. The sleeve and penetrating hole shall be sealed with a fire retardant sealant. Where it is necessary to place an outlet in a fire-rated wall, install a plaster ring (P-Ring), and then block, drywall, and caulk per local fire coding.
- ^ All wires and cables in the attic shall not contact bathroom vents, lighting fixtures, hot water pipes, and heating vents. If possible, all wires and cables in the attic should be routed above the attic floor.

Service Feed:

Service feed cabling shall be placed from the exterior network termination location in an uninterrupted path to the SWP. The service feed bundle shall contain a minimum of two (2) Cat 5e/6 cables and two (2) RG-6 cables. The service feed cable shall exit

the home at a height of 5' 6" (five foot, six inches) above finished grade.

Structured Wiring Panel (SWP) and Components

- The SWP shall accommodate all necessary wiring and devices, while maintaining minimum bend radius requirements for incoming and outgoing wiring.
- When the SWP is mounted on an interior concrete wall, plywood backing shall be used.
- A 110 VAC 20 Amp, non-GFI dedicated duplex outlet shall be installed within the SWP.
- The SWP shall be located within the climate controlled (conditioned space) area of the home.


Router:

A router is optional. If provided, the router shall be installed and securely fastened inside of the SWP.

- Wireless routers or access points are not recommended within the SWP. The wireless performance may be degraded due to interference from the SWP. Additionally, wireless routers are not recommended to be included due to the problematic nature of the devices.

Service Provider Drop Requirement

- A 1.5" (1½ inch) conduit from the network demarcation point of each residence to the property line is required at a location specified by the communication provider.
- All communication conduits from the property line to the dwelling unit shall be buried at least 24" (twenty-four inches) from finished grade.



Definitions

Blank Outlet

An outlet with unterminated cables covered with a blank plate.

Cat 5e/6

Category 5e or Category 6 wiring standard, as defined in a revision to the EIA 568A Commercial Wiring Standard. The Category 5e wiring standard shall be the lowest acceptable performance designation for twisted pair wiring and Category 6 is recommended.

Structured Wiring Panel (SWP)

The structured wiring enclosure or wiring distribution panel.

Data Outlet

An outlet with two Cat 5e terminations. One termination is labeled voice and the other data.

Media Outlet

An outlet containing one RG-6 and one Cat 5e/6 cable. RG-6 The coaxial cable grade that ensures adequate bandwidth for the delivery of video signals.

Router

The device connecting the data network in the home (LAN) with the communications provider's data network (WAN).

Quad Media Outlet

An outlet with two Cat 5e/6 terminations and two coax terminations.

UTP

Unshielded Twisted Pair Wire.

Homerun

A wiring topology where every wire is run separately from its termination point back to a central distribution point, usually in a utility room or dedicated A/V room. Also known as "star topology."

RIVER ISLANDS



CHAPTER 3

LANDSCAPE GUIDELINES AND STANDARDS

3.1 INTRODUCTION

This chapter addresses guidelines and standards for landscape elements to be installed by Builders. These elements include planting and irrigation of residential yards, driveways, site furnishings, and sustainable design measures. The provisions set forth within this chapter will provide a closely coordinated, cohesive, and memorable landscape experience to unify neighborhood character and ensure that every resident feels well-connected to site and landscape. The goal is to create a welcoming residential landscape that enhances the living experience, adds lasting value to homes and the neighborhood as a whole, and incorporates sustainable measures for landscape design and construction.

The West Village District, as with other districts in the project, will reinforce the overall theme of River Islands with an urban community that feels as if it grew within the context of the the California Delta as a corridor between the rural agricultural and country living of the San Joaquin Valley. The concept seeks to blend the modern home into the historical land use of the natural environment of the Central Valley's farmland and the surrounding waterways, which give such life to the environment. This theme may be expressed through the use of orchard-style planting, wildlife-attracting hedgerows, riparian-type planting, abundant trees, and durable long-lasting materials that convey a genuine sense of place.



Typical frontyard planting along residential streets



Parkway strip shrub and tree groupings create a sense of place

The City of Lathrop Municipal Code, Chapter 17.92: Landscape and Screening Standards and the City of Lathrop Design and Construction Standards provide additional requirements for landscape. Where documents differ, these Builder Guidelines and Standards shall apply.

3.2 RESIDENTIAL LANDSCAPE

3.2.1 Planting Design

Guidelines

- Planting themes have been selected to mimic existing characteristics and habitat of the delta waterways and vegetated agricultural hedgerows. Plant material selection should strongly consider the use of drought-tolerant, durable and long-lived species that give the appearance and imagery of the Delta Valley. Species should be well adapted to the climatic conditions and soil types typical of the River Islands Development. Robust evergreen shrub species intermixed with flowering native shrub species are strongly encouraged. Large naturally shaped flowering shrubs species should be selected to mimic the image of traditional hedgerows typical of the surrounding agricultural region. Flowering species that create year-round interest are of high preference.
- Landscape design should emphasize the use of nectar-producing and flowering plants that supply food, shelter and breeding habitat for beneficial insects that pollinate edible crops and control pests. Gardens for butterflies, hummingbirds, and native bees are encouraged.
- Landscape design should provide effective screening of retaining walls, utility enclosures, utility cabinets, or service areas to reduce negative visual impacts. Screen landscaping should incorporate evergreen plant species in order to maintain year-round leaf cover.
- Plant selection should avoid the use of tree species with invasive root systems near utility lines and paving and avoid the use of non-native, invasive species that may spread into open space areas. All plants should be carefully selected to avoid toxic species that could

- Low groundcover of robust evergreen species should be used for ground plane landscape, as an alternative to turf. Turf should only be used for high use areas and the selected turf should be a deep rooting variety or a California Native variety. The use of turf should follow the guideline and requirements as described in AB1881 and Chapter 17.92 of the Lathrop Municipal Code.
- Plants with higher water demands should be located in shade or where more runoff occurs.
- Landscape around homes should be designed to provide shading in the summer months and solar access during the winter. Planting deciduous trees next to buildings will reduce ambient temperature, reduce heat gain, and allow for cooler natural ventilation. Deciduous trees and vines in front of south-facing walls and windows will further cool buildings by intercepting sunlight during summer months, yet allow direct sunlight during the winter.
- Energy-efficient landscaping techniques are encouraged such as use of local materials, on-site composting, and chipping to reduce green waste hauling.
- Structures such as trellises and porticoes may be incorporated into the building/landscape edge, especially on south- and west-facing exposures, to provide shade in the summer and allow solar penetration when the sun is at a low angle in the winter.

Standards

- All private yard areas visible from public parks, streets, alleys or lakes shall be landscaped by the Builder/Developer. Homeowners shall be responsible for private yard areas enclosed within fences.
- Landscape plans for all areas where the builder is required to install landscaping shall be prepared by a landscape architect registered to practice in the State of California.
- Landscape construction practices shall adhere to the provisions in Section 3.4, below.

STREET TREE MASTER LIST

| LOTS | STREET DIRECTION | BOTANICAL NAME | COMMON NAME |
|-----------|--------------------------|--|---|
| Village 1 | North/South East/West | Pistacia c. 'Keith Davey' Tilia c. 'Greenspire' | Keith Davey Chinese Pistache Greenspire Little-Leaf Linden |

STREET TREE LIST BY CONNECTOR STREET

| STREET | BOTANICAL NAME | COMMON NAME |
|----------------|------------------------------|-------------------------|
| CAMBAY PARKWAY | Carpinus b. 'Franz Fontaine' | Franz Fontaine Hornbeam |
| CALLERTON AVE | Zelkova s. 'Green Vase' | Green Vase Zelkova |
| WINTON AVE | Quercus coccinea | Scarlet Oak |
| RIPTIDE WAY | Phoenix canariensis | Canary Island Date Palm |
| ROLL TIDE WAY | Acer rubrum 'October Glory' | October Glory Red Maple |

ACCENT TREE LIST

| BOTANICAL NAME | COMMON NAME |
|------------------------------|----------------------------|
| Cercis occidentalis | Western Redbud |
| Chitalpa tashkentensis | Chitalpa |
| Lagerstroemia indica | Crape Myrtle |
| Prunus c. 'Krauter Vesuvius' | Purple Leaf Flowering Plum |
| Prunus serrulata 'Kwanzan' | Kwanzan Flowering Cherry |

Note: These species are for reference and are not intended to be the only type of accent trees. See Appendix B for additional species.




Figure 3.1 Street Tree Locations - Non-Active Adult Homes (West Village)




TYPICAL CORNER LOT STREET TREE PLANTING



TYPICAL INTERNAL LOT STREET TREE PLANTING



PARKSTRIP SECTION
NOT TO SCALE



TYPICAL PARKSTRIP PLANTING SCHEME
NOT TO SCALE

PARKWAY STRIP PLANT LIST

| BOTANICAL NAME | COMMON NAME |
|---------------------------------------|----------------------------|
| Juniper | Juniper |
| Coprosma p. 'Verde Vista' | Coprosma |
| Cotoneaster dammeri 'Coral Beauty' | Bearberry Cotoneaster |
| Arctostaphylos 'Pacific Mist' | Manzanita |
| Cistus Salvifolius | Sageleaf Rockrose |
| Myoporum parvifolium | Australian Racer |
| Rosa x 'Noaschnee' | Flower Carpet White Rose |
| Rosmarinus offic. 'Huntington Carpet' | Huntington Carpet Rosemary |
| Teucrium chamaedrys 'Prostratus' | Germander |
| Rosmarinus O. 'Prostratus' | Dwarf Rosemary |

PARKWAY STRIP MASTER PLANT LIST

| VILLAGE / STREET | STREET / DIRECTION | BOTANICAL NAME | PLANT SPACING |
|------------------|--------------------|---------------------------------------|---------------|
| VILLAGE 1 | East/West | Arctostaphylos 'Pacific Mist' | 36" O.C. |
| | North/South | Juniper | 36" O.C. |
| CALLERTON AVE | East/West | Varies | 36" O.C. |
| CAMBAY PARKWAY | East/West | Varies | 36" O.C. |
| WINTON AVE | East/West | Rosa x 'Noaschnee' | 36" O.C. |
| ROLL TIDE WAY | North/South | Rosmarinus offic. 'Huntington Carpet' | 36" O.C. |
| RIPTIDE WAY | East/West | Rosa x 'Noaschnee' | 36" O.C. |




Figure 3-2: Parkway Strip Planting Master Plan

3

3.2.2 Front and Side Yards

- Front yards of lots should be designed and installed by the Builder as a continuous landscape with consistent plant materials and dimensions that unify the street edge (see Figure 3-1). Dominant ground plane plant material should consist of shrubs, perennials and grasses that maintain an attractive appearance and enhance natural habitat values.
- Hedgerows may be used on side property lines for privacy and definition of yard areas, and a continuous low border of low shrubs or groundcover may be installed adjacent to the sidewalk (see Figure 3-2).
- Shrubs located near street frontages or on corner lots should not exceed three feet in height.
- Builder is responsible for landscape, irrigation and maintenance of front and side yards.

Standards

- Landscaping for all front yard areas shall be installed by the Builder.
- The Builder shall design front yard landscape for all lots. These front yards shall include a minimum of one tree for regular lots and three trees for corner lots which shall match the species and size of the adjacent street trees or as indicated in Figure 3-1. Additional “accent” trees installed outside of the parkway strip areas may be of a different species (refer to Appendix for a list of acceptable “accent trees”).
- Other front yard areas shall be planted with shrubs and perennials that enhance habitat values and maintain an attractive year-round appearance along the street.
- All front and side yards shall be maintained by the homeowner.
- Irrigation shall be provided for all planted areas (see Section 3.4). The Builder shall install irrigation for all areas that they landscape. After construction, homeowners shall be responsible for irrigation of all yards and adjacent parkway strips. Parkway landscaping shall be maintained by the homeowner fronting along that parkway section, unless it’s the responsibility of a non-City public agency, HOA or maintenance district.

3.2.3 Rear Yards

See Section 3.3 for fencing requirements in lakeside rear yards.

Guidelines

- All rear yards of all lakeside homes should contain a minimum of two trees.
- For lakeside homes, the slope area from the rear yard fence to the lake edge should be planted in informal drifts of shrubs, grasses and perennials. Plant material should be located to maintain views of the water, with higher planting allowed on lower terraces and shorter species on upper portions of the slope. No trees are allowed within the slope areas outside of the 5’ tubular steel fence.

Standards

- All rear yards adjacent to the lake (from rear yard view fence to lake edge) shall be landscaped and mulched (with bark or gorilla hair) by the Builder. This includes view fencing installation at the top of rear yard slopes and side yard fencing installation.
- Developer shall install rear yard pilasters at every other lot corner, pathways to docks, and docks (see Figure 3-4). (Builder may install with the consent of the Developer).
- Irrigation shall be provided for all planted areas (see Section 3.4). The Builder shall install irrigation for all areas that they landscape. After construction, irrigation water may be provided by RD 2062 with homeowners responsible for maintenance of the irrigation system (non-potable water source). Homeowners shall be responsible for irrigation of all yards and adjacent parkway strips.

CONSTRUCTION RESPONSIBILITY

DEVELOPER RESPONSIBILITY*
 View Fence
 Pilasters
 Concrete Walk and Stairs
 Private Docks

BUILDER RESPONSIBILITY
 Privacy Fences (4' and 6')
 Back Yard Trees
 Hillside slope planting along water

*Builder may install with the consent of the Developer




Figure 3-3: Builder/Developer Responsibility Rear Yards/Lake Slopes

- Homeowners shall be responsible for maintenance of their rear yard to the view fence that separates their yard from the lake slope in accordance with these guidelines, the Lathrop Municipal Code and River Islands CC&Rs. Homeowners shall also be responsible for lake slope improvements as well, in accordance with recorded easements as described below.
- Landscaped slope areas under control of Reclamation District 2062 (RD 2062) shall have recorded easements to each individual lot outlining the restrictions and limitations regarding the improvements shown herein. Any subsequent improvements to these areas are subject to review and approval of RD 2062 under separate policy provisions separate from these guidelines.




Figure 3-4: Rear Yards/Lake Slopes at Lakeside Homes

3.3 SITE FURNISHINGS/ MATERIALS

3.3.1 Fences

Figures 3-6, 3-7, and 3-8 illustrates the location and types of fencing to be used, with a variety of heights and design to be used for various conditions. These fences consist of a ‘family’ of elements, similar in style and materials, used in a consistent manner throughout the neighborhood. Additional fencing and walls, including view fencing in the rear yards of lakeside homes, will be installed by the Developer. It should be noted that standards provided in this chapter shall also apply to medium density development and applied on a case by case basis due to the variety of product.

Guidelines

- In general, fencing should be designed to be natural-appearing and durable, compatible with neighborhood character, and reflective of the “Delta Agrarian” character of River Islands.
- Fencing should be made from high quality materials, be of durable construction, and present a “finished” appearance from adjacent properties.
- Solid fences or walls used for privacy or security may be used in either side or rear yard conditions. Fencing should be limited to six (6) feet in height and, in areas facing a public street or alley, must incorporate a change in articulation for the top 12-18 inches of the fence.
- Solid side yard privacy fencing that intersects open space view fencing should not exceed 5 feet in height within the rear setback.
- To reduce their visual prominence, fences should be used in combination with tree, vine, shrub, and hedge planting.

Standards

- 6’ Decorative wood fencing and 6’ side yard wood fencing shall be installed by Builder using the design treatments illustrated in Figure 3-8 and in locations indicated by Figures 3-5, 3-6, and 3-7.
- 6’Decorative wood fencing with lattice treatment shall be used for areas visible from public areas including roadways and parks.
- 6’ Decorative wood fencing shall be set back 10 feet from the sidewalk. Gates shall be installed on one side of the home to allow access from front yard to side yard.




Figure 3-5: Community Wall and Fence Diagram

- 6' Decorative wood fencing shall be used on side property lines. Fencing shall be limited to six (6) feet in height. Decorative privacy fencing (with lattice) shall be used in areas visible from public streets or other public areas. Privacy fencing for lakeside homes shall transition from six feet to five feet in height as indicated in Figure 3-8.
- In sloping areas visible from public streets or public use areas, fencing shall step down the slope. Fencing may slope with the grade in

areas that are outside of public view.

- On corner lots, front yard fencing shall be continuous along the front and side property line. Where slopes occur, fencing shall be installed along the top of slope. For corner lots, side yard fencing along street frontages shall be located a minimum of five (5) feet from the sidewalk.
- Maximum unbroken length of side yard fences should be 100 feet for adjacent street-facing lots. Fencing can be reduced in height at corners as required to allow for traffic safety and visibility.




Figure 3-6: Prototypical Fence Conditions




Figure 3-7: Prototypical Fence Conditions (Water Edge)







Figure 3-8: Prototypical Fence Conditions (For Builder/Developer)




5' TUBULAR STEEL FENCE AT LAKE FRONTAGE



6' TUBULAR STEEL FENCE FOR HIGH DENSITY RESIDENTIAL



5' TUBULAR STEEL FENCE WITH 3' GATE AT LAKE FRONTAGE



6' TUBULAR STEEL FENCE WITH 3' GATE FOR HIGH DENSITY

Figure 3-9: Prototypical Fence Conditions (For Builder)

Figure 3-10: Prototypical Fence Conditions (For Builder)

- Security fencing shall be provided around pool and spa areas in compliance with all applicable codes and ordinances.
- Barbed or razor wire, chain link and plastic/vinyl fencing is prohibited on residential properties.

3.3.2 Signage

- Temporary signage to market the sale of new homes – to be provided by River Islands. Signage should conform to the signage types and hierarchy described in the Appendix.

3.3.3 Landscape Lighting

Guidelines

- Landscape lighting should be designed to be hidden from direct view and to minimize glare and impacts to adjacent land uses, especially residences. Low-level, pedestrian-scale fixtures should be utilized to the degree possible.
- Landscape lighting should utilize durable, energy-efficient fixtures that provide pleasing color. High efficiency fixtures are encouraged to direct light where it is needed to avoid excessive glare and reduce impacts upon night sky and open space. No lighting should blink, flash, or be of unusually high intensity or brightness, except in the case of holiday lighting.
- Landscape lighting should be minimized to reduce light pollution and minimize energy usage.
- LED fixtures and intelligent control systems should be utilized to the extent possible.

3.3.4 Paving and Hardscape

Guidelines

- Paving surfaces on residential lots should be limited to the driveway, walkways, and patios. Paving to replace landscaping shall comply with the Lathrop Municipal Code.
- The general intent of pavement design is to provide an aspect of permanence with subtle textural variety using materials that

appear related to the natural landscape. Brightly-colored and highly reflective materials are not acceptable. Pervious paving is encouraged to the extent feasible.

- Use of enhanced paving materials (exposed aggregate, broom finish, integral color, unit pavers, stamped concrete, and bricks, etc.) is encouraged for front walks, patios and driveways. Planting areas are recommended between pavement and walls or fences. Concrete areas on the landscape plans should be designated with surface finish, color, expansion joints, and score joints. Expansion and score joints help isolate cracking locations in concrete and should occur 8 feet on center (max.) in each direction.
- Residential driveways serving front-facing garages should use enhanced materials, and/or scoring patterns to reduce the visual impacts.
- Selected paving color/albedo should meet a minimum SRI (Solar Reflective Index) value of 29 in order to aid in reducing the heat island effect (note: typical grey concrete usually falls between 38-52).

3.4 LANDSCAPE CONSTRUCTION PRACTICES

The following provisions address construction practices techniques to ensure healthy and successful projects and adhere to requirements and measures for sustainable landscape.

3.4.1 Irrigation and Water Conservation

The City of Lathrop Municipal Code, Chapter 17.92 Landscape and Screening Standards, contains additional requirements for irrigation and water conservation.

Guidelines

- The irrigation system should be designed to conserve water resources by efficiently and uniformly distributing water. Designs should be based upon applicable California Department of Water Resources ordinances and tailored to the climate of the City of Lathrop.

- Use of low volume spray heads and drip irrigation systems should be maximized. New irrigation techniques and drip irrigation systems should be used to ensure more efficient delivery of water.
- Irrigation design should accommodate hydrozones accordingly, separating high, medium and low water-use plants. Trees should be put on a separate system, specifically in lawn areas, and shrubs and trees should be irrigated with a drip or bubblers to provide deeper, more even watering and promote water conservation. Systems should also be separated by sun exposure, i.e., north/east exposures versus south/west exposures.
- Turf and groundcover should be irrigated with a conventional rotary nozzle spray system, using head-to-head spray coverage. In-stem pressure regulation and check valves are required on all heads. To effectively meet the intent of the state of California's conservation effort sub-surface drip irrigation should be the primary irrigation method. No above ground irrigation distribution method should be incorporated in areas less than ten feet (10") wide and shall maintain a twenty-four inch (24") offset from all pavement surfaces that drain directly to catchbasins.
- The irrigation controllers should be programmed according to the water needs of plants on each circuit, with consideration of the time of year and plant maturity. If precipitation rate exceeds the soil absorption rate, multiple shorter cycles should be programmed as required to allow absorption.
- Automatic irrigation controllers should be automatically adjusted using, at a minimum, daily ET (Evapotranspiration) rates and preferably hourly ET with an onsite rain shut-off device. Should an ET based controller not be utilized an onsite rain sensor with active moisture sensor may be used.
- All homes should be installed with an automatic master valve at the irrigation point of connection in conformance with AB1881 (MWEL0)
- Main lines should have 18" of cover.
- Irrigation valves should be screened from view from the street by landscaping or other attractive site materials.
- Irrigation systems should be monitored regularly for proper operation, leaks and broken heads, adjustment of controller programming, and elimination of excessive over spray and runoff.

Standards

- Irrigation shall be provided for all planted areas.
- Builder shall provide each home with an automatic irrigation controller that accommodates all aspects of the landscape design, including independent programming of multiple stations to cover front yard (including parkway strip), side yard, and backyard areas. Lake slope areas may be provided non-potable water from RD 2062.

3.4.2 Soil Preparation and Mulching

Standards

- Finish landscape grading by Builders after construction of homes, if required, shall maintain or re-establish the overland release per the design intention of the Developer's Civil Engineer. Builders shall be responsible for maintaining proper drainage without creating depressions or dams.
- Builders should require an Agricultural Suitability Soil Test. The soils should be tested for agricultural suitability, parasitic nematodes and herbicide or deleterious contamination. The test should be completed by a reputable testing agency and should include recommendation for amendments, soil conditioners, pH correction, and fertilization.
- Subsequent to installation of underground utilities, soil compacted by construction should be rototilled to a minimum depth of eight (8) inches. In order to prevent interface layers between import topsoil and native soil, native soil should be broken up by ripping or rototilling to a depth of 8 to 12 inches before the addition of import topsoil or amendment.
- All planted areas should be amended to provide for an optimum growing media for most plants.
- Amendments (e.g. nitrolized compost, gypsum, soil sulphur, fertilizer, iron sulfate, etc.) should be rototilled into the soil to a depth of 4 to 6 inches. Amendments are more effective when thoroughly incorporated into the soil. Avoid staining when using ferrous sulfate as an amendment by washing off all hardscape immediately after applying or mixing.

- At all planting areas except lawns, a minimum of two inches of organic mulch shall be applied on top of the soil surface after planting in order to cool the soil surface, reduce evaporation, and suppress weed growth. Organic mulches, including wood chips, shredded bark, and other commercially available mulches are preferred to inorganic materials. Organic mulches should not be dyed an artificial color, but should be a natural brown or dark brown in color. Permanent visible applications of inorganic sheeting, fabric, netting, etc. are not acceptable.

3.4.3 Planting

Standards

- Plant materials shall be selected from Appendix: Plant Selection Guide. Substitutions or additions may be considered by the DRB based on the suitability of the species in terms of similarity of form, adaptability, tolerance to site soils, climatic conditions or water quality, or other pertinent characteristics.
- Plant sizes and spacing shall comply with the specifications noted on Appendix: Plant Palette and shall be sufficient to provide healthy growth, attractive appearance, and full coverage of planting areas when plants are mature. In general, size and spacing requirements are as follows:
 - Primary front yard tree: Size to match adjacent street tree (24" box); spacing per requirements in Section 3.2 above.
 - Other front yard trees or side/rear yard trees: 15 gallon min.; spacing varies.
 - Hedgerows: 5 gallon; 36" o.c. or as needed to create hedge, given anticipated growth pattern
 - Other shrubs: 5 gallon; 48" o.c. or as needed for full cover, given anticipated growth pattern.
 - Groundcovers for habitat and border planting: 1 gallon; 18" o.c. or as needed for full cover, given anticipated growth pattern.
 - Smaller groundcovers or perennials for parkway strips or yards: 1 gallon; 12" o.c. or as needed for full cover, given anticipated growth pattern.
- Riparian planting for lakeside slope area: see Figure 3-2.
- See Figure 3-9 for tree and planting details.







Figure 3-11: Planting Detail

RIVER ISLANDS



CHAPTER 4

PROJECT
IMPLEMENTATION

This page left intentionally blank

4.1 Project Implementation

4.1.1 Stewart Tract Design Review Committee (STDRC)

All projects shall be subject to the design review process and submittal requirements described in the following sections. Projects will be reviewed by the Stewart Tract Design Review Committee (STDRC), according to the requirements set forth below and Section 17.61.160 of the Lathrop Municipal Code. The STDRC is a group of three design professionals that represent the master developer. The STDRC will review design and improvement plans for new construction on undeveloped and improved lands within the community for conformance with these West Village Non-Active Adult Architectural Guidelines/Design Standards (AG/DS) and with all applicable plans (described below). The STDRC's review is advisory only and does not guarantee approval of any permit from other agencies. The City of Lathrop utilizes the STDRC's recommendation for certain approvals to Building Division, Planning Commission and some cases Lathrop City Council, if applicable.

After STDRC review is advisory only, applicants are still required to obtain approval by the City of Lathrop for all construction projects and necessary approvals and permits. This includes landscaping and infrastructure permits if applicable.

Prior to the submission of development proposals to the City of Lathrop, the STDRC shall review such proposals and make recommendations to the Master Developer and the City; the STDRC shall also recommend exceptions and revisions to the Old River District AG/DS to the City for further consideration and potential action by the Planning Commission. The STDRC may create exceptions to the AG/DS to accommodate development proposals which might suggest minor design changes or adjustments that are consistent with the intent of these DG/DS; in some cases, an exception might apply to a design condition not foreseen in the original drafting of the AG/DS. A STDRC recommendation to grant an exception may or may not be coupled with a proposed project

proposal already being reviewed by the STDRC. A request for revision to the AG/DS must be made in writing to the City of Lathrop Community Development Department and be approved by the Planning Commission after review and recommendation of the STDRC.

4.1.2 Consistency Requirements

Plans must be found consistent with this document and other applicable City of Lathrop land use entitlements, as well as any recorded River Islands CC&Rs. While the adopted AG/DS document itself is consistent with previously approved planning documents for River Islands, the Builder should be aware of requirements of other applicable entitlements/plans that may also apply to your project. These entitlements/plans include:

1. City of Lathrop Comprehensive General Plan (as amended)
2. West Lathrop Specific Plan (as amended)
3. River Islands Phase 2 Urban Design Concept (UDC)
4. City of Lathrop Development Title (zoning and subdivision ordinances)
5. River Islands Development Agreement and Performance Standards
6. Vesting Tentative Map No. 6716 Conditions of Approval (as amended)
7. Old River District Neighborhood Development Plan (NDP) Adopted River Islands Conditions, Covenants and Restrictions (CC&Rs), if applicable

4.1.3 Design Review Submittal Requirements

As a minimum, all applicants shall provide the following to the Master Developer for processing STDRC review:

1. Location Map - should include Tract, lot and/or parcel numbers if available.
2. Conceptual Plans and Elevations- this shall include preliminary building floor plans for each architectural style and model type represented. This includes enhanced

elevations for those structures which will be adjacent to major streets and project features which are exposed to the public.

3. Conceptual front yard landscaping plans for each lot type.
4. Conceptual neighborhood landscaping plans.
5. Preliminary Color Palette & Materials (can be submitted in a "board" format).
6. Conceptual Lotting Plan (Subdivisions) - the lotting plans shall show at least five contiguous lots, including one corner lot (if applicable). The footprints for proposed structure shall be shown on the lot, along with any driveways, walks, landscaped areas, dimensioned setbacks, fencing and other major features.
7. Conceptual Streetscape Plan – shall show all proposed models and architectural themes on one elevation in color to depict the representative streetscape.

All submitted architectural plans and elevations shall be at a minimum scale of 1/8" to 1/4" = 1'-0" on 24" x 36" paper, as well provided as an electronic file in PDF format. 11" x 17" sized documents may be allowed on a case by case basis. Any other exceptions to the submittal requirements must be approved by the Master Developer.

At least one STDRC meeting shall be held to review the application materials. Each applicant is strongly encouraged to have the architect and other design professionals in attendance for this meeting. Additional meetings may be required if the submittal is incomplete or additional questions or issues cannot be addressed in the initial meeting. STDRC can conduct subsequent meetings via an e-mail discussion once the supplemental information has been provided which addresses the concerns raised.

The STDRC will submit a written recommendation letter and minutes reflecting the STDRC action to the applicant and to the City of Lathrop and any other applicable agencies after its review. The Master Developer may also provide a separate recommendation letter based upon the STDRC's recommendation


as may be required by CC&Rs or individual agreements between the Master Developer and the applicant.

All applicants shall be advised that the City of Lathrop has a separate design review process for review of proposed model homes and construction documents prior to planning and/or building permit approval. The actions taken by the STDRC shall be used to supplement the application process required by the City of Lathrop. The City of Lathrop Planning Division should be contacted for specific information related to the requirements associated with Architectural Design Review and Administrative Approval.

RIVER ISLANDS



APPENDIX



West Village District Architectural Design Guidelines and Development Standards

Accessory Structure Standards

Accessory Structures:

Minimum Setback Distance from Property Line

| Structure Height | Front Yard* | Street Side Yard (corner lot) | Side Yard (interior) | Rear Yard |
|------------------|-------------|-------------------------------|----------------------|-----------|
| ≤ 8 ft. | Not allowed | 10 ft. | 3 ft. | 3 ft. |
| >8 ft. to 15 ft. | Not allowed | 10 ft. | 5 ft. | 5 ft. |

*Landscape features are allowed in the front yard as shown in definition below.

1. Setback Measurement - Minimum setback distance between property line and accessory structure shall be measured from the wall or post(s) of the supporting structural member of the structure. Overhangs are allowed consistent with the current City adopted Building Code.
2. Separation Between Structures - All accessory structures shall maintain the minimum separation between other buildings as required under current City adopted Building Code.
3. Building Permit Required when Applicable – A building permit shall be obtained for all accessory structures as required by the City adopted Building Code, if applicable.
4. Attached Patio Covers – attached patio covers, sunrooms and similar structures not first approved with the original dwelling unit building permit, shall meet all setbacks of the dwelling unit, unless exceptions are approved by the River Islands Architectural Review Board with appeal to STDRC.

Definitions:

Accessory Structure - An attached or detached structure that is either entirely enclosed by walls and a solid roof or is partially enclosed with a solid or limited roof covering. Examples include, but are not limited to, detached garages, greenhouses, pool houses,

sunrooms, workshops, storage sheds, barns, as well as, free standing patio covers, carports, gazebos and stables. Accessory structures also include play equipment, windmills, water towers, and other similar structures.

Landscape Feature - A detached decorative structure with a maximum height of eight (8) feet typically used in conjunction with plant materials for aesthetic enhancement, including, but not limited to, garden trellis covers with non-solid roof construction, arched trellises, vertical lattice structures, statues, fountains, and similar features may be allowed in the front yard setback, subject to building/electrical/mechanical permits of the City of Lathrop and subject to review and approval of the River Islands Architectural Review Board (RIARB). Any decision of the RIARB may be appealed to the Stewart Tract Design Review Committee (STDRC).

Architectural Features:

1. Architectural features including sills, chimneys, fireplaces, cornices and eaves may extend into a required side yard, rear yard or a space between structures not more than two (2) feet and may extend into a required front yard not more than five (5) feet; provided, that where an architectural feature extends more than two (2) feet into a required side yard, the extension shall be protected by a minimum one-hour fire resistant standard.
2. Open, unenclosed, uncovered metal fire escapes and depressed ramps or stairways may project into any required yard or space between buildings not more than four (4) feet, subject to review and approval of the RIARB and may be appealed to the STDRC.
3. Planter boxes attached to a dwelling may be extended into a required front yard by not more than three (3) feet.
4. Walks, driveways and retaining walls may occupy any required yard, subject to City regulations regarding public utility easements, right of way encroachments and possible building permit regulations. Any extension or modification of approved walks, driveways and retaining walls approved with the original construction of the dwelling unit shall be subject to the review and approval of the RIARB and may be appealed to the STDRC.
5. Swimming pools, in-ground spas and hot tubs are subject to the regulations contained in the City's currently adopted Building Code.

Builder Identification Signs

Builders are to choose from 3 style options as shown on following pages.

River Islands Builder Site Signs

Option 1

Scale: .5" = 1'

AMERICAN TRADITIONAL

Black Steel Fence,

Digital Print on Aluminum



River Islands Builder Site Signs
Option 2
Scale: .5" = 1'

CRAFTSMAN COTTAGE
Wood Frame with Pickets,
Digital Print or
Blasted Sign Foam



River Islands Builder Site Signs

Option 3a

Scale: .5" = 1'

CALIFORNIA RANCH

Wood Frame with Pickets,

Digital Print or

Blasted Sign Foam



Plant List

RIVER ISLANDS- PLANT SELECTION GUIDE

All plant materials shall be selected from the following plant list as approved by the City of Lathrop as part of this Architectural Design Guidelines & Development Standards document. Any exceptions must be recommended for approval by the STDRC prior to installation. Basis for exceptions shall be limited to plant availability, where a similar available plant species may be substituted.

| Streetcape Between Wall and Walk | Streetcape Parkway Strips | Streetcape Medians | Streetcape Bio-Swale (Interior Levee Rd) | Parks & Open Spaces | In-Tract Street Trees | In-Tract Parkway Strips | In-Tract Rear-Yard Lake Frontage | Levees, Trails and Restoration Areas | Botanical Name | Common Name | Use Height | Use Width | Water Use | Attributes |
|----------------------------------|---------------------------|--------------------|--|---------------------|-----------------------|-------------------------|----------------------------------|--------------------------------------|---|--|------------|-----------|-----------|---|
| | | | | | | | | | Trees | | | | | |
| | | | | | | | | | <i>Acer buergerianum</i> | Trident Maple | 20'-25' | 20'-25' | M | |
| | | | | | | | | | <i>Acer x freemanii</i> 'Autumn Blaze' | Maple, 'Autumn Blaze' | 40'-50' | 40' | M | |
| | | | | | | | | | <i>Acer macrophyllum</i> | Big Leaf Maple | 30'-75' | 30'-50' | H | |
| | | | | | | | | | <i>Acer negundo</i> var. <i>californica</i> | California Box Elder | 30'-50' | | M | |
| | | | | | | | | | <i>Acer rubrum</i> 'Armstrong', 'October Glory', Redpointe' | Armstrong Red Maple | 40'-50' | 15' | H | |
| | | | | | | | | | <i>Aesculus californica</i> | Buckeye | 20'-30' | 20'-30' | VL | |
| | | | | | | | | | <i>Aesculus carnea</i> | Red Horsechestnut | 40' | 30' | M | |
| | | | | | | | | | <i>Alnus rhombifolia</i> | White Alder | | | | |
| | | | | | | | | | <i>Arbutus unedo</i> | Strawberry Tree | 8'-25' | 8'-25' | L | |
| | | | | | | | | | <i>Arbutus 'Marina'</i> | Marina' Strawberry Tree | 20'-30' | 20'-30' | L | |
| | | | | | | | | | <i>Arbutus marina</i> - 'Multi-trunked' | Strawberry Tree | 15'-30' | 15'-20' | L | Dark green oblong foliage with rosy pink fall flowers |
| | | | | | | | | | <i>Betula jacquemontii</i> (<i>Betula utilis jacquemontii</i>) | White Barked Himalayan Birch | 40'-60' | 25'-30' | H | |
| | | | | | | | | | <i>Carpinus betulus</i> 'Fastigiata' | European Hornbeam | 40' | 30' | M | |
| | | | | | | | | | <i>Catalpa speciosa</i> | Western Catalpa | 40'-60' | 20'-40' | M | |
| | | | | | | | | | <i>Cercidium x 'Desert Museum'</i> | Desert Museum Palo Verde | 20' | 20' | ? | |
| | | | | | | | | | <i>Cercis canadensis</i> 'Oklahoma' | Eastern Redbud | 25'-35' | 25'-35' | M | |
| | | | | | | | | | <i>Cercis occidentalis</i> | Western Redbud | 10'-20' | 10'-20' | VL | |
| | | | | | | | | | <i>Cercis occidentalis</i> - 'Multi-trunked' | Western Red Bud | 12'-18' | 10'-18' | L | Blue-green foliage with magenta flowers |
| | | | | | | | | | <i>Cercocarpus betuloides</i> | Island Mountain Mahogany | 5'-20' | 5'-20' | VL | |
| | | | | | | | | | <i>Chilopsis linearis</i> 'Monhews' | Timeless Beauty Desert Willow | 15'-20' | 15'-20' | VL | Fragrant showy purple flowers |
| | | | | | | | | | <i>Chionanthus retusus</i> | Chinese Fringe Tree | 20' | 15' | M | |
| | | | | | | | | | <i>X Chitalpa tashkentensis</i> | Chitalpa | 30' | 30' | L | White to pale or dark pink flowers |
| | | | | | | | | | <i>Crataegus phaenopyrum</i> | Washington Hawthorn | 25' | 20' | M | |
| | | | | | | | | | <i>Cupressus arizonica</i> | Arizona Cypress | 40' | 20' | VL | |
| | | | | | | | | | <i>Cupressus sempervirens</i> | Italian Cypress | 40'-70' | 10'-20' | M | |
| | | | | | | | | | <i>Ginkgo biloba</i> 'Autumn Gold' (Male only) | Ginkgo, 'Autumn Gold' | 35'-40' | 25'-35' | M | Use male only varieties |
| | | | | | | | | | <i>Gleditsia tricanthos inermis</i> | Thornless Honey Locust | 25'-50' | 25'-50' | L | |
| | | | | | | | | | <i>Koelreuteria paniculata</i> | Goldenrain Tree | 20'-35' | 25'-40' | M | |
| | | | | | | | | | <i>Lagerstroemia indica</i> 'Dynamite' | Crape Myrtle | 15'-25' | 15'-20' | L | Red Flowers |
| | | | | | | | | | <i>Lagerstroemia x fauriei</i> 'Natchez' | Crape Myrtle | 20'-30' | 15'-20' | L | |
| | | | | | | | | | <i>Lagerstroemia x fauriei</i> 'Natchez' - 'Multi-Trunked' | Natchez Crape Myrtle | 15'-20' | 12' Wide | L | White flowers |
| | | | | | | | | | <i>Lagerstroemia x fauriei</i> 'Muskogee' | Crape Myrtle | 20'-30' | 15'-20' | L | |
| | | | | | | | | | <i>Magnolia soulangiana</i> 'D.D. Blanchard' | Tulip Magnolia | 50' | 25'-35' | M | |
| | | | | | | | | | <i>Malus</i> | Flowering Crabapple, 'Snowdrift', 'Golden Raindrops' | 15'-20' | 15'-20' | M | |
| | | | | | | | | | <i>Olea europaea</i> 'Swan Hill' | Swan Hill Olive | 25'-30' | 25'-30' | VL | |
| | | | | | | | | | <i>Parkinsonia aculeata</i> | Mexican Palo Verde | 15'-20' | 10'-20' | VL | |
| | | | | | | | | | <i>Pinus pinea</i> | Stone Pine | | | L | |
| | | | | | | | | | <i>Pinus radiata</i> | Monterey Pine | 80'-100' | 25'-35' | M | |
| | | | | | | | | | <i>Pistacia chinensis</i> 'Pearl Street', 'Red Push' or 'Keith Davey' | Chinese Pistache Varieties | 30'-60' | 50' | L | |
| | | | | | | | | | <i>Platanus acerifolia</i> 'Bloodgood' | London Plane | 40'-50' | 25'-30' | M | |
| | | | | | | | | | <i>Platanus X acerifolia</i> 'Columbia' | | | | M | |
| | | | | | | | | | <i>Platanus racemosa</i> | California Sycamore | 50'-90' | 30'-50' | M | |
| | | | | | | | | | <i>Populus alba</i> 'Pyramidalis' | Seedless Bolleana Poplar | 50' | 15' | M | |
| | | | | | | | | | <i>Populus fremontii</i> | Fremont Cottonwood | 40'-60' | 30'-40' | M | |
| | | | | | | | | | <i>Populus nigra</i> 'Italica' | Lombardy Poplar | 100' | 15'-30' | M | |
| | | | | | | | | | <i>Prosopis glandulosa</i> 'Maverick' | Texas Mesquite | 25'-30' | 25'-30' | L | |
| | | | | | | | | | <i>Prunus caroliniana</i> 'Bright 'N Tight' (Compacta) | Bright 'N Tight Cherry Laurel | 8'-10' | 6'-8' | L | |

RIVER ISLANDS - PLANT SELECTION GUIDE

All plant materials shall be selected from the following plant list as approved by the City of Lathrop as part of this Architectural Design Guidelines & Development Standards document. Any exceptions must be recommended for approval by the STDR prior to installation. Basis for exceptions shall be limited to plant availability, where a similar available plant species may be substituted.

| Street | Median | Landscaping | Interior | Parks | Street Trees | Trails | Restoration Areas | Scientific Name | Common Name | Height 1 | Height 2 | Flower Color | Foliage Color |
|---------------------------|--------|-------------|----------|-------|--------------|--------|-------------------|--|------------------------|----------|----------|--------------|---|
| | | | | | | | | <i>Quercus cocinea</i> | Scarlet Oak | 60'-80' | 40'-60' | M | |
| | | | | | | | | <i>Quercus douglasii</i> | Blue Oak | 30'-50' | 40'-70' | VL | |
| | | | | | | | | <i>Quercus ilex</i> | Holly Oak | 40'-60' | 40'-60' | L | |
| | | | | | | | | <i>Quercus lobata</i> | Valley Oak | 50'-75' | 50'-80' | L | |
| | | | | | | | | <i>Quercus muehlenbergii</i> | Quinkpin Oak | | | ? | |
| | | | | | | | | <i>Quercus robur</i> | English Oak | 50'-60' | 30' | M | |
| | | | | | | | | <i>Quercus suber</i> | Cork Oak | 30'-60' | 30'-60' | L | |
| | | | | | | | | <i>Quercus virginiana</i> | Southern Live Oak | 40'-80' | 60'-90' | M | |
| | | | | | | | | <i>Quercus wislizenii</i> | Interior Live Oak | 30'-70' | 30'-70' | VL | |
| | | | | | | | | <i>Robinia 'Purple Robe'</i> | | | | L | |
| | | | | | | | | <i>Salix goodingii</i> | Gooding's Black Willow | 10'-25' | | H | |
| | | | | | | | | <i>Salix laevigata</i> | Red Willow | 15'-30' | | H | |
| | | | | | | | | <i>Salix lucida var. lasianдра</i> | Pacific Willow | | | H | |
| | | | | | | | | <i>Schinus molle</i> | California Pepper tree | 25'-40' | 25'-40' | L | |
| | | | | | | | | <i>Sophora japonica 'Regent'</i> | Pagoda Tree | 40' | 40'-60' | L | |
| | | | | | | | | <i>Syringa reticulata</i> | Japanese Tree Lilac | 30' | 20' | M | |
| | | | | | | | | <i>Tilia cordata 'Greenspire'</i> | Littleleaf Linden | 30'-50' | 15'-30' | M | |
| | | | | | | | | <i>Ulmus parvifolia 'Drake'</i> | Chinese Elm | 50'-70' | 30'-50' | M | |
| | | | | | | | | <i>Ulmus wilsoniana 'Frontier'</i> | | 20' | | M | |
| | | | | | | | | <i>Ulmus wilsoniana 'Patriot'</i> | | 30' | | L | |
| | | | | | | | | <i>Ulmus wilsoniana 'Emerald Sunshine'</i> | | | | L | |
| | | | | | | | | <i>Ulmus wilsoniana 'Prospector'</i> | | | | L | |
| | | | | | | | | <i>Umbellularia californica</i> | California Laurel | 20'-35' | 20'-35' | M | |
| | | | | | | | | <i>Vitex agnus-castus</i> | Chaste Tree | 15'-20' | 15'-20' | L | |
| | | | | | | | | <i>Zelkova serrata 'Green Vase'</i> | Zelkova, Green Vase | 50' | 50' | M | |
| Shrubs (Large Background) | | | | | | | | | | | | | |
| | | | | | | | | <i>Abelia grandiflora</i> | Glossy Abelia | 8' | 5' | M | |
| | | | | | | | | <i>Agave filifera</i> | | | | L | |
| | | | | | | | | <i>Alyogyne heugeli</i> | Blue Hibiscus | 6'-10' | 6'-8' | L | Light blue flowers |
| | | | | | | | | <i>Anisodonte x hypomandarum</i> | Cape Mallow | 4' | 4' | M | Purple/pink flowers |
| | | | | | | | | <i>Arbutus u. 'Oktoberfest'</i> | Strawberry Tree | 6'-8' | 6'-8' | L | Dark green foliage |
| | | | | | | | | <i>Arctostaphylos densiflora 'Howard McMinn'</i> | Howard McMinn | 5'-6' | 7' | L | |
| | | | | | | | | <i>Berberis thunbergii</i> | Japanese Barberry | 4'-6' | | L | |
| | | | | | | | | <i>Buddleja davidii</i> | Butterfly Bush | 6'-10' | 6'-10' | M | |
| | | | | | | | | <i>Carpenteria californica</i> | Bush Anemone | 3'-6' | | L | |
| | | | | | | | | <i>Cephalanthus occidentalis</i> | Button Willow | 3'-15' | 3'-15' | M | |
| | | | | | | | | <i>Cistus hybridus (Cistus corbariensis)</i> | White Rockrose | 2'-5' | 2'-4' | L | |
| | | | | | | | | <i>Cistus ladanifer (Cistus ladaniferus maculatus)</i> | Crimson-Spot Rockrose | 3'-5' | 3'-5' | L | |
| | | | | | | | | <i>Cistus x purpureus</i> | Orchid Roserock | 4' | 4' | M | Dark pink flowers |
| | | | | | | | | <i>Coprosma repens</i> | Mirror Plant | 10' | 6' | M | |
| | | | | | | | | <i>Cornus stolonifera (sericea) 'Bailey'</i> | Red-Twigged Dogwood | 6'-8' | 6'-8' | H | |
| | | | | | | | | <i>Cotinus coggygia (Rhus cotinus) 'Purpurea'</i> | Smoke Bush | 15' | 15' | L | |
| | | | | | | | | <i>Dodonaea viscosa 'Purpurea'</i> | Purple Hopseed Bush | 10' | 8'-10' | L | Red/burgundy foliage |
| | | | | | | | | <i>Elaeagnus pungens</i> | Silverberry | 6'-15' | | L | |
| | | | | | | | | <i>Eriogonum fasciculatum</i> | California Buckwheat | 1'-3' | 4' | L | |
| | | | | | | | | <i>Fremontodendron californicum</i> | California Flannelbush | | | VL | |
| | | | | | | | | <i>Grevillea x 'Noell'</i> | Noell Grevillea | 5' | 6' | L | Glossy lime green needle-like foliage with pink and white flowers |
| | | | | | | | | <i>Heteromeles arbutifolia</i> | Toyon | 6'-10' | | VL | |
| | | | | | | | | <i>Laurus nobilis</i> | Bay Laurel | 12'-40' | | L | |
| | | | | | | | | <i>Lavatera maritima</i> | Tree Mallow | 6' | 6' | L | Gray-Green foliage with light pink/purple flowers |
| | | | | | | | | <i>Lavatera thuringiaca 'Mrs Barnsley'</i> | Mallow | | | L | |
| | | | | | | | | <i>Leucophyllum frutescens 'Compactum'</i> | Texas Ranger | 4'-5' | 4'-5' | L | |
| | | | | | | | | <i>Lupinus arboreus</i> | Yellow Bush Lupine | 5'-8' | 5'-8' | L | |

RIVER ISLANDS- PLANT SELECTION GUIDE

All plant materials shall be selected from the following plant list as approved by the City of Lathrop as part of this Architectural Design Guidelines & Development Standards document. Any exceptions must be recommended for approval by the STDRC prior to installation. Basis for exceptions shall be limited to plant availability, where a similar available plant species may be substituted.

| Streetscape Between Wall and Walk | Streetscape Parkway Strips | Streetscape Medians | Streetscape Bio-Swale (Interior Lane Rd.) | Parks & Open Spaces | In-Tract Street Trees | In-Tract Parkway Strips | In-Tract Rear-Yard Lake Frontage | Levees, Trails and Restoration Areas | | | | | | | |
|---|----------------------------|---------------------|---|---------------------|-----------------------|-------------------------|----------------------------------|--------------------------------------|--|--|--------------------------------|---------|---------|---|---|
| | | | | | | | | | | Mahonia aquifolium | Oregon Grape | 6' | | M | |
| | | | | | | | | | | Myrtus communis | True Myrtle | 5'-6' | 4'-5' | L | |
| | | | | | | | | | | Nandina domestica | Heavenly Bamboo | 3'-8' | 2'-4' | L | |
| | | | | | | | | | | Nerium oleander 'Little Red' | Dwarf Red Oleander | 4' | 4' | L | Red flowers |
| | | | | | | | | | | Nerium oleander 'Petite Pink' | Dwarf Pink Oleander | 4' | 4' | L | Pink flowers |
| | | | | | | | | | | Osmanthus fragrans | Sweet Olive | 10' | 10'-12' | M | |
| | | | | | | | | | | Osmanthus x fortunei | Hybrid Tea Olive | 6'-20' | 10'-12' | M | |
| | | | | | | | | | | Philadelphus lewisii | Wild Mock-orange | 4'-10' | 6'-10' | M | |
| | | | | | | | | | | Philadelphus 'Belle Etoile' | Purple Spot Mock Orange | 5'-7' | 5'-7' | M | |
| | | | | | | | | | | Phormium tenax 'Atropurpureum' | New Zealand Flax | 4'-5' | 4'-5' | L | Burgundy-bronze bladed foliage |
| | | | | | | | | | | Phormium 'Yellow Wave' | Yellow Wave New Zealand Flax | 4'-5' | 4'-5' | M | Yellow and lime green bladed foliage |
| | | | | | | | | | | Prunus caroliniana 'Bright 'N Tight' (Compacta) | Bright 'N Tight Cherry Laurel | 8'-10' | 6'-8' | L | |
| | | | | | | | | | | Rhaphiolepis indica | India Hawthorn | 4'-5' | | L | |
| | | | | | | | | | | Rhaphiolepis indica 'Clara' | India Hawthorn | 3'-5' | 3'-5' | L | |
| | | | | | | | | | | Rhaphiolepis indica 'Springtime' | India Hawthorn | 4'-6' | | L | |
| | | | | | | | | | | Raphiolepis umbellata | Yeddo Hawthorn | 4'-6' | 4'-6' | L | |
| | | | | | | | | | | Rhamnus californica 'Mound San Bruno' | San Bruno Coffeberry | 3'-15' | 8' | L | |
| | | | | | | | | | | Rhamnus californica 'Eve Case' | Dwarf Coffeberry | 4'-8' | 4'-6' | L | |
| | | | | | | | | | | Rhamnus crocea | Redberry | | | L | |
| | | | | | | | | | | Rhamnus tomentella | Hoary Coffeberry | | | L | |
| | | | | | | | | | | Ribes aureum (var. gracillimum) | Golden Currant | 3'-6' | | L | |
| | | | | | | | | | | Ribes sanguineum | Pink Flowering Currant | 4'-12' | | M | |
| | | | | | | | | | | Rosa californica 'Plena' | California Wild Rose | | | L | |
| | | | | | | | | | | Teucrium fruticans | Bush Germander | 5'-6' | 5'-6' | L | Gray leaves, lavender flowers |
| | | | | | | | | | | Teucrium fruticans | Bush Germander | 4'-8' | 4'-10' | L | |
| | | | | | | | | | | Viburnum t. 'Spring Bouquet' | Spring Bouquet Viburnum | 4'-6' | 4'-6' | M | Deep green leathery foliage with tight clusters of pink buds and white flowers |
| | | | | | | | | | | Xylosma congestum | Shiny Xylosma | 8-10' | 8-10' | L | |
| Shrubs (Medium Foreground)(species appropriate within sight-line view corridor) | | | | | | | | | | | | | | | |
| | | | | | | | | | | Abelia x grandiflora 'Kaleidoscope' | Glossy Abelia | 2'-2.5' | 3'-4' | M | White flower |
| | | | | | | | | | | Berberis thunbergii 'Cruizum' | Crimson Ruby Japanese Barberry | 2' | 2' | M | Deep red/burgundy foliage |
| | | | | | | | | | | Callistemon citrinus 'Compacta' | Bottlebrush | | | L | |
| | | | | | | | | | | Callistemon citrinus 'Little John' or 'Captain Cook' | Dwarf Bottlebrush | 3' | 3' | L | |
| | | | | | | | | | | Coleonema pulchrum 'Varieties' | Pink Breath of Heaven | 3'-4' | 4' | M | Light green foliage with tiny pink flowers |
| | | | | | | | | | | Mahonia aquifolium 'Compacta' | | | | M | |
| | | | | | | | | | | Myrsine africana | African Boxwood | 3'-8' | 3'-6' | L | |
| | | | | | | | | | | Pittosporum t. 'Wheeler's Dwarf' | Mock Orange | 3'-4' | 4'-5' | M | White flower |
| | | | | | | | | | | Punica granatum 'Nana' | Dwarf Pomegranate | 3' | 5' | L | Orange flowers |
| | | | | | | | | | | Rhaphiolepis indica 'Ballerina' | Dwarf Pink Indian Hawthorne | 2' | 4' | L | Pink flowers |
| | | | | | | | | | | Salvia greggii / Salvia x jamensis | Autumn Sage | 3'-4' | 2' | L | |
| | | | | | | | | | | Salvia greggii 'Alba' | | 1'-4' | 1'-4' | L | |
| | | | | | | | | | | Salvia microphylla | Mint Bush Sage | 3'-5' | 4'-8' | M | |
| | | | | | | | | | | Spiraea bumalda | Spiraea | 2'-3' | 3'-4' | M | |
| | | | | | | | | | | Spiraea x bumalda 'Goldflame' | Goldflame Spirea | 3'-4' | 4' | M | Yellow-green foliage with pink/red flowers |
| | | | | | | | | | | Viburnum davidii | David Viburnum | 3' | 3' | M | Large glossy green deep veined foliage, tight clusters of pink buds and white flowers |
| | | | | | | | | | | Zauschneria californica | California Fuschia | 3' | 3'-4' | L | Gray leaves w/ red flowers |
| Shrubs (Accents)(species appropriate within sight-line view corridor) | | | | | | | | | | | | | | | |
| | | | | | | | | | | Achillea millefolium californica | Yarrow | 1-3' | 1-3' | L | |
| | | | | | | | | | | Achillea millefolium rosea 'Island Pink' | Pink Yarrow | 1'-3' | | L | |
| | | | | | | | | | | Achillea tomentosa | Woolly Yarrow | 6" | | L | |
| | | | | | | | | | | Agapanthus africanus | lily-of-the-Nile | 1.5'-2' | 1.5'-2' | M | Blue/white flower |

RIVER ISLANDS- PLANT SELECTION GUIDE

All plant materials shall be selected from the following plant list as approved by the City of Lathrop as part of this Architectural Design Guidelines & Development Standards document. Any exceptions must be recommended for approval by the STDRC prior to installation. Basis for exceptions shall be limited to plant availability, where a similar available plant species may be substituted.

| Streetscape Between Wall and Walk | Streetscape Parkway Strips | Streetscape Medians | Streetscape Bioswale (Interior Levee Rd.) | Parks & Open Spaces | In-Tract Street Trees | In-Tract Parkway Strips | In-Tract Rear-Yard Lake Frontage | Seeds, Foliage and Restoration Areas | Plant Species | Common Name | Height | Width | Flower Color | Notes |
|-----------------------------------|----------------------------|---------------------|---|---------------------|-----------------------|-------------------------|----------------------------------|--------------------------------------|---------------------------------------|------------------------------|----------|---------|--------------|---|
| | | | | | | | | | Aloe species | Blue Star Flower | varies | | L | |
| | | | | | | | | | Amsonia tabernaemontana | Serpentine Columbine | 2'-3' | | ? | |
| | | | | | | | | | Aquilegia eximia | Powis Castle Sagebrush | 2' | 1-3' | L | |
| | | | | | | | | | Artemisia 'Powis Castle' | Narrow-leaved Milkweed | 3' | 6' | L | |
| | | | | | | | | | Asclepias fascicularis | Plumbago | 1'-3' | 1' | ? | |
| | | | | | | | | | Ceratostigma plumbaginoides | Berkeley Sedge | 0.75'-1' | 1'-1.5' | M | Deep blue flower |
| | | | | | | | | | Carex divulsa | Fortnight Lily, Bicolor Iris | | | L | Deep green clumping evergreen grass |
| | | | | | | | | | Dietes bicolor | Fortnight Lily | | | L | |
| | | | | | | | | | Dietes vegeta | Santa Barbara Daisy | 3'-4' | 2'-3' | M | White flower |
| | | | | | | | | | Erigeron karvinskianus | California Poppy | 1'-2' | 3'-5' | L | White with some pink flowers |
| | | | | | | | | | Eschscholzia californica | Blue Bunch Grass | 1' | 1.5' | VL | |
| | | | | | | | | | Festuca idahoensis 'siskiyou blue' | Atlas Fescue | 14" | 10" | L | |
| | | | | | | | | | Festuca mairei | Elijah's Blue, Blue Festuca | 2'-3' | 2-3" | L | Evergreen clumping yellowish gray-green foliage |
| | | | | | | | | | Festuca ovina 'Glaucua' | Red Fescue | 4"-10" | 6" | M | |
| | | | | | | | | | Festuca rubra | Lenten Rose | 3"-12" | 6" | M | |
| | | | | | | | | | Helleborus x hybridus | Stella De Oro Dwarf Daylily | | | M | Heavy clusters of large yellow flowers |
| | | | | | | | | | Hemorrhallis x 'Stella de Oro' | Orange Daylily | 2' | 2' | M | Tawny orange |
| | | | | | | | | | Hemerocallis fulva | Coral Yucca | 2'-2.5' | 2'-2.5' | M | |
| | | | | | | | | | Hesperaloe parviflora | Lillian's Pink Coral Bells | 2' | 2' | / | |
| | | | | | | | | | Heuchera 'Lillian's Pink' | Rosada Coral Bells | | | ? | |
| | | | | | | | | | Heuchera 'Rosada' | Coral Bells | | | M | |
| | | | | | | | | | Heuchera sanguinea | Canyon Snow Pacific Iris | | | ? | |
| | | | | | | | | | Iris 'Canyon Snow' | CA Gray Rush | | 2' | H | |
| | | | | | | | | | Juncus patens | Red Hot Poker | 2' | 2' | M | |
| | | | | | | | | | Kniphofia uvaria | English Lavender | | 8'-2' | L | |
| | | | | | | | | | Lavandula angustifolia | English Lavender | 8'-2' | 8'-2' | L | Gray-green foliage with deep violet blue flowers |
| | | | | | | | | | Lavandula a. 'Buena Vista' | Goodwin Creek Lavender | 2' | 2' | L | |
| | | | | | | | | | Lavandula 'Goodwin Creek Grey' | Otto Quast Spanish Lavender | | | L | |
| | | | | | | | | | Lavandula stoechas 'Otto Quast' | Canyon Prince Wild Rye | 18"-3' | 2' | L | |
| | | | | | | | | | Leymus condensatus 'Canyon Prince' | Lily Turf | 2'-4' | 2' | VL | |
| | | | | | | | | | Liriope muscari | Dwarf Mat Rush | | | M | |
| | | | | | | | | | Lomandra l. 'Breeze' | Bush Lupine | 2'-3' | 2'-4' | L | |
| | | | | | | | | | Lupinus albifrons | Mexican Deergrass | 3'-5' | 2-3" | L | |
| | | | | | | | | | Miscanthus sinensis 'Morning Light' | Red Fountain Grass | 5'-6' | 3'-4" | M | |
| | | | | | | | | | Muhlenbergia dubia | Foothill Penstemon | 2'-3' | 2'-3" | L | |
| | | | | | | | | | Pennisetum setaceum 'Cupreum' | Showy Penstemon | 3'-4' | 3'-4" | L | |
| | | | | | | | | | Penstemon heterophyllus 'Margarita' | Russian Sage | 1'-3' | 1'-2' | L | Lavender flowers |
| | | | | | | | | | Penstemon species | Little Spire | | | M-L | |
| | | | | | | | | | Penstemon spectabilis | New Zealand Flax | 3' | 4' | L | Vertical spikey gray-green foliage with lavender-blue flowers |
| | | | | | | | | | Perovskia a. 'Little Spire' | New Zealand Flax | 2' | 2' | L | Yellow wit green margined bladed foliage |
| | | | | | | | | | Phormium tenax 'Apricot Queen' | New Zealand Flax | 3' | 4' | L | Reddish brown bladed foliage |
| | | | | | | | | | Phormium tenax 'Dusky Chief' | New Zealand Flax | 5'-6' | 4'-5' | L | |
| | | | | | | | | | Phormium tenax 'shirazz' | New Zealand Flax | | | L | |
| | | | | | | | | | Phormium tenax 'Tom Thumb' | New Zealand Flax | 1'-2' | 1'-2' | L | |
| | | | | | | | | | Salvia | Bee's Bliss Salvia | | | L-M | |
| | | | | | | | | | Salvia 'Bee's Bliss' | Hot Lips Sage | 1'-2' | 8' | M | |
| | | | | | | | | | Salvia m. 'Hot Lips' | Mrs. Beard Salvia | 3' | 3' | L | Red/white flowers |
| | | | | | | | | | Salvia 'Mrs. Beard' | Creeping Sage | 2' | 3 - 6' | L | |
| | | | | | | | | | Salvia sonomensis | Hummingbird Sage | | | L | |
| | | | | | | | | | Salvia spathacea | California Goldenrod | | | L | |
| | | | | | | | | | Solidago californica | California aster | 1-3' | 18"-3' | L | |
| | | | | | | | | | Symphotrichum chilense | Society Garlic | 1-3' | | L | Purple flowers |
| | | | | | | | | | Tulbaghia violacea | Variegated Society Garlic | 18" | 18" | L | Silver/white blades w/purple flowers |
| | | | | | | | | | Tulbaghia v. 'Silver lace' | Crater Lake Blue Speedwell | 18" | 12" | M | Gentian blue |
| | | | | | | | | | Veronica austriaca 'Crater Lake Blue' | | | | | |

RIVER ISLANDS- PLANT SELECTION GUIDE

All plant materials shall be selected from the following plant list as approved by the City of Lathrop as part of this Architectural Design Guidelines & Development Standards document. Any exceptions must be recommended for approval by the STDRC prior to installation. Basis for exceptions shall be limited to plant availability, where a similar available plant species may be substituted.

| Streetscape Between Wall and Walk | Streetscape Parkway Strips | Streetscape Medians | Streetscape Bio-Swale (Interior Levee Rd.) | Parks & Open Spaces | In-Tract Street Trees | In-Tract Parkway Strips | In-Tract Rear-yard Lake Frontage | Leves, Trails and Restoration Areas | | | | | | | |
|---|----------------------------|---------------------|--|---------------------|-----------------------|-------------------------|----------------------------------|-------------------------------------|--|--|------------------------------------|---------|---------|----|---|
| | | | | | | | | | | Zauschneria californica 'Catalina' | Island California Fuschia | 1-3' | 1-3' | L | |
| | | | | | | | | | | Zauschneria cana | California Fuschia | 2-3' | 18"-3' | L | |
| Shrubs (Grasses)(species appropriate within sight-line view corridor) | | | | | | | | | | | | | | | |
| | | | | | | | | | | Bouteloua gracilis | Blue Grama Grass | 6"-18" | 6"-1' | L | |
| | | | | | | | | | | Calamagrostis x acutiflora 'Karl Foerster' | Karl Foerster's Feather Reed Grass | 2' | 2' | L | Stunning vertical feathery plumes, turn golden in fall |
| | | | | | | | | | | Carex barbarae | White Root Sedge | 1'-3' | 1'-3' | M | Deep green native meadow grass |
| | | | | | | | | | | Carex divulsa | Berkeley Sedge | | | L | Deep green clumping evergreen grass |
| | | | | | | | | | | Carex pansa | California Meadow Sedge | 3'-4" | | M | |
| | | | | | | | | | | Carex praegracilis | Clustered-field Sedge | 1' | 6" | M | |
| | | | | | | | | | | Carex testacea | Orange Sedge | 18"-24" | 18"-24" | M | Evergreen, green and orange spring / summer, vibrant orange in winter |
| | | | | | | | | | | Deschampsia caespitosa | Tufted Hair Grass | 1'-3' | 1'-3' | L | |
| | | | | | | | | | | Deschampsia elongata | Slender Hair Grass | 3' | | L | |
| | | | | | | | | | | Eleocharis macrostachys | Spike Rush | 3' | 2' | L | |
| | | | | | | | | | | Elymus glaucus 'Anderson' | Blue Wild Rye | 2-3' | 2' | L | |
| | | | | | | | | | | Elymus triticoides | Creeping Wildrye | | | L | |
| | | | | | | | | | | Eschscholzia californica | California Poppy | 1' | 1.5' | VL | |
| | | | | | | | | | | Festuca californica | California Fescue | 2'-3' | 2-3' | M | |
| | | | | | | | | | | Festuca idahoensis'siskiyou blue' | Blue Bunch Grass | 14" | 10" | L | |
| | | | | | | | | | | Festuca mairei | Atlas Fescue | 2'-3' | 2-3' | L | Evergreen clumping yellowish gray-green foliage |
| | | | | | | | | | | Festuca occidentalis | | | | M | |
| | | | | | | | | | | Festuca ovina 'Glauca' | Elijah's Blue, Blue Festuca | 4"-10" | 6" | M | |
| | | | | | | | | | | Festuca rubra | Red Fescue | 3"-12" | 6" | M | |
| | | | | | | | | | | Grindelia camporum | Gum Plant | 1'-3' | 1'-3' | L | |
| | | | | | | | | | | Helictotrichon sempervirens | Blue Oat Grass | 2'-3' | | L | |
| | | | | | | | | | | Hordeum brachyantherum 'Californicum' | Meadow Barley | | | VL | |
| | | | | | | | | | | Imperata cylindrica 'Rubra' | Japanese Blood Grass | 1'-2' | | H | |
| | | | | | | | | | | Juncus balticus(balticus?) | Baltic Rush | 3' | | H | |
| | | | | | | | | | | Juncus effusus | Pacific Rush | 3'-6' | 3' | H | |
| | | | | | | | | | | Juncus patens | CA Gray Rush | 2' | 2' | H | |
| | | | | | | | | | | Leersia oryzoides | Rice Cutgrass | | | M | |
| | | | | | | | | | | Leymus condensatus 'Canyon Prince' | Canyon Prince Wild Rye | 2'-4' | 2' | VL | |
| | | | | | | | | | | Leymus triticoides 'Grey Dawn' | Creeping Wild Rye | 2' | 18" | VL | |
| | | | | | | | | | | Lomandra l. 'Breeze' | Dwarf Mat Rush | 2'-3' | 2'-4' | L | |
| | | | | | | | | | | Melica imperfecta | Coast Melic Grass, Oniongrass | 1'-2' | 1'-2' | VL | |
| | | | | | | | | | | Melica californica | Melica | 4' | | ? | |
| | | | | | | | | | | Miscanthus sinensis | Japanese Silver Grass | 5'-6' | 3'-4' | H | |
| | | | | | | | | | | Miscanthus sinensis 'Morning Light' | | 5'-6' | 3'-4' | H | |
| | | | | | | | | | | Muhlenbergia capillaris | Hairy Awn Muhly | 3' | 6' | L | |
| | | | | | | | | | | Muhlenbergia dubia | Mexican Deergrass | 2'-3' | 2'-3' | L | |
| | | | | | | | | | | Muhlenbergia rigens | Deer Grass | 3' | 3' | L | |
| | | | | | | | | | | Nasella pulchra 'Yolo' | Purple Needle Grass | 2' | 2'-3' | L | |
| | | | | | | | | | | Pennisetum alopecuroides 'Little Bunny' | Dwarf Fountain Grass | 18" | 18" | L | Trim to ground in winter |
| | | | | | | | | | | Pennisetum alopecuroides 'Moudry' | Black Fountain Grass | 18"-2' | 18"-2' | L | |
| | | | | | | | | | | Pennisetum orientale | Oriental Fountain Grass | 12"-18" | 12-18" | L | |
| | | | | | | | | | | Pennisetum setaceum 'Rubrum' | Red Fountain Grass | 3'-4' | 3'-4' | L | |
| | | | | | | | | | | Scirpus americanus | Three-square Bulrush | 5' | 5' | H | |
| | | | | | | | | | | Scirpus actus var. occidentalis | Hardstem Bulrush | 5'-8' | 5'-8' | H | |
| | | | | | | | | | | Scirpus californica | California Bulrush | 6"-10" | 6"-10" | H | |
| | | | | | | | | | | Scirpus microcarpus | Small-fruited Bulrush | 6"-10" | 6"-10" | H | |
| | | | | | | | | | | Sporobolus airoides | Alkali Sacaton | 1'-3' | 3' | VL | |
| | | | | | | | | | | Stipa cernua | Nodding Feather Grass | 2'-3' | 2'-3' | VL | |
| | | | | | | | | | | Stipa pulchra | Purple Needle Grass | 1'-2' | 1'-2' | L | |
| | | | | | | | | | | Stipa gigantea | Giant Feather Grass | 2'-3' | 2-3' | VL | |

RIVER ISLANDS- PLANT SELECTION GUIDE

All plant materials shall be selected from the following plant list as approved by the City of Lathrop as part of this Architectural Design Guidelines & Development Standards document. Any exceptions must be recommended for approval by the STDR prior to installation. Basis for exceptions shall be limited to plant availability, where a similar available plant species may be substituted.

| Streetscape Between Wall and Walk | Streetscape Parkway Strips | Streetscape Medians | Streetscape Bio-Swale (Interior Levee Rd.) | Parks & Open Spaces | In-Tract Street Trees | In-Tract Parkway Strips | In-Tract Rear-Yard Lake Frontage | Events, Trails and Recreation Areas | | | | | | |
|--|----------------------------|---------------------|--|---------------------|-----------------------|-------------------------|----------------------------------|-------------------------------------|---|----------------------------------|-----------|---------|----|---|
| | | | | | | | | | ETY Mix (Carex Divulsa, Eschscholzia californica, Festuca Idahoensis, Layia platyglossa, Salvia l. "Bee's Bliss", Sysynchium idahoensis) | Entry Mix | 1'-2' | 1-2' | L | |
| | | | | | | | | | Native Mow Free Mix (Festuca idahoensis, Festuca rubra, Festuca occidentalis) | No Mow Fescue | 12"-18" | | M | |
| Shrubs (Groundcovers)(species appropriate within sight-line view corridor) | | | | | | | | | | | | | | |
| | | | | | | | | | Acacia r. 'Desert Carpet' | Desert Carpet Acacia | 1'-2' | 10'-12' | L | Leathery gray green foliage with puffy yellow ball shaped flowers |
| | | | | | | | | | Ajuga species | Carpet Bugles | 1' | 3' | M | |
| | | | | | | | | | Arctostaphylos 'Pacific Mist' | | 2 1/2' | 4' | L | |
| | | | | | | | | | Artemisia californica 'Montara' | California Sagebrush | 18"-5' | | L | |
| | | | | | | | | | Artemesia 'Powis Castle' | Powis Castle Artemesia | 3' | 5' | M | gray green foliage |
| | | | | | | | | | Baccharis pilularis | Coyote Bush | | | L | |
| | | | | | | | | | Baccharis pilularis 'Pigeon Point' | Dwarf Coyote Brush | 6' | 6' | L | |
| | | | | | | | | | Ceanothus griseus horizontalis 'Yankee Point' | Shrub Ceanothus | 2'-3' | 8' | L | Blue flowers |
| | | | | | | | | | Ceanothus maritimus 'Valley Violet' | Valley Violet Maritime Lilac | | | L | |
| | | | | | | | | | Ceanothus thyrsiflorus 'Skylark' | Blueblossom | 3'-6' | 5' | L | |
| | | | | | | | | | Ceanothus 'Concha' | | | | L | |
| | | | | | | | | | Ceanothus 'Dark Star' | Dark Star California Lilac | 5'-6' | 8'-10' | L | |
| | | | | | | | | | Ceanothus 'Joyce Coulter' | Wild California Lilac | 3'-5' | 8'-10' | L | |
| | | | | | | | | | Ceanothus 'Ray Hartman' | Ray Hartman California | 12'-20' | 15'-20' | L | |
| | | | | | | | | | Cistus salvifolius | Sageleaf Rockrose | 2' | 6' | L | |
| | | | | | | | | | Coprosma kirkii | Kirk's Coprosma | 2-3' | | L | |
| | | | | | | | | | Cotoneaster dammeri 'Eichholz' | Bearberry Cotoneaster | 8" | 6'-8' | L | White flowers, red berries |
| | | | | | | | | | Cotoneaster lacteus (Cotoneaster parneyi) | | 8" | 10" | L | |
| | | | | | | | | | Cotoneaster microphyllus | Rockspray Cotoneaster | 2-3' | 6' | L | |
| | | | | | | | | | Erigeron 'Wayne Roderick' | Wayne Roderick Seaside Daisy | 8" | 1 1/2' | M | |
| | | | | | | | | | Erigeron karvinskianus | Santa Barbara Daisy | 10"-20" | 3' | L | |
| | | | | | | | | | Eschscholzia californica | California Poppy | 1' | 1.5' | VL | |
| | | | | | | | | | Hypericum calycinum | Aaron's Beard | 1' | | M | |
| | | | | | | | | | Hypericum moseranum | Gold Flower | 1' | | M | |
| | | | | | | | | | Lessingia filaginifolia var. californica 'Silver Carpet' | Silver Carpet California- Aster | | | M | |
| | | | | | | | | | Lobularia maritima | Sweet Alyssum | 2"-12" | 8"-12" | M | |
| | | | | | | | | | Lupinus microcarpus | Chick Lupine | 2 1/2' | | M | |
| | | | | | | | | | Myoporum parvifolium | Myoporum | 6" | 9" | L | |
| | | | | | | | | | Oenothera hookeri | Evening Primrose | 1'-3' | 1'-3' | L | |
| | | | | | | | | | Phacelia californica | Phacelia | 18" | | M | |
| | | | | | | | | | Potentilla verna | Spring Cinquefoil | 2'-3' | 3'-4' | M | |
| | | | | | | | | | Ribes viburnifolium | Evergreen Currant | 3'-6' | 12' | L | |
| | | | | | | | | | Rosa 'Noamel' | Apple Blossom Flower Carpet Rose | 2' | 3' | M | White/pink flowers |
| | | | | | | | | | Rosa 'Noare' | Red Flower Carpet Rose | 2' | 3' | M | Red flowers |
| | | | | | | | | | Rosa 'Noaschnee' | White Flower Carpet Rose | 2' | 3' | M | White flowers |
| | | | | | | | | | Rosa 'Noatraum' | Pink Flower Carpet | 2' | 3' | M | Pink flowers |
| | | | | | | | | | Rosmarinus o. 'Irene' | Rosemary | 1'-1 1/2' | 2'-3" | L | Blue flowers |
| | | | | | | | | | Rosmarinus o. Prostratus | Dwarf Rosemary | 2' | 4' | L | Blue flowers |
| | | | | | | | | | Sedum | Stone Crop | 2"-5" | 1' | L | |
| | | | | | | | | | Sisyrinchium bellum | Blue-eyed Grass | 4"-12" | 6"-24" | L | |
| | | | | | | | | | Trachelospermum asiaticum | Asian Jasmine | 2' | 10' | M | |
| | | | | | | | | | Trachelospermum jasminoides | Star Jasmine | 2' | 10' | M | |

RIVER ISLANDS- PLANT SELECTION GUIDE

All plant materials shall be selected from the following plant list as approved by the City of Lathrop as part of this Architectural Design Guidelines & Development Standards document. Any exceptions must be recommended for approval by the STDR prior to installation. Basis for exceptions shall be limited to plant availability, where a similar available plant species may be substituted.

| Streetscape Between Wall and Walk | Streetscape Parkway Strips | Streetscape Medians | Streetscape Bio-Swale (Interior Levee Rd.) | Parks & Open Spaces | In-Tract Street Trees | In-Tract Parkway Strips | In-Tract Rear-Yard Lake Frontage | Lawns, Trails and Restoration Areas | | | | | |
|-----------------------------------|----------------------------|---------------------|--|---------------------|-----------------------|-------------------------|----------------------------------|-------------------------------------|---|------------------------|---------|------|----|
| | | | | | | | | | ETY Mix (Carex Divulsa, Eschscholzia californica, Festuca Idahoensis, Layia platyglossa, Salvia I. "Bee's Bliss", Sysyrinchium idahoensis) | Entry Mix | 1'-2' | 1-2' | L |
| | | | | | | | | | Native Mow Free Mix (Festuca idahoensis, Festuca rubra, Festuca occidentalis) | No Mow Fescue | 12"-18" | | M |
| Vines | | | | | | | | | | | | | |
| | | | | | | | | | Aristolochia californica | California Pipevine | | | L |
| | | | | | | | | | Campsis radicans (Bignonia radicans) | Common Trumpet Creeper | | | L |
| | | | | | | | | | Clematis armandii 'Snow Drift' | Evergreen clematis | 15-20' | | M |
| | | | | | | | | | Clytostoma callistegioides | Violet Trumpet Vine | | | M |
| | | | | | | | | | Distictis buccinatoria | Trumpet Vine | 20'-30' | | M |
| | | | | | | | | | Ficus pumila | Creeping Fig | 10' | | M |
| | | | | | | | | | Gelsemium sempervirens | Carolina Jessamine | 20' | | L |
| | | | | | | | | | Hardenberdia violacea 'Happy Wanderer' | Hardenbergia Vine | 10' | | M |
| | | | | | | | | | Jasminum polyanthum | Pink Jasmine | 20' | | M |
| | | | | | | | | | Lonicera hispidula | Honeysuckle | 3-10' | | L |
| | | | | | | | | | Macfadyena unguis-cati | Cats Claw | 20-40' | | L |
| | | | | | | | | | Vitis californica | California Wild Grape | 12-30' | | VL |
| | | | | | | | | | Wisteria sinensis 'Alba' or 'Cooke's Special' | | | | M |