

**ADDENDUM NO. 1 - June 24, 2021**

**River Islands Parkway Widening Project – Phase 2  
CIP PS 06-06**

This addendum amends the Contract Drawings and Specifications for this project as follows:

1. Add to the Contract Specifications in Appendix “A” - Attachment 1 - CalRecycle Form 168 and cover sheet. This form must be filled out, signed and submitted with the Contractor’s bid.
2. The City will contract and pay for staking
3. Polypropylene is the approved material for the 18” storm drain. Do not use PVC
4. Coordination with Caltrans will be needed for work to be performed within their right-of-way including, but not limited to:
  - a. Ramp closures (Traffic Control Plans will be needed and approved by Caltrans)
  - b. Night work (seal coating, AC work on off ramps, signal mods, etc.)
5. Contractor will need to acquire a Provisional Encroachment Permit from Caltrans
6. Coordination with PG&E will be needed for replacement of the #7 vault lid
7. All ¾” HMA to conform to Caltrans Type A HMA
8. Increase microsealing area to approx. 70,000 SF. Refer to attachment (C)
9. Revisions made to install additional signing and striping. Refer to attachment (B) and the revised Bid Schedule below.
10. The Bid Schedule Table below has been revised to denote the correct units for the following:
  - a. Bid Item 9 revised from *SF* to **TON**
  - b. Bid Item 10 revised from *SF* to **TON**
  - c. Bid Item 11 revised from *SF* to **TON**
  - d. Bid Item 12 revised from *SF* to **TON**
  - e. Bid Item 16 revised from *LF* to **EA**
  - f. Bid Item 18 revised from *LF* to **SF**
  - g. Bid Item 19 revised from *LF* to **EA**
  - h. Bid Item 22 revised from *LF* to **EA**

**BID SCHEDULE – RIVER ISLANDS PARKWAY WIDENING PHASE 2, PS 06-06**

Bid Item	Description	Quantity	Units	Unit Price	Extended Price
9	7" A.C. pavement including seal coats and conforms	164	TON		
9A	Microsealing	70,000	SF		
10	16.5" Class II Aggregate Base	307	TON		
11	17.5" AB under curb and gutter	69	TON		
12	2" A.C. overlay including conforms	68	TON		
16	Relocate City Standard Catch Basin	1	EA		
18	Monolithic Sidewalk	1,489	SF		
19	Curb Ramp with detectable warning surface	1	EA		
22	Raise valve boxes to grade	1	EA		
29	6" Thermoplastic Traffic stripe	1,930	LF		
30	8" Thermoplastic Traffic stripe	1,280	LF		
31	12" Thermoplastic Stripe	295	LF		
32	Thermoplastic Pavement Arrows	14	EA		
33	Pavement Markers (Retroreflective blue, white and yellow)	130	EA		
34	Remove Thermoplastic Traffic Stripe and Pavement Markings	3,410	LF		
35	Pedestrian Barrier	3	EA		

11. Remove Bid Item 26 and replace with *Bid Alternative 1* to install new video detection camera and radar system (ITERIS). See below for description and attachment (A) for the revised Signal and Lighting plans

**BID ALTERNATE 1**

BID ITEM	DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	EXTENDED TOTAL
ALT 1 26 (A)	Remove signal modification of Southbound I-5 and River Islands Parkway and install video detection camera on SMA with riser. (ITERIS model vantage detector next hybrid video/radar system)	1	LS		

**TOTAL BID ALTERNATE 1: \$ \_\_\_\_\_**

**TOTAL BID ALTERNATE 1 IN WORDS: \_\_\_\_\_**

When submitting the bid for the project, the Contractor must acknowledge receipt of the addendum.

Recommended by: Ken Reed 6-24-2021  
Ken Reed  
Senior Construction Manager  
Date

Approved by: Michael King 6-24-2021  
Michael King, P.E.  
Public Works Director  
Date