



Public Works Department

390 Towne Centre Dr. – Lathrop, CA 95330

Phone (209) 941-7430 – fax (209) 941-7449

www.ci.lathrop.ca.us

ADDENDUM NO. 3 – August 28, 2023

**Louise Ave and McKinley Ave Intersection Improvements
CIP PS 15-02**

This addendum amends the Contract Drawings and Specifications for this project as follows:

1. Below is the revised Bid Schedule changing the quantity of Bid Item No. 16 to **157 LF**.

REVISED BID SCHEDULE

Bid Item	Description	Quantity	Units	Unit Price	Extended Price
1	Mobilization / Bonds / Insurance	1	LS		
2	Traffic Control	1	LS		
3	Erosion and Sediment Control Plan (ESCP)	1	LS		
4	Sawcut and remove Existing HMA	77,782	SF		
5	Adjust water valve covers and service box to finish grade	3	EA		
6	Relocate water service box	1	EA		
7	Install fire hydrant	1	EA		
8	Traffic Signal Modifications and Improvements at Louise/ McKinley Ave (Labor Only)	1	LS		
9	Construct PCC Curb Ramps	1	EA		
10	Construct PCC Curb / Gutter, City Std. Detail R-11	60	LF		
11	Construct PCC Sidewalk	365	SF		
12	Install storm drain manhole (City Standard Detail D-22)	2	EA		
13	Install new catch basin (Type "A")	1	EA		
13B	Install new catch basin (Type "B")	11	EA		
14	Install 15" Polypropylene storm lateral	38	LF		
15	Construct 6" retaining curb around catch basin 14	1	LS		
16	Install (6'x8') horizontal drain with 60" perforated HDPE	157	LF		

17	Install (5'x8') horizontal drain with 48" perforated HDPE	412	LF		
17B	Install (4'x10') horizontal drain with 30" perforated HDPE	206	LF		
18	Construct shallow swale 4" max depth	500	LF		
19	Place New HMA @ 9.5" Thick	5,900	TON		
19B	Aggregate Base	4,340	CY		
20	Place Microsurfacing	74,012	SF		
21	Place 10" aggregate base shoulder backing	1	LS		
22	Remove Existing Thermoplastic Markings and Striping	1	LS		
23	Thermoplastic Striping - Caltrans Std. Pln. A20, Detail 9	2,751	LF		
24	Thermoplastic Striping - Caltrans Std. Pln. A20, Detail 22	3,610	LF		
25	Thermoplastic Striping - Caltrans Std. Pln. A20, Detail 27B	4,245	LF		
26	Thermoplastic Striping - Caltrans Std. Pln. A20, Detail 32	880	LF		
27	Thermoplastic Striping - Caltrans Std. Pln. A20, Detail 38	835	LF		
28	Thermoplastic Striping - 12" White Line	885	LF		
29	Thermoplastic Marking - Type I Arrow (24')	3	EA		
30	Thermoplastic Marking - Type II (R) Arrow	6	EA		
31	Thermoplastic Marking - Type III (L) Arrow	5	EA		
32	Thermoplastic Marking - Type IV (L) Arrow	3	EA		
33	Thermoplastic Marking - Pavement Legend (Signal, Ahead, Stop)	8	EA		
34	Install Blue RPM @ fire hydrant	2	EA		
35	Install New Chain Link Fence	1,090	LF		
36	Relocate and Install new FH and ARV	3	EA		

When submitting the bid for the project, the Contractor must acknowledge receipt of the addendum.

Recommended by: Ken Reed
Ken Reed
Senior Construction Manager

8-28-23
Date

Approved by: Brad Taylor FOR
Brad Taylor
City Engineer

8-28-23
Date