

ADDENDUM NO. 1
March 31, 2025

LATHROP ELECTRIC VEHICLE CHARGING STATIONS
CIP GG 24-28

This addendum amends the Contract Drawings and Specifications for this project as follows:

1. Sheet G200 from the Improvement Plans has been superseded by the attached Sheet G200-A to show the additional trees to be removed.
2. Revise Bid Item List per Sheet 2 of this Addendum No. 1
3. Federal Wage Determination 10-Day Check:

General Decision Number: CA20250018 03/21/2025

Superseded General Decision Number: CA20240018

State: California

Copy of Wage Determination can be found at:

<https://sam.gov/wage-determination/CA20250018/6>

The following Requests for Information (RFI) have been received by the city, and are followed by the City's answer (A):

RFI 1: Can you please confirm the number of trees to be removed for the project?

A1: A total of (6) existing trees will be removed. Sheet G200-A supersedes G-200 and shows the location of the trees to be removed.

BID ITEM LIST

ITEM NO.	ITEM	UNIT OF MEASURE	ESTIMATED QUANTITY	UNIT PRICE (IN FIGURES)	ITEM TOTAL (IN FIGURES)
1	Mobilization, Bonds & Insurance	LS	1		
2	Traffic Control	LS	1		
3	Erosion & Sediment Control Plan (ESCP)	LS	1		
4	Construction Staking	LS	1		
5	Furnish and Install Bi-Facial 410W Panels	EA	100		
6	Furnish and Install PV Inverter	EA	1		
7	Furnish and Install PV BOS and DC	LS	1		
8	Furnish and Install AC Transformers	EA	2		
9	Furnish and Install AC Wires	LS	1		
10	Furnish and Install AC Switch of 600A, 3P, 280V/120Y (Panelboard)	EA	1		
11	Furnish and Install 600A, 3P Circuit Breaker	EA	1		
12	Furnish and Install AC Disco, 600A, 208V/120Y, 3P (Fused Disconnect Switch)	EA	1		
13	Furnish and Install AC Junction Box	EA	3		
14	Furnish and Install Battery BESS 30KW, 62 KWh, 208V/120Y, 3P	EA	1		
15	Furnish and Install Lighting Fixtures under Carport	EA	4		
16	Furnish and Install EV Chargers and Poles	EA	10		
17	Furnish and Install AC Balance of Solar	LS	1		
18	Furnish and Install AC load Monitoring Meters	EA	3		
19	Remove (ex) Trees	EA	6		
20	Install Landscape per Plans	LS	1		
21	Remove (ex) Parking Lot Street Lights	EA	3		
22	Long Trench (Bore)	LF	400		
23	Place Type II Microsurfacing	SF	8300		
24	Construct ADA Curb Ramp - Case C	EA	1		


25	Furnish and Install PV Steel Carport (Powershingle Canopy)	LS	1		
26	Provide Special Structural Inspections	LS	1		
27	Construct 36" Diameter Pole Foundation (15' deep) per Plans	EA	4		
28	Construct Pad for Switchgear, EV Chargers	EA	1		
29	Install New Signing and Striping	LS	1		


TOTAL BID:

Total Bid Amount In Words:

NOTE: "TOTAL BID" is only on the last page of the Bid Item List.

When submitting the bid for the project, the Contractor must acknowledge receipt of the addendum.

Recommended by:  _____ 03-27-2025
Angel Abarca
Project Engineer Date

Approved by:  _____ 3/28/2025
Brad Taylor, P.E.
City Engineer Date

