

**ADDENDUM NO. 1 – Nov. 25, 2025**

**Spartan Way Median Fence, CIP PS 26–20**

**Bids Due: December 2, 2025 by 2:00 PM**

This addendum amends the Contract Drawings and Specifications for this project as follows:

1. Revise Section 32 31 00 Fencing 2.02 G. accordingly:  
G. Finish: all fence members shall be primed and powder coated Black – Green, RAL 6012.
2. Revise Section 32 31 00 Fencing 3.02 C accordingly:
  1. Concrete Fill: Place 3,000 psi concrete around posts to dimensions indicated and vibrate or tamp for consolidation. Protect aboveground portion of posts from concrete splatter, and provide convex shaped finish to top of concrete pier to shed water away from post.
  2. Concrete Color: Add 4 lbs. of lamp black per cubic yard of concrete to match existing random slate pattern of median flatwork.

When submitting the bid for the project, the Contractor must acknowledge receipt of the addendum.

Recommended by:

  
Steven Hollenbeak  
Assistant Engineer

11.25.25  
Date

Approved by:

  
Brad Taylor, P.E.  
City Engineer

11/25/2025  
Date